# LabWindows®/CVI

## **User Interface Reference Manual**

July 1996 Edition

**Part Number 320683C-01** 

© Copyright 1994, 1996 National Instruments Corporation. All rights reserved.



#### **Internet Support**

GPIB: gpib.support@natinst.com
DAQ: daq.support@natinst.com
VXI: vxi.support@natinst.com
LabVIEW: lv.support@natinst.com
LabWindows: lw.support@natinst.com

HiQ: hiq.support@natinst.com

Lookout: lookout.support@natinst.com VISA: visa.support@natinst.com

FTP Site: ftp.natinst.com

Web Address: www.natinst.com



#### **Bulletin Board Support**

BBS United States: (512) 794-5422 or (800) 327-3077

BBS United Kingdom: 01635 551422

BBS France: 1 48 65 15 59



### **FaxBack Support**

(512) 418-1111



#### **Telephone Support (U.S.)**

Tel: (512) 795-8248 Fax: (512) 794-5678



### **International Offices**

Australia 03 9 879 9422, Austria 0662 45 79 90 0, Belgium 02 757 00 20, Canada (Ontario) 519 622 9310, Canada (Québec) 514 694 8521, Denmark 45 76 26 00, Finland 90 527 2321, France 1 48 14 24 24, Germany 089 741 31 30, Hong Kong 2645 3186, Italy 02 413091, Japan 03 5472 2970, Korea 02 596 7456, Mexico 95 800 010 0793, Netherlands 0348 433466, Norway 32 84 84 00, Singapore 2265886, Spain 91 640 0085, Sweden 08 730 49 70, Switzerland 056 200 51 51, Taiwan 02 377 1200, U.K. 01635 523545

### **National Instruments Corporate Headquarters**

6504 Bridge Point Parkway

Austin, TX 78730-5039 Tel: (512) 794-0100

## Warranty

The media on which you receive National Instruments software are warranted not to fail to execute programming instructions, due to defects in materials and workmanship, for a period of 90 days from date of shipment, as evidenced by receipts or other documentation. National Instruments will, at its option, repair or replace software media that do not execute programming instructions if National Instruments receives notice of such defects during the warranty period. National Instruments does not warrant that the operation of the software shall be uninterrupted or error free.

A Return Material Authorization (RMA) number must be obtained from the factory and clearly marked on the outside of the package before any equipment will be accepted for warranty work. National Instruments will pay the shipping costs of returning to the owner parts which are covered by warranty.

National Instruments believes that the information in this manual is accurate. The document has been carefully reviewed for technical accuracy. In the event that technical or typographical errors exist, National Instruments reserves the right to make changes to subsequent editions of this document without prior notice to holders of this edition. The reader should consult National Instruments if errors are suspected. In no event shall National Instruments be liable for any damages arising out of or related to this document or the information contained in it.

EXCEPT AS SPECIFIED HEREIN, NATIONAL INSTRUMENTS MAKES NO WARRANTIES, EXPRESS OR IMPLIED, AND SPECIFICALLY DISCLAIMS ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. CUSTOMER'S RIGHT TO RECOVER DAMAGES CAUSED BY FAULT OR NEGLIGENCE ON THE PART OF NATIONAL INSTRUMENTS SHALL BE LIMITED TO THE AMOUNT THERETOFORE PAID BY THE CUSTOMER. NATIONAL INSTRUMENTS WILL NOT BE LIABLE FOR DAMAGES RESULTING FROM LOSS OF DATA, PROFITS, USE OF PRODUCTS, OR INCIDENTAL OR CONSEQUENTIAL DAMAGES, EVEN IF ADVISED OF THE POSSIBILITY THEREOF. This limitation of the liability of National Instruments will apply regardless of the form of action, whether in contract or tort, including negligence. Any action against National Instruments must be brought within one year after the cause of action accrues. National Instruments shall not be liable for any delay in performance due to causes beyond its reasonable control. The warranty provided herein does not cover damages, defects, malfunctions, or service failures caused by owner's failure to follow the National Instruments installation, operation, or maintenance instructions; owner's modification of the product; owner's abuse, misuse, or negligent acts; and power failure or surges, fire, flood, accident, actions of third parties, or other events outside reasonable control.

## Copyright

Under the copyright laws, this publication may not be reproduced or transmitted in any form, electronic or mechanical, including photocopying, recording, storing in an information retrieval system, or translating, in whole or in part, without the prior written consent of National Instruments Corporation.

### **Trademarks**

Product and company names listed are trademarks or trade names of their respective companies.

## WARNING REGARDING MEDICAL AND CLINICAL USE OF NATIONAL INSTRUMENTS PRODUCTS

National Instruments products are not designed with components and testing intended to ensure a level of reliability suitable for use in treatment and diagnosis of humans. Applications of National Instruments products involving medical or clinical treatment can create a potential for accidental injury caused by product failure, or by errors on the part of the user or application designer. Any use or application of National Instruments products for or involving medical or clinical treatment must be performed by properly trained and qualified medical personnel, and all traditional medical safeguards, equipment, and procedures that are appropriate in the particular situation to prevent serious injury or death should always continue to be used when National Instruments products are being used. National Instruments products are NOT intended to be a substitute for any form of established process, procedure, or equipment used to monitor or safeguard human health and safety in medical or clinical treatment.

# **Contents**

About This Manual	xix
Organization of This Manual	xix
Conventions Used in This Manual	XX
Customer Communication	xxi
Chapter 1	
User Interface Concepts	1-1
Introduction to the Graphical User Interface	
User Interface Events	
Controlling Your User Interface Using Callbacks or G	
Source Code Connection	
Control Modes for Generating Commit Events	
Using CodeBuilder to Create Source Code for Your G	
Operating a Graphical User Interface	
Using Panels	
Using Menu Bars	1-6
Using Controls	1-7
Data Types of Controls	1-8
Numeric Controls	1-8
String Controls	1-9
Text Messages	1-10
Text Box Controls	1-10
Command Button Controls	1-11
Toggle Button Controls	1-11
LED Controls	1-12
Binary Switch Controls	1-12
Ring Controls	1-13
List Box Controls	1-14
Decorations	1-16
Graph Controls	1-16
Zooming and Panning on Graphs	
Strip Chart Controls	1-20
Picture Controls	
Timer Controls	
Canvas Controls	
Using Pop-Up Panels	
Operating the Message Pop-Up Panel	
Operating the Generic Message Pop-Up Panel	
Operating the Prompt Pop-Up Panel	
Operating the Confirm Pop-Up Panel	1-23

Operating the File Select Pop-Up Panel	1-23
Operating Graph Pop-Up Panels	1-24
Using Fonts	
Metafonts That Use Typefaces Native To Each Platform	
Fonts That Use Typefaces Native To Each Platform	
Metafonts That Use Typefaces Installed by LabWindows/CVI	
Chapter 2	
User Interface Editor Reference	2-1
User Interface Editor Overview	
Using the User Interface Editor Popup Menus:	
Code Builder Overview	
User Interface Editor Menus	
File Menu	
New, Open, Save, and Exit LabWindows/CVI Commands	
Save As and Close Commands	
Save Copy As	
Save All	
Add File to Project	
Read Only	
Print	
Edit Menu	
Undo and Redo	
Cut and Copy	
Paste	
Delete	
Copy Panel and Cut Panel	
Menu Bars	
Panel	
Control	2-11
Tab Order	
Set Default Font	2-15
Apply Default Font	2-15
Control Style	
Create Menu	
Panel	2-16
Menu Bar	
Controls	2-16
View Menu	2-17
Find UIR Objects	2-17
Show/Hide Panels	2-19
Preview User Interface Header File	2-19
Arrange Menu	2-20
Alignment	
Align Horizontal Centers	
Distribution	2-21

Distribute Vertical Centers	2-22
Control ZPlane Order	2-22
Center Label	2-22
Control Coordinates	2-23
The Code Menu	2-23
Set Target File	2-23
Generate	
All Code	2-25
Main Function	2-26
All Callbacks	2-27
Panel Callback	2-28
Control Callbacks	2-28
Menu Callbacks	2-28
View	2-28
Preferences	2-29
Default Panel Events and Default Control Events	2-30
Always Append Code to End	2-30
Run Menu	2-30
Library Menu	2-30
Window Menu	2-31
Options Menu	2-31
Operate Visible Panels	2-31
Next Tool	2-31
Preferences	2-32
Undo Preferences	2-32
Color Preferences	2-32
Constant Name Assignment	2-32
Assign Missing Constants	2-33
Save In Text Format	2-33
Load From Text Format	2-34
Chapter 3 Programming with the User Interfere Library	2.1
Programming with the User Interface Library	
Developing and Running a Program	
Creating a Graphical User Interface	
If you design your GUI programmatically	
If you design your GUI programmatically	
Assigning Constant Names in the User Interface Editor  Controlling a Graphical User Interface	
User Interface Events	
Using Cathleag Functions to Respond to User Interface Events	
Using GetUserEvent to Respond to User Interface Events	
Programming with Panels	
Panel Functions	
Role of Child Panels	3-11

Processing Panel Events	. 3-11
Panel Attributes	. 3-11
Panel Attribute Discussion	. 3-17
Platform Independent Fonts That Are Resident on PCs and UNIX	3-20
Platform-Independent Metafonts That Are Resident on PCs and U	NIX
	. 3-20
Metafonts Supplied by LabWindows/CVI	. 3-21
Host Fonts	
User Defined Metafont	. 3-21
Programming with Menu Bars	. 3-21
Menu Bar Functions	. 3-21
Processing Menu Bar Events	. 3-22
Using Callback Functions	. 3-22
Using an Event Loop	. 3-23
Menu Bar Attributes	
Menu Bar Attribute Discussion	. 3-26
Programming with Controls	. 3-28
Control Functions for All Controls	. 3-28
Control Functions for List Controls (List Boxes and Rings)	. 3-29
List Boxes and Rings	
List Boxes only	
Control Functions for Text Boxes	. 3-30
Processing Control Events	. 3-31
Using Callback Functions	
Using an Event Loop	. 3-31
Control Attributes	. 3-32
Control Attribute Discussion	. 3-46
Programming with Picture Controls	3-51
Simple Picture Control	. 3-52
Picture Control Attributes	. 3-52
Appearance of Picture Controls	. 3-53
Giving Picture Controls More Visual Impact	. 3-53
Programming with Canvas Controls	. 3-53
Functions for Drawing on Canvas	
Batch Drawing	. 3-54
Canvas Coordinate System	. 3-54
Offscreen Bitmap	. 3-55
Clipping	. 3-55
Background Color	. 3-55
Pens	. 3-55
Pixel Values	. 3-56
Canvas Attribute Discussion	. 3-56
Using Rect and Point Structures	. 3-59
Functions and Macros for Making Rects and Points	. 3-59
Functions for Modifying Rects and Points	3-60
Functions for Comparing or Obtaining Values from Rects and Points	. 3-61

Using Bitmap Objects	3-61
Functions for Creating, Extracting, or Discarding Bitmap Objects	3-62
Windows Metafiles	
Functions for Displaying or Copying Bitmap Objects	3-63
Functions for Retrieving Image Data from Bitmap Objects	
Programming with Timer Controls	
Timer Control Functions	
Using Timer Callbacks	3-64
Timer Control Attributes	3-64
Timer Control Attribute Discussion	3-65
Details of Timer Control Operations	3-65
Programming with Graph and Strip Chart Controls	
Functions for Graphs and Strip Charts	
Functions for Graphs Only	
Functions for Strip Charts Only	
Processing Graph and Strip Chart Events	
Graph and Strip Chart Attributes	
Graph Attribute Discussion	
Plot Origin Discussion	
Two Y Axis (graphs only)	
Optimizing Graph Controls	
Optimizing Speed	
Speed and ATTR_SMOOTH_UPDATE	
Speed and VAL_AUTO_SCALE	
Controlling How Graphs Refresh	
Optimizing Memory Usage	
Programming with Pop-Up Panels	
Using the System Attributes	
Unsafe Timer Events	
Reporting Load Failures	
Suppressing Event Processing	
Generating Hard Copy Output	
Functions for Hard Copy Output	
Hard Copy Attributes	
Hard Copy Attribute Discussion	
Special User Interface Functions	
RunUserInterface	
Precedence of Callback Functions	
Swallowing Events	
GetUserEvent	
InstallMainCallback and SetIdleEventRate	
ProcessDrawEvents	
ProcessSystemEvents	
PostDeferredCall	
QueueUserEvent	
FakeKeystroke	

QuitUserInterface	3-94
Chapter 4	
User Interface Library Reference	4-1
User Interface Library Overview	
User Interface Function Panels	
Hard Copy Output	
Compatible Printers	
Obtaining Hard Copy Output	
Configuring Your System for Hard Copy Output	
RGB Color Values	
Fonts	
Shortcut Keys	
Plot Array Data Types	
Include Files	
Reporting Errors	
User Interface Library Function Reference	
AllocBitmapData	
AllocImageBits	
CanvasClear	
CanvasDefaultPen	
CanvasDimRect	4-17
CanvasDrawArc	4-18
CanvasDrawBitmap	4-20
CanvasDrawLine	
CanvasDrawLineTo	4-23
CanvasDrawOval	4-23
CanvasDrawPoint	4-25
CanvasDrawPoly	4-26
CanvasDrawRect	4-27
CanvasDrawRoundedRect	4-28
CanvasDrawText	4-29
CanvasDrawTextAtPoint	4-31
CanvasEndBatchDraw	4-33
CanvasGetClipRect	4-34
CanvasGetPenPosition	4-35
CanvasGetPixel	4-36
CanvasGetPixels	4-37
CanvasInvertRect	4-38
CanvasScroll	
CanvasSetClipRect	
CanvasSetPenPosition	
CanvasStartBatchDraw	
CanvasUpdate	
CheckListItem	
ClearAxisItems	4-45

ClearListCtrl	4-46
ClearStripChart	4-46
ClipboardGetBitmap	4-47
ClipboardGetText	4-48
ClipboardPutBitmap	4-48
ClipboardPutText	
ConfigurePrinter	
ConfirmPopup	4-50
CreateMetaFont	
DefaultCtrl	
DefaultPanel	
DeleteAxisItem	4-54
DeleteGraphPlot	4-55
DeleteImage	
DeleteListItem	
DeleteTextBoxLine	4-58
DirSelectPopup	
DiscardBitmap	
DiscardCtrl	
DiscardMenu	
DiscardMenuBar	
DiscardMenuItem	
DiscardPanel	
DiscardSubMenu	
DisplayImageFile	4-64
DisplayPCXFile	
DisplayPanel	
DOSColorToRGB	4-66
DOSCompatWindow	4-67
DuplicateCtrl	4-68
DuplicatePanel	
EmptyMenu	
EmptyMenuBar	4-70
FakeKeystroke	4-71
FileSelectPopup	
FontSelectPopup	4-73
GenericMessagePopup	
Get3dBorderColors	
GetActiveCtrl	4-79
GetActiveGraphCursor	
GetActivePanel	
GetAxisItem	
GetAxisItemLabelLength	
GetAxisRange	
GetAxisScalingMode	
GetBitmapData	

GetBitmapFromFile	. 4-88
GetBitmapInfo	. 4-89
GetCtrlAttribute	. 4-90
GetCtrlBitmap	
GetCtrlBoundingRect	. 4-92
GetCtrlDisplayBitmap	. 4-93
GetCtrlIndex	. 4-94
GetCtrlVal	. 4-95
GetCursorAttribute	. 4-96
GetCVITaskHandle	. 4-97
GetCVIWindowHandle	. 4-97
GetGlobalMouseState	. 4-98
GetGraphCursor	. 4-99
GetGraphCursorIndex	. 4-100
GetImageBits	. 4-101
GetImageInfo	. 4-104
GetIndexFromValue	. 4-105
GetLabelFromIndex	. 4-106
GetLabelLengthFromIndex	. 4-106
GetListItemImage	. 4-107
GetMenuBarAttribute	. 4-108
GetMouseCursor	. 4-109
GetNumAxisItems	. 4-109
GetNumCheckedItems	. 4-111
GetNumListItems	. 4-111
GetNumTextBoxLines	. 4-112
GetPanelAttribute	. 4-113
GetPanelDisplayBitmap	. 4-113
GetPanelMenuBar	. 4-115
GetPlotAttribute	. 4-115
GetPrintAttribute	. 4-116
GetRelativeMouseState	. 4-117
GetScreenSize	. 4-118
GetSharedMenuBarEventPanel	. 4-118
GetSleepPolicy	. 4-119
GetSystemAttribute	
GetSystemPopupsAttribute	. 4-120
GetTextBoxLine	. 4-120
GetTextBoxLineLength	. 4-121
GetTextDisplaySize	. 4-122
GetTraceAttribute	. 4-122
GetUILErrorString	. 4-123
GetUserEvent	. 4-124
GetValueFromIndex	. 4-125
GetValueLengthFromIndex	. 4-125
GetWaitCursorState	.4-126

HidePanel	4-127
InsertAxisItem	4-127
InsertListItem	4-129
InsertSeparator	4-131
InsertTextBoxLine	4-131
InstallCtrlCallback	4-132
InstallMainCallback	4-134
InstallMenuCallback	4-135
InstallMenuDimmerCallback	4-136
InstallPanelCallback	4-137
InstallPopup	4-138
IsListItemChecked	4-139
LoadMenuBar	4-139
LoadMenuBarEx	4-141
LoadPanel	4-142
LoadPanelEx	4-144
MakeColor	4-145
MakePoint	4-147
MakeRect	4-147
MessagePopup	4-148
MultiFileSelectPopup	4-149
NewBitmap	4-150
NewCtrl	4-152
NewMenu	4-153
NewMenuBar	4-154
NewMenuItem	4-155
NewPanel	4-157
NewSubMenu	4-159
PlotArc	4-159
PlotBitmap	4-161
PlotIntensity	4-162
PlotLine	4-165
PlotOval	4-166
PlotPoint	4-167
PlotPolygon	4-168
PlotRectangle	4-170
PlotScaledIntensity	4-172
PlotStripChart	4-175
PlotStripChartPoint	4-177
PlotText	4-178
PlotWaveform	4-180
PlotX	4-182
PlotXY	4-183
PlotY	4-184
PointEqual	4-186
PointPinnedToRect	4-187

PointSet	4-187
PostDeferredCall	4-188
PrintCtrl	4-189
PrintPanel	4-190
PrintTextBuffer	4-192
PrintTextFile	4-193
ProcessDrawEvents	4-194
ProcessSystemEvents	4-194
PromptPopup	4-195
QueueUserEvent	4-196
QuitUserInterface	4-196
RecallPanelState	4-197
RectBottom	4-198
RectCenter	4-198
RectContainsPoint	4-199
RectContainsRect	4-200
RectEmpty	4-200
RectEqual	4-201
RectGrow	4-201
RectIntersection	4-202
RectMove	4-203
RectOffset	4-203
RectRight	4-204
RectSameSize	
RectSet	4-205
RectSetBottom	4-206
RectSetCenter	4-206
RectSetFromPoints	4-207
RectSetRight	4-208
RectUnion	4-208
RefreshGraph	4-209
RegisterWinMsgCallback	4-209
RemovePopup	4-211
ReplaceAxisItem	4-212
ReplaceListItem	
ReplaceTextBoxLine	
ResetTextBox	4-214
ResetTimer	4-215
ResumeTimerCallbacks	4-216
RunPopupMenu	. 4-216
RunUserInterface	4-218
SavePanelState	
SetActiveCtrl	4-220
SetActiveGraphCursor	4-220
SetActivePanel	
SetAxisScalingMode	4-222

SetAxisRange	4-223
SetCtrlAttribute	4-225
SetCtrlBitmap	4-226
SetCtrlIndex	4-228
SetCtrlVal	4-228
SetCursorAttribute	4-229
SetFontPopupDefaults	4-230
SetGraphCursor	4-232
SetGraphCursorIndex	4-233
SetIdleEventRate	4-234
SetImageBits	
SetInputMode	
SetListItemImage	
SetMenuBarAttribute	
SetMouseCursor	
SetPanelAttribute	
SetPanelMenuBar	
SetPanelPos	
SetPlotAttribute	
SetPrintAttribute	
SetSleepPolicy	
SetSystemAttribute	
SetSystemPopupsAttribute	
SetTraceAttribute	
SetWaitCursor	
SuspendTimerCallbacks	
UnRegisterWinMsgCallback	
ValidatePanel	
WaveformGraphPopup	
XGraphPopup	
XYGraphPopup	
YGraphPopup	4-252
Chapter 5	
<del>-</del>	<i>E</i> 1
LabWindows/CVI Sample Programs	
Example Program Files	
Using the Sample Programs	
1. io.prj—Standard I/O	
2. callback.prj—Introduction to Callback Functions	
3. events.prj—User Interface Events	
4. menus.prj—Menus Controlled by Callback Functions	
5. graphs.prj—Graphs	
6. chart.prj—Strip Charts	
7. cursors.prj—Graph Cursors	
8. popups.prj—Pop-Up Panels	5-3

	9. listbox.prj—Selection Lists	5-4
	10. panels.prj—Child Windows	5-4
	11. timerctl.prj—Timer Controls	5-4
	12. textbox.prj—Text Boxes	5-4
	13. picture.prj—Using Picture Controls	5-4
	14. build.prj—Building a User Interface Programmatically	5-4
	15. getusrev.prj—Programming with Event Loops	5-4
	16. keyfiltr.prj—Handling Keyboard Input	
	17. moustate.prj—Getting the Mouse State	
	18. listdelx.prj—Colors in List Boxes	
	19. 2yaxis.prj - Two Y Axes on a Graph	5-5
	20. intgraph.prj - Intensity Plots	
	21. autostrp.prj - Autoscaling the Y-Axis on a Strip Chart	
	22. canvas.prj - Canvas Controls	5-6
	23. canvsbmk.prj - Canvas Benchmark	5-6
	24. drawpad.prj - Using Canvas as Drawing Pad	5-6
	25. piedemo.prj - Pie Chart	5-6
	26. imagedit.prj - Changing Image Colors	
	27. clipbord.prj - Using System Clipboard	5-6
Appendix B Customer Commi	ınicationG	B-1
•		•
		1114071 1
	Figures	
Figure 1-1. A Typical	LabWindows/CVI Graphical User Interface	1-1
Figure 1-2. The Out (	Of Range Dialog Box	1-4
Figure 1-3. A Child P	anel Within a Parent Panel	1-5
Figure 1-4. A Menu F	Bar and Pull-Down Menu	1-6
Figure 1-5. A Pull-Do	own Menu with a Sub-Menu	1-0 1 Q
Figure 1-0. Numeric (	Control	1-0
Figure 1-8. A Text M	essage	1 ) 1-1(
Figure 1-9. A Text Bo	ox Control	1-10
Figure 1-10. The Con	nmand Button Controls	1-11
Figure 1-11. The Tog	gle Button Controls	1-11
	O Controlsary Switch Controls	
riguie 1-13. The bills	ary Switch Cultudis	1-12 1-12
Higure I-14. Ring Co	ntrols	

Figure 1-15. A Ring Control in Pop-Up Format	1-13
Figure 1-16. A Selection List Control in Check Mode	
Figure 1-17. GUI Decorations	1-16
Figure 1-18. A Graph Control	1-16
Figure 1-19. A Strip Chart Control	
Figure 1-20. The Timer Control	
Figure 1-21. A Message Pop-Up Panel	1-22
Figure 1-22. A Generic Message Pop-Up Panel	
Figure 1-23. A Prompt Pop-Up Panel	1-22
Figure 1-24. A Confirm Pop-Up Panel	
Figure 1-25. A File Select Pop-Up Panel under Windows 3.1	1-23
Figure 1-26. A File Select Pop-Up Panel under Windows 95	
Figure 1-27. A Graph Pop-Up Panel	1_24
Tiguic 1-27. A Graphi Top-Op I alici	1-4
Figure 2-1. A User Interface Editor Window	2_1
Figure 2-2. The File Menu	
Figure 2-3. The Edit Menu	
Figure 2-4. The Menu Bar List Dialog Box	2-7
Figure 2-5. The Edit Menu Bar Dialog Box	2-8
Figure 2-6. Source Code Connection	
Figure 2-7. Panel Attributes	
Figure 2-8. Quick Edit Window	
Figure 2-9. Source Code Connection	
Figure 2-10. Control Settings for a Numeric Control	
Figure 2-11. The Edit Label/Value Pairs Dialog Box	
Figure 2-12. Control Appearance for a Numeric Control	2-13
Figure 2-13. Label Appearance for a Numeric Control	
Figure 2-14. Quick Edit Window	2-14
Figure 2-15. The Edit Tab Order Dialog Box	2-15
Figure 2-16. The Create Menu	
Figure 2-17. The View Menu	2-17
Figure 2-18. Find UIR Objects Dialog Box	2-17
Figure 2-19. Find UIR Objects Dialog Box After a Search Executes	2-18
Figure 2-20. The Show/Hide Panel Sub-Menu	
Figure 2-21. The Arrange Menu	
Figure 2-22. The Alignment Menu	
Figure 2-23. The Distribution Submenu	
Figure 2-24. The Code Menu	2-23
Figure 2-25. The Set Target File Dialog Box	2-23
Figure 2-26. The Generate Menu	2-24
Figure 2-27. The Generate Code Dialog Box	2-24
Figure 2-28. The Generate All Code Dialog Box	2-25
Figure 2-29. The Generate Main Function Dialog Box	2-26
Figure 2-30. The View Menu	2-20
Figure 2-31. The Preferences Menu	2-22
Figure 2.32. The Options Many	2-47
Figure 2-32. The Options Menu	2-21
rigure 2-33. The Oser interface Preferences Dialog Dox	<b>2-3</b> 2
Figure 2.1. The Callbook Francian Concert	2 5
Figure 3-1. The Callback Function Concept	3-3 2 0
Figure 3-2. The Event Loop Concept	3-8
Figure 3-3. The Geometric Attributes of a Panel	3-18

## **Tables**

Table 1-1. Keys For Selecting Cursors	1-17
Table 1-2. Image Formats	
Table 3-1. User Interface Events	
Table 3-2. Panel Attributes	
Table 3-3. Common Color Values	
Table 3-4. Values and Cursor Styles for ATTR_MOUSE_CURSOR	
Table 3-5. Font Values	
Table 3-6. Menu and Menu Item Attributes	
Table 3-7. Key Modifiers and Virtual Keys	
Table 3-8. Constants for Masking Three Bit Fields in GetMenuBarAttribute	
Table 3-9. Control Attributes	3-32
Table 3-10. Control Styles for ATTR_CTRL_STYLE	3-46
Table 3-11. Control Data Types for the ATTR_DATA_TYPE attribute	3-50
Table 3-12. Numeric Formats	3-51
Table 3-13. ATTR_CHECK_RANGE Values	
Table 3-14. Control Attributes for Canvas Controls	3-56
Table 3-15. Values for ATTR_DRAW_POLICY	3-57
Table 3-16. Values for ATTR_OVERLAPPED_POLICY	3-58
Table 3-17. Values for ATTR_PEN_MODE	3-58
Table 3-18. Values and Macros for Rect Structures	
Table 3-19. Timer Control Attributes	
Table 3-20. Graph and Strip Chart Attributes	3-68
Table 3-21. Cursor Styles for ATTR_CROSS_HAIR_STYLE	3-78
Table 3-22. Styles for ATTR_CURSOR_POINT_STYLE	
and ATTR_TRACE_POINT_STYLE	3-78
Table 3-23. Line Styles for ATTR_LINE_STYLE	3-79
Table 3-24. Plot Styles for ATTR_PLOT_STYLE	
Table 3-25. Values for ATTR_PLOT_ORIGIN	3-81
Table 3-26. System Attributes	
Table 3-27. Hard Copy Attributes	3-89
Table 3-28. Values for ATTR_COLOR_MODE	3-91
Table 4-1. The User Interface Library Function Tree	4-2
Table 5-1. Sample Program Files	5-2

## **About This Manual**

The LabWindows/CVI User Interface Reference Manual contains information about creating and controlling custom user interfaces with the LabWindows/CVI User Interface Library. To use this manual effectively, you need to be familiar with the information in Getting Started with LabWindows/CVI and the LabWindows/CVI User Manual. Also, you should know how to perform basic tasks with LabWindows/CVI and Windows.

You should read Chapter 1, *User Interface Concepts*, and Chapter 3, *Programming with the User Interface Library*, before you develop a program with the User Interface Library. You should also examine and execute the example programs outlined in Chapter 5, *LabWindows/CVI Sample Programs*. These examples illustrate many of the concepts presented in Chapters 1 and 3 and should help you develop your own user interface.

## **Organization of This Manual**

The LabWindows/CVI User Interface Reference Manual is organized as follows.

- Chapter 1, *User Interface Concepts*, describes building and controlling a graphical user interface in LabWindows/CVI. It explains how your user interface resource (.uir) files and your code files interact, so that you can structure your event-driven programs correctly. In addition, it describes the objects and concepts that comprise a graphical user interface (GUI). This chapter also describes how to operate menu bars, panels, and controls with the keyboard and mouse.
- Chapter 2, *User Interface Editor Reference*, tells you how to create a GUI interactively. It describes the User Interface Editor and the procedures for creating and editing panels, controls, and menu bars.
- Chapter 3, *Programming with the User Interface Library*, describes how to use the User Interface Library in the application programs you create.
- Chapter 4, *User Interface Library Reference*, describes the functions in the LabWindows/CVI User Interface Library. The *User Interface Library Function Overview* section contains general information about the User Interface Library functions and panels. The *User Interface Library Function Reference* section contains an alphabetical list of function descriptions.
- Chapter 5, *LabWindows/CVI Sample Programs*, contains a list of the sample programs in LabWindows/CVI and a brief description of each.
- Appendix A, *Error Conditions*, lists the meanings associated with the integer error codes that the LabWindows/CVI User Interface library functions return.

- Appendix B, *Customer Communication*, contains forms you can use to request help from National Instruments or to comment on our products and manuals.
- The *Glossary* contains an alphabetical list and description of terms used in this manual, including abbreviations, acronyms, metric prefixes, mnemonics, and symbols.
- The *Index* contains an alphabetical list of key terms and topics in this manual, including the page where you can find each one.

## **Conventions Used in This Manual**

The following conventions are used in this manual.

**bold** Bold text denotes a parameter, menu item, return value, function panel

item, or dialog box button or option.

italic Italic text denotes emphasis, a cross reference, or an introduction to a

key concept.

**bold italic** Bold italic text denotes a note, caution, or warning.

monospace Text in this font denotes text or characters that you should literally

enter from the keyboard. Sections of code, programming examples, and syntax examples also appear in this font. This font also is used for

the proper names of disk drives, paths, directories, programs,

subprograms, subroutines, device names, variables, filenames, and extensions, and for statements and comments taken from program code.

italic monospace Italic text in this font denotes that you must supply the appropriate

words or values in the place of these items.

<> Angle brackets enclose the name of a key. A hyphen between two or

more key names enclosed in angle brackets denotes that you should simultaneously press the named keys, for example, <Ctrl-Alt-Delete>.

» The » symbol leads you through nested menu items and dialog box

options to a final action. The sequence **File** » **Page Setup** » **Options** » **Substitute Fonts** directs you to pull down the **File** menu, select the **Page Setup** item, select **Options**, and finally select the **Substitute Fonts** option from the last dialog box.

paths Paths in this manual are denoted using backslashes (\) to separate

drive names, directories, and files, as in the following path.

drivename\dir1name\dir2name\myfile

Acronyms, abbreviations, metric prefixes, mnemonics, and symbols, and terms are listed in the *Glossary*.

## **Customer Communication**

National Instruments wants to receive your comments on our products and manuals. We are interested in the applications you develop with our products, and we want to help you if you have problems with them. To make it easy for you to contact us, this manual contains comment and technical support forms for you to complete. These forms are in Appendix B, *Customer Communication*, at the end of this manual.

# **Chapter 1 User Interface Concepts**

This chapter describes building and controlling a graphical user interface in LabWindows/CVI. It explains how your user interface resource (.uir) files and your code files interact, so that you can structure your event-driven programs correctly. In addition, it describes the objects and concepts that comprise a graphical user interface. This chapter also describes how to operate menu bars, panels, and controls with the keyboard and mouse.

## **Introduction to the Graphical User Interface**

A LabWindows/CVI graphical user interface (GUI) can consist of panels, command buttons, pull-down menus, graphs, strip charts, knobs, meters, and many other controls and indicators. Figure 1-1 shows a typical GUI created with LabWindows/CVI. You can build a GUI in LabWindows/CVI interactively using the User Interface Editor, a drop-and-drag editor with tools for designing, arranging and customizing user interface objects. With the interactive User Interface Editor, you can build an extensive GUI for your program without writing a single line of code. When you are finished designing your GUI in the User Interface Editor, you save the GUI as a User Interface Resource (.uir) file. Chapter 2, *User Interface Editor Reference*, has detailed information on the User Interface Editor.

In addition to the User Interface Editor, the User Interface Library has functions for creating or altering the appearance of the controls on your GUI during run-time, so you can programmatically add to, change, or build your entire GUI.




Figure 1-1. A Typical LabWindows/CVI Graphical User Interface

## **User Interface Events**

When you design a user interface, you are defining areas on your computer screen, in the form of controls, that can generate events. For example, when you click on a command button, the button generates a user interface event which is then passed to your C program. Actually, LabWindows/CVI controls generate multiple user interface events. For example, a single mouse-click on a command button will pass the following user interface events to your program for processing.

- 1. GOT\_FOCUS event—If the command button is not the active control (does not have the input focus), a mouse-click on the button will make it the active control. When a control gets the input focus, a GOT\_FOCUS event occurs.
- 2. LEFT\_CLICK event—When users click with the left mouse button on the command button, a LEFT\_CLICK event occurs. LabWindows/CVI user interface controls can recognize left, right, single, and double mouse clicks.
- 3. COMMIT event—When the user releases the mouse button, a COMMIT event occurs signifying that the user has performed a commit event on the control.

Each control type available in the LabWindows/CVI User Interface Editor displays different types of information and passes different user interface events to your program. The first half of this chapter introduces each control type available in LabWindows/CVI, telling you how to operate each control type and which events can be passed by each control type.

## Controlling Your User Interface Using Callbacks or GetUserEvent

Once you have built your GUI in LabWindows/CVI, you must develop a C program to process the events generated from the user interface and control the flow of your program. LabWindows/CVI offers two basic methods for designing your programs: callback functions and event-loops. When you use callback functions, you write individual functions in your program that are called directly by user interface controls. For example, you may have a function in your program called AcquireData which is assigned to a button labeled Acquire. Whenever the Acquire button is clicked, all of the event information generated by the button will be passed directly to the AcquireData function where it is processed.

Alternatively, you can use an event-loop to process your user interface commit events in LabWindows/CVI. With an event-loop, all commit events are funneled through a call to the GetUserEvent function in your program. The GetUserEvent function identifies which controls generated the events and your program processes the events accordingly.

Both callback functions and event-loops have advantages, depending on your application. You can use either method in your program, or combine methods for added flexibility. For further details, read the section *Creating a Graphical User Interface* in Chapter 3 of this manual, *Programming with the User Interface Library*.

## **Source Code Connection**

To establish the connection between your .uir files and your C source files you must include a header file in your source code. When you create a control in the User Interface Editor, you must assign some information to the control so that it can be properly accessed by your program. Each control is given a *constant name* in the User Interface Editor. The constant name is used in functions from the User Interface Library in your program to identify the controls on your GUI. For example, you define a numeric readout on your user interface with the constant name READOUT, residing on a panel with the constant name PANEL. To set the value displayed in the readout from your program, you would call the function SetCtrlVal with the name PANEL\_READOUT as one of the parameters to specify the control in which to set the value.

In addition to assigning constant names to each control on your GUI, you can also assign callback functions to controls in the User Interface Editor. For example, if you wanted a function called AcquireData to be executed whenever the command button ACQUIRE is clicked, you assign the callback function name AcquireData to the ACQUIRE button in the User Interface Editor.

Whenever you save a .uir file in the User Interface Editor, LabWindows/CVI automatically creates a corresponding header (.h) file with the same base filename. The header file declares all of the constant names and callback functions that you have assigned within the .uir file. By including the header file in your source code, all of the constant names and callback functions associated with your GUI are automatically declared.

## **Control Modes for Generating Commit Events**

Commit events are generated when the user of the GUI actually commits to an operation such as making a menu selection or typing in a number and pressing <Enter>. When you create a control you can assign one of the following control modes, which determines how the control generates commit events.

- Normal
- Indicator
- Hot
- Validate

*Normal* specifies that the user can operate the control and that it can be changed programmatically.

*Indicator* specifies that you can change the control programmatically but users cannot generate commit or value changed events. Strip chart and text message controls are always indicators.

*Hot* is identical to normal except that the control generates a commit event when acted upon by the user. Normally, a hot control generates a commit event when its state is changed. For example, if the user moves a binary switch from off to on, a commit event is generated. The following control types have unique rules on how commit events are generated.

- For hot numeric, string, and text box controls, a commit event is generated when the user presses <Enter> or <Tab> after entering a value into the control, or if the user clicks elsewhere with the mouse after entering a value into the control.
- For hot selection list controls not in check mode, a commit event is generated when the user presses <Enter> while the control is active, or double-clicks on a list item.
- For hot selection list controls in check mode, a commit event is generated when the user presses the spacebar while the control is active, or double-clicks on a list item.
- For hot graph controls, a commit event is generated when the user moves a cursor with the arrow keys or when the user releases the mouse button after moving a cursor.

Validate is identical to hot except that, before the commit event is generated, the program validates all numeric controls on the panel that have their range-checking attribute set to Notify. LabWindows/CVI checks the control value against a predefined range. If it finds an invalid condition, LabWindows/CVI activates the control, causing a notification box like the one shown in Figure 1-2 to display. The validate control cannot generate a commit event until the user enters a new, valid value into all controls that are out of range. This process ensures that all numeric/scalar controls are valid before the commit event is reported to your application program.




Figure 1-2. The Out Of Range Dialog Box

## **Using CodeBuilder to Create Source Code for Your GUI**

With the LabWindows/CVI CodeBuilder, you can create automatically complete C code that compiles and runs based on a user interface (.uir) file you are creating or editing. By choosing certain options presented to you in the **Code** menu of the User Interface Editor, you can produce *skeleton code*. Skeleton code is syntactically and programmatically correct code that compiles

and runs before you have typed a single line of code. With the CodeBuilder feature, you save the time of typing in standard code included in every program, eliminate syntax and typing errors, and maintain an organized source code file with a consistent programming style. Because a CodeBuilder program compiles and runs immediately, you can develop and test the project you create, concentrating on one function at a time.

## **Operating a Graphical User Interface**

Before creating your first GUI using LabWindows/CVI, you must understand the graphical objects that are available and how they operate. You will learn how to operate all of the GUI controls and indicators in this section.

## **Using Panels**

A *panel* is a rectangular region of the screen where controls and menu bars reside. Panels provide the backdrop for many different activities, such as representing the front panel instrument.

Panels operate like windows. You can minimize panels, resize them, move them, overlap multiple panels, or can contain another. An example of a child panel within a parent panel is shown in Figure 1-3. The outer panel is called the parent panel; the inner panel is called a child panel. Child panels can appear within other child panels. You cannot drag a child panel outside its parent panel. If you shrink a parent panel, a child panel may be partially or completely hidden in the shrunken panel view.




Figure 1-3. A Child Panel Within a Parent Panel

To operate a panel from the keyboard:

- Press <Shift-Ctrl> and the up arrow key to move to the parent panel of the current panel.
- Press <Shift-Ctrl> and the down arrow key to move to the child panel of the current panel.

• Press <Shift-Ctrl> and the left or right arrow key to move to rotate between panels at the current level in the panel hierarchy.

- Press <Tab> to move to the next control on a panel.
- Press <Shift-Tab> to move to the previous control on a panel.

To operate a panel with the mouse:

- Click anywhere inside a panel to make it active.
- Click anywhere on a control to make it active.

## **Using Menu Bars**

A *menu bar* is a mechanism for encapsulating a set of commands. A menu bar appears as a bar at the top of a panel and contains a set of menu titles. A sample menu bar and pull-down menu appear in Figure 1-4.




Figure 1-4. A Menu Bar and Pull-Down Menu

A menu title ending in an exclamation point is called an *immediate action menu* and does not have an associated pull-down menu. When the user clicks on an immediate action menu it executes immediately.

A menu title without an exclamation point has a pull-down menu. The menu contains a collection of menu items and submenu titles. Submenu items are displayed to the side of submenu titles. A sample submenu appears in Figure 1-5.




Figure 1-5. A Pull-Down Menu with a Sub-Menu

To operate a menu bar from the keyboard:

• To display a menu or execute an immediate action menu, press the <Alt> key and the underlined letter of the menu title. When a menu is displayed, its title is highlighted.

- Press the right or left arrow key to display adjacent menus.
- Press the up or down arrow key or the underlined letter of the menu item to select items in a menu. When an item is selected, its label is highlighted.
- Press <Enter> to execute the highlighted item and remove the menu.
- Press <Esc> to remove the menu without executing a menu item.

To operate a menu bar with the mouse:

- To display a menu or execute an immediate menu, click on the menu title.
- To execute an item within a menu, click on the menu item. The menu disappears.
- Click anywhere outside the menu to remove the menu without executing the menu item.

Menu titles and menu items that are dimmed are not selectable.

## **Using Controls**

A *control* is an object that resides on a panel to accept input from the user and to display information. The User Interface Library supports the following control types.

- Numeric
- String
- Text Message
- Text Box
- Command Button
- Toggle Button
- LED
- Binary Switch
- Ring Control
- List Box
- Decorations
- Graphs and Strip Charts

- Pictures
- Timer Control
- Canvas Control

To make a control ready to accept input, click on the control with the mouse or press <Tab> or <Shift-Tab> to move from control to control. Pressing <Alt> and the underlined letter in the label of the control makes that control ready to accept input, provided that no menu bars are accessible.

## **Data Types of Controls**

Every control has a *data type* associated with it. The data type of the control determines the data type of variables used to set and obtain the value of the control. The following list shows LabWindows/CVI control data types.

unsigned char char char \* unsigned short int short int unsigned long int long int float double

Not all data types are valid for each type of control.

#### **Numeric Controls**

*Numeric controls* are used to input or display numeric values. A typical use of these controls might be to input or display a voltage value. Numeric controls have many different graphical representations, including knobs, meters, thermometers, gauges, and dials. The numeric controls are shown in Figure 1-6.




Figure 1-6. Numeric Controls

When a numeric control is not restricted to indicator, you may change its value from the keyboard or with the mouse.

To operate a numeric control from the keyboard:

- Press the left or right arrow key to move the cursor within the digital display of the control.
- Press the up or down arrow key to increase or decrease the value displayed in the control.
- Press <Home> to move the cursor to the beginning of the text.
- Press <End> to move the cursor to the end of the text.
- Press <Shift-Home> to highlight all text to the left of the cursor.
- Press <Shift-End> to highlight all text to the right of the cursor.

To operate a numeric control with the mouse:

- Click on the up/down arrows of the digital display to change the value of the control.
- Click on and drag the needle (for circular controls like knobs) or the slider (for slide controls) to change the value of the control.
- Click on scale labels to set the control to the value of the label.

If the control mode of a numeric control is hot or validate, a commit event is generated when the user presses the up or down arrow keys, or when the user changes the digital display of a numeric control and then presses the <Enter> or <Tab> key or clicks on another object with the mouse.

## **String Controls**

String controls are used to input or view strings of character values. You can use these controls to input a person's name. A string control is shown in Figure 1-7.




Figure 1-7. A String Control

To operate a string control:

Press the left or right arrow key to move the cursor around in the string control.

- Press <Home> to move the cursor to the beginning of the text.
- Press <End> to move the cursor to the end of the text.

If the control mode of the string is hot or validate, a commit event is generated when the user changes the string and then presses the <Enter> or <Tab> key or clicks on another object with the mouse.

### **Text Messages**

*Text messages* are indicator controls used to programmatically display strings of text. You cannot operate them using the keyboard, but you can assign callback functions to them so that they respond to mouse click events. A text message control is shown in Figure 1-8.

Warning: Temperature Too High!

Figure 1-8. A Text Message

#### **Text Box Controls**

*Text box* controls are large string controls that feature line, word, and character wrap modes and scroll bars to facilitate displaying large amounts of text. As with the string control, you can interactively enter text into text boxes and you can control the text box programmatically.

A sample text box appears in Figure 1-9.




Figure 1-9. A Text Box Control

When entering text into a textbox:

- Press <Ctrl-Tab> to insert four spaces.
- Press <Ctrl-Enter> to start a new line.
- Press <Home> or <End> to move to the beginning or end of the current line.
- Press < Page Up> or < Page Down> to scroll the text box up or down one page.

• Text can be selected by holding down <Shift> and pressing the arrow keys, <Home>, <End>, <Page Up>, or <Page Down>.

If the control mode of the text box is hot or validate, a commit event is generated when the user changes the value of the text box and then presses the <Enter> or <Tab> key or clicks on another object with the mouse.

#### **Command Button Controls**

*Command buttons* are used to trigger an action, which is indicated by the label on the button. The command buttons are shown in Figure 1-10.



Figure 1-10. The Command Button Controls

To operate a command button from the keyboard, press <Enter> or <space> to activate the button. If the control mode of the button is hot or validate, a commit event will be generated when the user presses the <Enter> or <space> key. The button changes appearance momentarily to indicate that it was selected.

To operate a push button with the mouse, click on the button. The button remains depressed until the user releases the mouse or moves it off the button. If the control mode of the command button is hot or validate, a commit event is generated when the user clicks and releases the mouse over the command button area. If the user releases the mouse outside of the button area, a commit event is not generated.

#### **Toggle Button Controls**

*Toggle buttons* allow you to select between two different states. A toggle button has two positions: pressed or unpressed. When the button is pressed its value is 1, and when it is unpressed its value is 0. The toggle buttons are shown in Figure 1-11.



Figure 1-11. The Toggle Button Controls

To operate a toggle button from the keyboard:

- Press the up arrow key or <Home> to press the toggle button in.
- Press the down arrow key or <End> to pop the toggle button out.
- Press <space> or <Enter> to change the state of the button.

To operate a toggle button with the mouse, click on the toggle button to change its state.

If the control mode of the toggle button is hot or validate, a commit event is generated when the button is active and the user changes its state.

#### **LED Controls**

*LEDs* (Light Emitting Diodes) indicate an on/off state. When the LED is on, its value is 1 and it displays its ON color. When the LED is off, its value is 0 and it displays its OFF color. The LED controls are shown in Figure 1-12.



Figure 1-12. The LED Controls

LED controls operate like toggle button controls.

## **Binary Switch Controls**

*Binary switches*, like toggle buttons, allow you to select between two states: on or off. You can also associate a value with each state of a binary switch. The binary switches are shown in Figure 1-13.




Figure 1-13. The Binary Switch Controls

Binary switch controls operate like toggle button controls.

## **Ring Controls**

You use *ring controls* to select from a group of items. Many of the ring controls look like numeric controls, but ring controls have a finite set of label/value pairs. The ring controls are shown in Figure 1-14.




Figure 1-14. Ring Controls

To operate a ring control from the keyboard:

- Press the up arrow key to select the previous ring control item.
- Press the down arrow key to select the next ring control item.

Ring controls with arrows can also be operated in pop-up format, in which a linear list of all the ring items is displayed at once. A sample ring control in pop-up format is shown in Figure 1-15.




Figure 1-15. A Ring Control in Pop-Up Format

To operate a ring control pop-up with the keyboard:

- Press <space> to display the ring control pop-up.
- Press the up and down arrow keys to highlight particular items.
- Press <Enter> to select the highlighted item. The pop-up control disappears and the ring control is updated to match the new selection.

• Press <Esc> to remove the pop-up without changing the selected item.

To operate a ring with the mouse:

• If the ring control has arrows, click on the arrows to select the ring control items.

To operate a ring control pop-up with the mouse:

- Click on the ring control to display the ring pop-up.
- Click on an item to select it. The pop-up disappears and the ring control is updated to match the new selection.
- When the pop-up exceeds the size of the screen, hold the mouse button down on the top item to scroll up.
- When the pop-up exceeds the size of the screen, hold the mouse button down on the bottom item to scroll down.
- Click on an item to select it. The pop-up disappears and the ring control is updated to match the new selection.
- Click outside the menu to cancel the operation and remove the pop-up.

Note: If the ring pop-up exceeds twice the size of the screen, users see a list box instead of a ring pop-up. See the section List Box Controls in this chapter for instructions on operating list box controls.

If the control mode of a ring control is hot or validate, a commit event is generated when the user changes the ring's value.

#### **List Box Controls**

*List box controls* are used to select an item from a list. A sample selection list control is shown in Figure 1-16.




Figure 1-16. A Selection List Control in Check Mode

The scroll bar on the right side of the list scrolls the list up and down.

To operate a list box control from the keyboard:

- Press the up arrow key to highlight the previous list item.
- Press the down arrow key to highlight the next list item.
- Press <Home> to scroll to the top of the list.
- Press <End> to scroll to the bottom of the list.
- Press <Page Up> to scroll up one page.
- Press < Page Down > to scroll down one page.
- Use the Quick Type feature to locate a list item. When you type A, Quick Type takes you to the first occurrence of an item beginning with "A." When you type a complete item name Quick Type takes you to that item. (When you press a key after a delay of at least one second, the Quick Type buffer is flushed.)
- Press the left arrow key to go to the previous item in the Quick Type buffer.
- Press the right arrow key to go to the next item in the Quick Type buffer.
- If the list box is in check mode, press <space> or <Enter> to toggle the check mark of the current item.

To operate a list box control with the mouse:

- Click on an item to highlight it; this action toggles the check mark when in check mode.
- Double-click on an item to select it, when not in check mode.
- Hold the mouse button down on either arrow to scroll through the list.
- Drag the scroll bar marker to a new position.
- Click above the scroll bar marker to scroll up one page.
- Click below the scroll bar marker to scroll down one page.

To generate a commit event when a list box is set to hot or validate mode:

• When the control is set to **Check Mode**, select an item in the list box and press <space> or click on it.

User Interface Concepts Chapter 1

• When the control is not set to **Check Mode**, select an item in the list box and press <Enter> or double-click on it.

#### **Decorations**

Decorations are used to enhance the visual appeal of the GUI. They do not contain data but they can be assigned callback functions so that they can respond to mouse click events. The decorations are shown in Figure 1-17.




Figure 1-17. GUI Decorations

## **Graph Controls**

*Graph controls* display graphical data as one or more plots. A *plot* consists of a curve, a point, a geometric shape, or a text string. A sample graph control is shown in Figure 1-18.




Figure 1-18. A Graph Control

Graph controls can have one or more cursors associated with them. With cursors you can select a point or region of the graph for further processing or analysis. If the graph control is hot, cursors will generate commit events. If you want to use cursors, the graph controls must *not* be in indicator mode.

To operate a graph with cursors using the keyboard, use the keys in the following tables for both free-form and snap-to-point cursors.

Table 1-1. Keys For Selecting Cursors

When you press	You select			
<page-up></page-up>	The previous cursor.			
<page-down></page-down>	The next cursor.			
Left arrow key	Left ten pixels.			
Right arrow key	Right ten pixels.			
Up arrow key	Up ten pixels.			
Down arrow key	Down ten pixels.			
<shift>-left arrow key</shift>	Left one pixel.			
<shift>-right arrow key</shift>	Right one pixel.			
<shift>-up arrow key</shift>	Up one pixel.			
<shift>-down arrow key</shift>	Down one pixel.			
<ctrl>-left arrow key</ctrl>	To the left edge of the plot area.			
<ctrl>-right arrow key</ctrl>	To the right edge of the plot area.			
<ctrl>-up arrow key</ctrl>	To the top edge of the plot area.			
<ctrl>-down arrow key</ctrl>	To the bottom edge of the plot area.			
<home></home>	To the lower left corner of the plot area.			
<end></end>	To the upper right corner of the plot area.			
Left arrow key	To the previous point on the current plot.			
Right arrow key	To the next point on the current plot.			
Up arrow key	To the next point on the current plot.			
Down arrow key	To the previous point on the current plot.			
<shift>-left arrow key</shift>	Back 10 points on the current plot.			

(continues)

User Interface Concepts Chapter 1

Table 1-1. Keys For Selecting Cursors (Continued)

When you press	You select				
<shift>-right arrow key</shift>	Forward 10 points on the current plot.				
<shift>-up arrow key</shift>	Forward 10 points on the current plot.				
<shift>-down arrow key</shift>	Back 10 points on the current plot.				
<ctrl>-left arrow key</ctrl>	Left to the closest point in the X direction on the current plot.				
<ctrl>-right arrow key</ctrl>	Right to the closest point in the X direction on the current plot.				
<ctrl>-up arrow key</ctrl>	Up to the closest point in the Y direction on the current plot.				
<ctrl>-down arrow key</ctrl>	Down to the closest point in the Y direction on the current plot.				
<home></home>	To the first visible point on the current plot.				
<end></end>	To the last visible point on the current plot				
<shift-page up=""></shift-page>	To the previous plot.				
<shift-page down=""></shift-page>	To the next plot.				

If the graph is configured as a hot control, an event will be generated whenever the user presses one of the preceding keys.

Operate a graph with cursors using the mouse as follows.

- Drag a cursor to move it. If the cursor is in snap-to-point mode, the cursor tracks the mouse until the user releases the mouse button and then it snaps to the nearest data point. If the cursor is in free-form mode, the cursor tracks the mouse until the user releases the mouse button and then stays at the new position.
- Move the active cursor left and right by dragging the active cursor marker at the top or bottom edge of the plot area. Likewise, you can move the active cursor up and down by dragging the active cursor marker at the left or right edge of the plot area.

If the graph control is configured in hot mode, a commit event is generated whenever the user moves a cursor using the arrow keys or releases the mouse after moving a cursor.

EVENT\_VAL\_CHANGED events are generated continuously while a user drags a graph cursor.

## **Zooming and Panning on Graphs**

You can use *zooming*—the ability to expand or contract the viewport around a particular point—in graph controls. When you zoom *in*, the logical area contained in the viewport gets smaller, thereby showing the area with more resolution. When you zoom *out*, the viewport shows a wider area. You can also use *panning*, the ability to shift the viewport.

By default, however, zooming and panning are disabled. You must explicitly enable them in the User Interface Editor or programmatically. Also, a graph control must not be in indicator-only mode if zooming and panning are to be used.

To start zooming in on a point, press the <Ctrl> key and left mouse button down over the point. The resolution in the viewport is continuously increased until you release the mouse. (You do not need to keep the <Ctrl> key down.) If you drag the mouse, the zooming continues but does so over the new point under the mouse cursor. The zooming stops when you release the left mouse button or click on the right mouse button.

You zoom out just like you zoom in, except that you use the right mouse button instead of the left mouse button.

To start panning, press the <Ctrl-Shift> keys and the left mouse button over a point on the viewport. Then drag the mouse to another point. The graph viewport is scrolled so that the original point now appears under the new mouse cursor location. You can drag the mouse anywhere on the screen.

To restore the viewport to its original state after zooming or panning, press <Ctrl-Spacebar>.

If you are using auto-scaling in the graph, the auto-scaling must be temporarily disabled while zooming or panning. If any plotting occurs while the end-user is zooming or panning, the zooming or panning is terminated and the new data is shown using auto-scaling.

User Interface Concepts Chapter 1

## **Strip Chart Controls**

*Strip chart controls* display graphical data in real time. A strip chart consists of one or more traces that are updated simultaneously. A sample strip chart control appears in the following figure.




Figure 1-19. A Strip Chart Control

#### **Picture Controls**

A picture control allows you to place images on panels, such as logos and diagrams. For example, you can use a picture control to place a schematic that instructs the user how to hook up a unit for testing. When you want to place images on command or toggle buttons or on ring controls, LabWindows/CVI frees you from programming the simple Picture control. Separate command and toggle buttons and ring controls exist for pictures. For more information on those picture controls, read the *Programming with Picture Controls* section of Chapter 3, *Programming with the User Interface Library*.

The image formats that work with all types of picture controls appear in Table 1-2.

Image Format	Platform			
PCX	Windows and UNIX			
BMP, DIB, RLE, ICO	Windows only			
XWD	UNIX only			
WMF	Windows 95 and NT only			

Table 1-2. Image Formats

#### **Timer Controls**

Use *Timer Controls* to trigger actions at specific time intervals. The timer control schedules these actions so that you do not have to. The timer control is shown in Figure 1-20.



Figure 1-20. The Timer Control

Timer controls repeat a given action at a specified time interval for an indefinite period of time, which makes them useful programming tools when a repeated action is required. You can specify a function to be called at the end of each interval.

LabWindows/CVI has functions to suspend and reset the timer controls.

Timer controls are not visible during program execution. They are only visible in the User Interface Editor. For more information, read the *Programming with Timer Controls* section of Chapter 3, *Programming with the User Interface Library*.

#### **Canvas Controls**

Use *canvas controls* as an arbitrary drawing surface. You can draw text, shapes, and bitmap images. An offscreen bitmap is maintained so that the appearance of the canvas can be restored when the region is exposed.

If you want to display images that are not rectangular or that have "holes" in them, you can use bitmaps that have a transparent background.

# **Using Pop-Up Panels**

A pop-up panel is a panel that pops up, accepts user input, and then disappears.

Pop-up panels can be stacked, with each new pop-up panel appearing on top of the previous one. When a pop-up panel is active it appears in the foreground and is the only panel or pop-up you can operate.

The User Interface Library contains a collection of predefined pop-up panels for common operations, such as displaying a multi-line message, prompting the user for input, prompting the user for confirmation, selecting a file, and graphing numerical data.

Specific function calls invoke each predefined pop-up panel. The function displays the pop-up panel and waits for the user to select an action. Then the pop-up disappears and control returns to the program.

User Interface Concepts Chapter 1

## **Operating the Message Pop-Up Panel**

The *message pop-up panel* displays multi-line messages. Use the newline character (\n) to start a new line of text. A sample message pop-up panel appears in the following figure.



Figure 1-21. A Message Pop-Up Panel

## **Operating the Generic Message Pop-Up Panel**

The *generic message pop-up panel* displays a pop-up panel with a message string, a response buffer, and up to three buttons with programmable labels. A sample generic message pop-up panel appears in Figure 1-22.



Figure 1-22. A Generic Message Pop-Up Panel

## **Operating the Prompt Pop-Up Panel**

The *prompt pop-up panel* requests input from the user. A sample prompt pop-up panel appears in Figure 1-23.



Figure 1-23. A Prompt Pop-Up Panel

## **Operating the Confirm Pop-Up Panel**

The *confirm pop-up panel* allows the user to confirm an action. A sample confirm pop-up panel appears in Figure 1-24.



Figure 1-24. A Confirm Pop-Up Panel

## **Operating the File Select Pop-Up Panel**

The *file select pop-up panel* displays a list of files on disk from which the user can select. A file select pop-up panel for Windows 3.1 appears in the following figure.




Figure 1-25. A File Select Pop-Up Panel under Windows 3.1

A unique feature of this dialog box is the **Directories** ring in the upper-right corner of the dialog box. When activated, this ring allows users to select from a list of directories that contain previously opened files.

User Interface Concepts Chapter 1

A file select pop-up panel for Windows 95 appears in the following figure.




Figure 1-26. A File Select Pop-Up Panel under Windows 95

## **Operating Graph Pop-Up Panels**

You can choose from four different types of graph pop-up panels to display a graph of numerical data: *X-graph pop-up*, *Y-graph pop-up*, *XY-graph pop-up*, and *Waveform graph pop-up*. A sample graph pop-up panel appears in the following figure.




Figure 1-27. A Graph Pop-Up Panel

## **Using Fonts**

## **Metafonts That Use Typefaces Native To Each Platform**

Metafonts contain typeface information, point size, and text styles such as bold, underline, italic, and strikeout. The following metafonts use typefaces that are native to each platform supported by LabWindows/CVI. Each of these metafonts has been specified so that the height and width of the font is as similar as possible across platforms.

```
VAL_MENU_META_FONT
VAL_MESSAGE_BOX_META_FONT
VAL_DIALOG_META_FONT
VAL_EDITOR_META_FONT
VAL_APP_META_FONT
```

You can create metafonts from any font on your system with the CreateMetaFont function.

## Fonts That Use Typefaces Native To Each Platform

The following fonts use typefaces that are native on both PC and UNIX systems. Fonts contain typeface information only.

```
VAL_MENU_FONT
VAL_MESSAGE_BOX_FONT
VAL_DIALOG_FONT
VAL_EDITOR_FONT
VAL_APP_FONT
```

## Metafonts That Use Typefaces Installed by LabWindows/CVI

The following metafonts are included in LabWindows/CVI, but use typefaces that are not native to PC or UNIX systems. The typefaces are distributed with LabWindows/CVI and the run-time engine.

```
VAL_7SEG_META_FONT
VAL_SYSTEM_META_FONT
```

# Chapter 2

# **User Interface Editor Reference**

As explained in Chapter 1, you can create your GUI programmatically using function calls or interactively using the User Interface Editor. This chapter tells you how to create a GUI interactively. It describes the User Interface Editor and the procedures for creating and editing panels, controls, and menu bars.

When you use the User Interface Editor you create and modify user interface resource (.uir) files. Enter the User Interface Editor by selecting **New** or **Open** from the **File** menu and choosing **User Interface** (\*.uir).

## **User Interface Editor Overview**

A User Interface Editor window appears in the following figure.




Figure 2-1. A User Interface Editor Window

From this window, you can create and edit GUI panels, controls, and menu bars. The menus are described in this chapter in the section *User Interface Editor Menus*. Use the tool bar beneath the menu bar for high-level editing with the mouse. When you click on a particular tool, the mouse cursor changes to reflect the new editing mode.

[]

You can select, position, and size objects by using the Editing tool.



A You can modify text associated with objects by using the Labeling tool.



You can color objects by using the Coloring tool. Clicking the right mouse button displays a color palette from which you can choose a color. Clicking the left mouse button automatically colors the object with the current color of the Coloring tool. Holding down the <Ctrl> key changes the tool to an eyedropper icon, \( \scale=\). When you click on an object with the eyedropper icon, the current color of the Coloring tool becomes the color of that object. Then you can apply that object's color to another object.



Use the Operating tool to operate objects. When you are in the operate mode, events display on the right side of the tool bar. These event displays have a built-in delay to give you time to see each event.

# **Using the User Interface Editor Popup Menus:**

You can bring up a pop-up menu by clicking with the right mouse button on the User Interface Editor Window. The type of pop-up menu that appears depends on the surface you click on.

- If you click on the User Interface Editor Window background, a pop-up menu appears containing commands to create a panel or a menu bar.
- If you click on a panel background, a pop-up menu appears with each of the control types you can create.
- If you click on a control, a pop-up menu appears with commands to generate or view the callback function for the control.

## **Code Builder Overview**

With the LabWindows/CVI CodeBuilder, you can create automatically complete C code that compiles and runs based on a user interface (.uir) file you are creating or editing. By choosing certain options presented to you in the Code menu, you can produce skeleton code. Skeleton code is syntactically and programmatically correct code that compiles and runs before you have typed a single line of code. With the CodeBuilder feature, you save the time of typing in standard code included in every program, eliminate syntax and typing errors, and maintain an organized source code file with a consistent programming style. Because a CodeBuilder program compiles and runs immediately, you can develop and test the project you create, concentrating on one function at a time.

When you choose Code » Generate » All Code, LabWindows/CVI places the #include statements, variable declarations, callback function skeletons, and main function in the source code file you specify as the target file. Each function skeleton contains a switch construct with a case statement for every default event you specify. You can set default events for control callback functions and panel callback functions by choosing Code » Preferences. Although

skeleton code runs, you must customize it to implement the actions you want to take place in the case of each event.

When you generate code for a specific control or panel callback function, LabWindows/CVI places the skeleton code for that function in the target file in the same complete format as was done for the **Code** » **Generate** » **All Code** command. However, this code might not run. In order for a project to run, there must be a main function. If you lack the main function or any of the callback functions defined in the .uir file, the code is incomplete.

It is a good idea to use the **Code** » **Generate** » **All Code** option first, to produce a running project from the current state of the .uir file. Then, after adding panels, controls or menu items to the .uir file, use the **Generate Panel**, **Control Callbacks** and **Menu Callbacks** commands to make corresponding additions to the source file.

Also with CodeBuilder, you can take care of program termination for automatically generated code. For a CodeBuilder program to terminate successfully, you must include a call to the QuitUserInterface function. When you choose Code » Generate » All Code, the Generate All Code dialog box prompts you to choose which callback functions terminate the program. You can select one or more callback functions to ensure proper program termination.

# **User Interface Editor Menus**

The User Interface Editor has a menu bar that contains the following options: **File**, **Edit**, **Create**, **View**, **Options**, **Window**, and **Help**.

#### File Menu

The **File** menu is shown in the following figure.




Figure 2-2. The File Menu

## New, Open, Save, and Exit LabWindows/CVI Commands

The New, Open, Save, and Exit LabWindows/CVI commands in the User Interface Editor menu bar work like New, Open, Save and Exit LabWindows/CVI commands in the Project window. If you require more information, consult Chapter 3, *Project Window*, in the *LabWindows/CVI User Manual*.

#### **Save As and Close Commands**

The **Save As** and **Close** commands work like **Save** and **Close** in common Windows applications. It is assumed that you are familiar with these commands.

## Save Copy As

The **Save Copy As** command writes the contents of the active window to disk using a user-specified name, without changing the name of the active window. If you want to append a different extension, type a new extension after the filename. If you want no extension to be appended, enter only a period after the filename.

#### Save All

The **Save All** command saves all open files to disk.

## **Add File to Project**

The **Add File to Project** command adds the .uir file in the current window to the project list.

## **Read Only**

The **Read Only** command suppresses the editing capabilities in the current window.

#### **Print**

The **Print** command opens the **Print** dialog box which allows you to send the entire .uir file or the visible screen area to a printer or a file. The **Print** dialog box also allows you to set print preferences. The print preferences (attributes) are described in the *Generating Hard Copy Output* section of Chapter 3, *Programming with the User Interface Library*.

#### **Edit Menu**

Items in this **Edit** menu are used for editing panels, controls, and menu bars. Figure 2-3 shows the **Edit** menu.

<u>F</u> ile	Edit Create	<u>V</u> iew	<u>A</u> rrange	Code	Run	Library	<u>W</u> indow	<u>O</u> ptions	<u>H</u> elp
	<u>U</u> ndo Panel	Move	;	Ctrl+Z					
	Red <u>o</u>		Ctrl	+BkSp					
	Cuţ			Ctrl+X					
	<u>С</u> ору			Ctrl+C					
	<u>P</u> aste			Ctrl+V					
	De <u>l</u> ete			Del					
	Copy Pa <u>n</u> el		Ctrl+S	Shift+C					
	Cut Pan <u>e</u> l		Ctrl+S	Shift+X					
	<u>M</u> enu Bars								
	Panel								
	Cont <u>r</u> ol			Enter					
	Ta <u>b</u> Order			Ctrl+T					
	Set Default	Font	Ctrl+	Shift+F					
	Apply Defau	ılt <u>F</u> on	ıt	Ctrl+F					
	Control Styl			F11					

Figure 2-3. The Edit Menu

Note: Undo and Redo are enabled when you perform an edit action. The Cut and Copy commands are enabled when you select a control, and Paste is enabled when you place an object in the Clipboard using the Cut or Copy command. If you select an edit command while it is disabled, nothing happens.

#### Undo and Redo

The **Undo** command reverses your last edit action and the screen returns to its previous state. Edit actions are stored on a stack so that you can undo a series of your edit actions. The stack stores up to 100 edit actions and is set using the **Preferences** command in the **Options** menu.

The **Redo** command reverses your last **Undo** command, restoring the screen to its previous state. **Redo** is helpful when you use the **Undo** command to reverse a series of your edit actions and accidentally go too far. The **Redo** command is enabled only when your previous action was the **Undo** command. Any action disables the **Redo** command.

Actions that can be undone and redone are dynamically displayed in the menu, for example, when you move a control the menu presents the option **Undo Move Control**.

## **Cut and Copy**

The **Cut** and **Copy** commands put controls in the Clipboard. The **Cut** command removes the selected control and places it in the Clipboard. The **Copy** command copies the selected control and places it in the Clipboard, leaving the selected control in its original location. Controls you cut or copy do not accumulate in the Clipboard. Every time you cut or copy a control it replaces whatever was previously stored in the Clipboard.

To use the **Cut** or **Copy** commands, follow these steps.

- 1. Select the control you want to place in the Clipboard by clicking on the control or pressing <Tab> until the control is highlighted. Select multiple controls by dragging the mouse over the controls or <Shift>-clicking on the controls.
- 2. Select **Cut** or **Copy** from the **Edit** menu.

#### **Paste**

The **Paste** command inserts controls, panels, or text from the Clipboard. You can **Paste** an object from the Clipboard as many times as you like. Controls or panels remain in the Clipboard until you use **Cut**, **Cut Panel**, **Copy**, or **Copy Panel** again. The **New** and **Open** commands do not erase the Clipboard.

#### **Delete**

The **Delete** command deletes selected controls without placing the controls in the Clipboard. Because **Delete** does not place controls in Clipboard, you cannot restore the controls using the **Paste** command.

#### **Copy Panel and Cut Panel**

The **Copy Panel** and **Cut Panel** commands put an entire panel in the Clipboard. The **Cut Panel** command removes the selected panel and places it in the Clipboard. The **Copy Panel** command copies the selected panel and places it in the Clipboard, leaving the selected panel in its original location. Panels you cut or copy do not accumulate in the Clipboard. Every time you cut or copy a panel it replaces whatever was previously stored in the Clipboard.

To use the **Cut Panel** or **Copy Panel** commands, follow these steps.

- 1. Select the panel you want to place in the Clipboard by clicking on the panel or pressing <Shift-Ctrl> and one of the arrow keys (up, down, right, or left) until the panel is activated.
- 2. Select **Cut Panel** or **Copy Panel** from the **Edit** menu.

#### **Menu Bars**

The **Menu Bars** command brings up the Menu Bar List dialog box shown in the following figure.



Figure 2-4. The Menu Bar List Dialog Box

The list contains all of the menu bars in the resource file, listed by constant prefix. The following list describes the command buttons.

- Create brings up a new Edit Menu Bar dialog box (Figure 2-5). After a menu bar is created, it is inserted below the current menu bar in the menu bar list.
- Edit brings up the Edit Menu Bar dialog box for the selected menu bar.
- **Cut** deletes the currently highlighted item in the menu bar list and copies it to the menu bar clipboard.
- Copy copies the currently highlighted item in the menu bar list to the menu bar clipboard.
- **Paste** inserts the contents of the menu bar clipboard to the menu bar list. The menu bar is inserted above the currently highlighted item in the menu bar list.
- **Done** closes the Menu Bar List dialog box.

Edit Menu Bar Insert New Item: Menu Bar Constant Prefix: Above Below Item: Constant Name: Insert Separator: Below Above Callback Function: Modifier Key: None Shortcut Key: No Shortcut Key Dimmed ■ Checked <<< >>> View Cut Сору Paste OK Cancel

The Edit Menu Bar dialog box is shown in the following figure.

Figure 2-5. The Edit Menu Bar Dialog Box

The Edit Menu Bar dialog box presents the following options.

- The Menu Bar Constant Prefix is the resource ID for the menu bar. This resource ID is passed to the LoadMenuBar function which loads the panel into memory. The Menu Bar Constant Prefix is defined in the .h file when you save the .uir file. If you do not assign a Menu Bar Constant Prefix, the User Interface Editor assigns one for you when you save the .uir file.
- Item shows the name of the current menu, sub menu, or menu command. If you type two underscores before any letter in the item, the user can select the item by pressing <Alt> and the underlined letter.
- Constant Name is appended to the Menu Bar Constant Prefix to form the ID for the current item. The ID is used in functions such as GetMenuBarAttribute and

SetMenuBarAttribute. The ID is also returned by GetUserEvent when an event is generated by a menu command.

- Naming a **Callback Function** is optional. In this box you can type the name of the function to be called when an event is generated by the current menu item.
- Modifier Key and Shortcut Key combine to form the hot key for the current item.
- **Dimmed** specifies whether or not the current item is initially dimmed.
- **Checked** specifies whether or not the current item initially has a check mark.
- **Insert New Item** inserts the next item above or below the currently selected item.
- **Insert Separator** inserts a separator (a line) above or below the currently selected item.
- The right hierarchy button, >>> , moves the currently selected item down one level in the sub menu hierarchy.
- View displays the current state of the menu bar and pull-down menus.

#### **Panel**

The **Panel** command brings up the Edit Panel dialog box. This dialog box has three sections entitled *Source Code Connection*, *Panel Attributes*, and *Quick Edit Window*.

The Source Code Connection section of the Edit Panel dialog box is shown in the following figure.




Figure 2-6. Source Code Connection

In the **Constant Name** box you type the resource ID for the panel. You pass this resource ID to the LoadPanel function to load the panel into memory. The **Constant Name** is defined in the .h file when you save the .uir file. If you do not assign a **Constant Name**, the User Interface Editor will assign one when you save the .uir file.

Naming a **Callback Function** is optional. In this box you can type the name of the function to be called when an event is generated on the panel.

The Panel Settings sections of the Edit Panel dialog box appear in the following figure.




Figure 2-7. Panel Attributes

Note: The preceding figure shows settings and attributes available in the Windows version of LabWindows/CVI. The Edit Panel dialog box in the UNIX version of LabWindows/CVI lacks some items because that program cannot update some panel attributes for parent panels.

The *Programming with Panels* section of Chapter 3, *Programming with the User Interface Library*, describes panel attributes in detail.

The Quick Edit Window section of the Edit Panel dialog box appears in the following figure.




Figure 2-8. Quick Edit Window

From the Quick Edit Window, you can perform high level edits on the panel. The tools in the tool bar operate like the tools in the main User Interface Editor window. For further information, see the section *User Interface Editor Overview*, earlier in this chapter.

#### Control

The **Control** command brings up the dialog box for editing the selected control. You can also double-click on a control to get this dialog box. The dialog box usually has five sections entitled *Source Code Connection, Control Settings, Control Appearance, Quick Edit Window*, and *Label Appearance*. The contents of the sections vary slightly depending on the control that is being edited.

The Source Code Connection section of the control dialog box is shown in the following figure.




Figure 2-9. Source Code Connection

The User Interface Editor appends **Constant Name** to the panel resource ID to form the ID for the control. The ID identifies the control in any control-specific functions such as GetCtrlVal and SetCtrlAttribute. The ID will be defined in the .h file when you save the .uir file. If you do not assign a **Constant Name**, the User Interface Editor will assign one for you when you save the .uir file.

Naming a **Callback Function** is optional. In this box you can type the name of the function to be called when an event message is generated on the panel.

The Control Settings section of the dialog box senses the type of control that is being edited. It contains the data-specific attributes for the control. The Control Settings section for the Numeric control is shown in the following figure.




Figure 2-10. Control Settings for a Numeric Control

Rings and list boxes have a **Label/Value Pairs** button in the Control Settings section. This button activates the **Edit Label/Value Pairs** dialog box shown in the following figure.




Figure 2-11. The Edit Label/Value Pairs Dialog Box

Use the Edit Label/Value Pairs dialog box to create and edit the contents of ring and list box controls. Use the list control functions in the User Interface Library to control rings and list boxes.

The Control Appearance section of the dialog box senses the type of control that is being edited. It contains attributes pertaining to the physical appearance of the control. The Control Appearance section for the Numeric control appears in the following figure.



Figure 2-12. Control Appearance for a Numeric Control

The Label Appearance section of the dialog box contains attributes pertaining to the physical appearance of the control label. The Label Appearance section for the Numeric control is shown in the following figure.



Figure 2-13. Label Appearance for a Numeric Control

If you type a double underscore before any letter in the label, the user can select the control by pressing <Alt> and the underlined letter, provided that no menu bar is accessible. This feature helps you access controls on pop-up panels.

The Quick Edit Window section of the Edit Control dialog box appears in the following figure.




Figure 2-14. Quick Edit Window

From the Quick Edit Window, you can perform high level edits on the control. The tools in the tool bar operate like the tools in the main User Interface Editor window. The Quick Edit Window also provides immediate feedback for any changes you make in other section of the dialog box.

Simply stated, the dialog box of any control allows you to interactively set all of the attributes of the control. The *Programming with Controls* section in Chapter 3, *Programming with the User Interface Library*, describes these attributes in detail.

## **Tab Order**

Each control on a panel has a position in the tab order. The tab order determines which control becomes the next active control when the user presses <Tab> or <Shift-Tab>.

When you create a control, it is added to the end of the tab order. When you copy and paste a control, the new control sits immediately before the source control in the tab order. Select **Tab Order** from the **Edit** menu to put the panel into tab order edit mode as shown in the following figure.




Figure 2-15. The Edit Tab Order Dialog Box

Click on a control with the special pointer cursor, to change the tab position of a control to the number in the **Click to set to** box. You can change the cursor to the special eyedropper cursor, by holding down the <Ctrl> key. This eyedropper cursor changes the number in the **Click to set to** box to the current tab position associated with that control. Clicking on sets the new tab order. Clicking on reases the new tab order and keeps the original tab order, which appears in dim display to the right of the new tab order you enter.

#### **Set Default Font**

The **Set Default Font** command in the **Edit** menu makes the font of the currently selected control the default control font. If the label is also selected (or is the only item selected), the font of the label becomes the default label font. Newly created controls inherit the default fonts.

## **Apply Default Font**

The **Apply Default Font** command in the **Edit** menu sets the font of the currently selected control (and/or label) to the default control (and/or default label font).

## **Control Style**

Use the **Control Style** command to change the style of the selected control. For example, you can change a ring slide control to a ring knob control, and the label/value pairs remain intact.

#### **Create Menu**

Commands in the **Create** menu create panels, menu bars, and controls.

Figure 2-16 shows the **Create** menu.




Figure 2-16. The Create Menu

#### **Panel**

The **Panel** command places a new, untitled panel onto the User Interface Editor window. The *Edit Menu* section of this chapter provides details on editing the panel.

#### Menu Bar...

The **Menu Bar** command brings up the Edit Menu Bar dialog box. The *Edit Menu* section of this chapter provides details on editing the menu.

#### **Controls**

The remaining options in the **Create** menu allow you to create GUI controls. You can edit the controls you create from the **Edit** menu. The *Edit Menu* section of this chapter provides details on editing the menu.

#### View Menu

This section explains how to use the commands in the **View** menu in the User Interface Editor window.

Figure 2-17 shows the **View** menu.




Figure 2-17. The View Menu

## Find UIR Objects...

Use the **Find UIR Objects** command to locate objects in user interface resource file. When you select this command, the Find UIR Objects dialog box opens, as shown in Figure 2-18.




Figure 2-18. Find UIR Objects Dialog Box

Select the type(s) of objects you want to search for by checking the appropriate check boxes in the left column of the dialog box.

Select the search criterion from the **Search By** ring control. The choices are:

• Constant Prefix (valid for panels and menu bars)

- Constant Name (valid for controls, menus, and menu items)
- Prefix + Constant Name (valid for all)
- Callback Function Name (valid for all except menu bars)
- Label (valid for all except menu bars)

Enter the text you want to search for into the string control. You can view a list of all the strings in the file which match the current search criterion by clicking on the arrow to the right of the string control, or by using the up and down arrow keys.

Use **Wrap** to continue searching from the beginning of the file once the end of the file has been reached.

The **Case Sensitive** option finds only instances of the specified text which match exactly.

If you select **Regular Expression**, LabWindows/CVI treats certain characters in the search string control as regular expression characters instead of literal characters. The regular expression characters are described in Table 4-1 of the *LabWindows/CVI User Manual*.

Press the **Find** button to perform the search. If any user interface objects are matched, the dialog box is replaced by the one shown in Figure 2-19.




Figure 2-19. Find UIR Objects Dialog Box After a Search Executes

This dialog box allows you to browse through the list of matches. As you come to each object, its callback function name and label are shown, and the object is highlighted.

**Find Prev** searches backward for the previously matched object.

**Find Next** searches for the next matching object.

The **Edit** command terminates the search and brings up the Edit dialog box for the user interface object currently highlighted.

The **Stop** command terminates the search.

#### **Show/Hide Panels**

The **Show/Hide Panels** command has a sub-menu, as shown in the following figure.




Figure 2-20. The Show/Hide Panel Sub-Menu

Use this submenu to select individual panels to view in the User Interface Editor, or to select **Show All Panels** or **Hide All Panels**.

**Bring Panel to Front** command has a submenu that allows you to select a panel from a list to bring to the front for editing.

**Next Panel** brings the next panel in the current .uir file to the front for editing.

**Previous Panel** brings the previous panel in the current .uir file to the front for editing.

#### **Preview User Interface Header File**

The **Preview User Interface Header File** command brings up a Source code window with a preview of the header file that would be associated with the .uir file in the User Interface Editor window if it were saved.

# **Arrange Menu**

This section explains how to use commands in the **Arrange** menu in the User Interface Editor window. Figure 2-21 shows the **Arrange** menu.




Figure 2-21. The Arrange Menu

## Alignment...

The **Alignment** command allows you to align controls on a panel. Use the mouse to select a group of controls by dragging over them or you can <Shift-Click> on each item you want to include in the group. Then you can select an alignment method from the submenu shown in the following figure.




Figure 2-22. The Alignment Menu

- Left Edges vertically aligns the left edges of the selected controls to the left-most control.
- Horizontal Centers vertically aligns the selected controls through their horizontal centers.
- Right Edges vertically aligns the right edges of the selected controls to the right-most control.



**Top Edges** horizontally aligns the top edges of the selected controls to the upper-most control.



Vertical Centers horizontally aligns the selected controls through their vertical centers.



**Bottom Edges** horizontally aligns the bottom edges of the selected controls to the lower-most control.

### **Align Horizontal Centers**

The **Align Horizontal Centers** command performs the same action as the **Alignment** command, using the alignment option last selected in the **Alignment** command submenu.

## Distribution...

The **Distribution** command allows you to distribute controls on a panel. Select a group of controls by dragging the mouse over them or you can <Shift-Click> on each item you want to include in the group. Then you can select a distribution method from the submenu as shown in the following figure.




Figure 2-23. The Distribution Submenu



**Top Edges** sets equal vertical spacing between the top edges of the controls. The uppermost and lower-most controls serve as anchor-points.



**Vertical Centers** sets equal vertical spacing between the centers of the controls. The upper-most and lower-most controls serve as anchor-points.



**Bottom Edges** sets equal vertical spacing between the bottom edges of the controls. The upper-most and lower-most controls serve as anchor-points.



**Vertical Gap** sets equal vertical gap spacing between the controls. The upper-most and lower-most controls serve as anchor-points.



**Vertical Compress** compresses the spacing of controls to remove any vertical gap between the controls.



**Left Edges** sets equal horizontal spacing between the left edges of the controls. The left-most and right-most controls serve as anchor-points.



**Horizontal Centers** sets equal horizontal spacing between the centers of the controls. The left-most and right-most controls serve as anchor-points.



**Right Edges** sets equal horizontal spacing between the right edges of the controls. The left-most and right-most controls serve as anchor-points.



**Horizontal Gap** sets equal horizontal gap spacing between the controls. The left-most and right-most controls serve as anchor-points.



**Horizontal Compress** compresses spacing of the controls to remove any horizontal gap between the controls.

#### **Distribute Vertical Centers**

The **Distribute** command performs the same action as the **Distribution** command according to the option last selected in the **Distribution** command submenu.

#### **Control ZPlane Order**

The **Control Z-Plane Order** option lets you sets the sequence in which controls are drawn. Controls are always drawn in order, from the back to the front of the z-plane order. The **Control ZPlane Order** submenus presents four commands:

- **Move Forward** moves the control one place forward in the z-plane order.
- **Move Backward** moves the control one place backward in the z-plane order.
- Move to Front moves the control to the front of the z-plane order so that it is drawn last.
- Move to Back moves the control to the back of the z-plane order so that it is drawn first.

#### **Center Label**

The Center Label command centers the label of the selected control.

#### **Control Coordinates...**

The **Control Coordinates** command invokes a dialog box allowing you to interactively set the width, height, top, and bottom of all selected controls and labels.

## The Code Menu

Use the commands in the **Code** menu to generate code automatically based on a (.uir) file you are creating or editing. Figure 2-24 shows the **Code** menu.




Figure 2-24. The Code Menu

## Set Target File...

Use the **Set Target File** command to specify to which file LabWindows/CVI generates code. Selecting this command brings up the Set Target File dialog box, shown in Figure 2-25. By default, LabWindows/CVI places the generated code in a new window, unless a source code (.c) file is open. Then, that source file is the default target file. CodeBuilder uses the same target file as the function panel target file, except when the function panel target file is the Interactive Execution window.



Figure 2-25. The Set Target File Dialog Box

To set a target file, select a file from the list of options in the Set Target File dialog box, and then select **OK**. The options include all open source files and a new window.

#### Generate

The commands in the **Generate** menu produce code based on the .uir file. Figure 2-26 shows the **Generate** menu. The code produced by the **Generate** menu uses the bracket styles specified with the **Bracket Styles** command in the Source window's **Options** menu.




Figure 2-26. The Generate Menu

Note: Panel Callback and Control Callbacks are enabled when you select any panel or control for which you have specified a callback function name. All Callbacks is enabled once you have created any object with a callback function name. Menu Callbacks is enabled once you have created a menu bar that contains at least one item with a callback function name.

When you generate code to accompany a .uir file, LabWindows/CVI places the skeleton code in the target file. You must save the .uir file before you can generate any code based on that file. When you save a .uir file, LabWindows/CVI generates a header file (a file with a .h suffix) with the same name. This .h file and userint.h are included in the source file.

If you try to generate the same function more than once, the Generate Code dialog box appears. Figure 2-27 shows the Generate Code dialog box. Each previously generated code fragment appears highlighted. Choose an option in the Generate Code dialog box to replace the existing function, insert a new function, or skip to the next generated function.




Figure 2-27. The Generate Code Dialog Box

#### All Code...

Use the **All Code** command to generate code to accompany the .uir file. Selecting **Code** » **Generate** » **All Code** brings up the Generate All Code dialog box, shown in Figure 2-28. This dialog box displays a checklist and prompts you to choose the panel(s) the main function loads and displays at run time. LabWindows/CVI automatically assigns a default panel variable name for each panel in the .uir file.




Figure 2-28. The Generate All Code Dialog Box

The Generate All Code dialog box also prompts you to choose the callback function(s) that terminate the program. For a CodeBuilder program to terminate successfully, you must include a call to the QuitUserInterface function.

Note: Callback functions associated with close controls are automatically checked in the Program Termination section of the Generate All Code dialog box. You can specify close controls in the Edit Panel dialog box.

To automatically generate all code, select the panels you want to load and display in the user interface. Also select the callback function(s) you want to terminate the program, and then select **OK**.

When you choose **Code** » **Generate** » **All Code**, LabWindows/CVI produces the #include statements, the variable declarations, the function skeletons and the main function, and places them in the target file. The callback function you selected to terminate program execution includes a call to the User Interface Library QuitUserInterface function.

Unless you have selected the **Always Append Code to End** option, LabWindows/CVI places the skeleton code for each callback function at the cursor position in the target file. If the cursor is inside an existing function, LabWindows/CVI repositions the cursor at the end of that function before inserting the new function. CodeBuilder places all functions of one type (panel, control, or menu) together in the source file. Any panel callbacks are placed first in the source file, control callbacks are placed next and menu callbacks are placed last. See the *Preferences* section in this chapter for more details on specifying the location of generated code.

Function skeletons for control and panel callbacks include the complete prototype, the proper syntax, a return value and a switch construct containing a case for each default control or panel event. Function skeletons for menu callbacks include the complete prototype and open and close brackets. You can set the default events by selecting **Code** » **Preferences**. See the *Preferences* section for more details. You can set the location of the open and close brackets by selecting the **Bracket Style** command from the **Options** menu of a Source window.

#### Main Function...

Use the **Main Function** command to generate code for the main function, and write it to the target file. Selecting **Code** » **Generate** » **Main Function** option brings up the Generate Main Function dialog box, shown in Figure 2-29. This dialog box prompts you to choose the panel the main function loads and displays at run time. LabWindows/CVI automatically assigns a default panel variable name for each panel in the .uir file.




Figure 2-29. The Generate Main Function Dialog Box

Note: If you previously selected Code » Generate » All Code command, you do not need to execute this command as well. Only use this command when you want to replace the main callback function to add or change the panels to be loaded at run time.

To automatically generate code for the main function, select the panel(s) you want to load and display in the user interface, and then select **OK**.

When you choose **Code** » **Generate** » **Main Function**, LabWindows/CVI produces the #include statements, the variable declarations, and the main callback function, and places them in the target file.

Note: If the source file contains only the main function and the #include statements, and you have not yet created the appropriate callback functions, you might get an error when trying to run the project. When the main function calls LoadPanel, LabWindows/CVI generates a non-fatal error for each callback function it cannot find in the source file.

The checkbox, **Generate WinMain()** instead of main(), enables you to use WinMain instead of main for your main program. In LabWindows/CVI, you can use either function as your program entry point. When linking your application in an external compiler, it is easier to use WinMain.

If your project target is a DLL, neither WinMain or main are generated. Instead, a DLLMain function is generated. The bulk of the User Interface function calls, however, are generated in a function call InitUIForDLL. You can call InitUIForDLL in your DLL at the point you want to load and display panels.

When you link your executable or DLL in an external compiler, you need to include a call to the InitCVIRTE function in WinMain, main, or DLLMain (or DLLEntryPoint for Borland C/C++). In a DLL, you also need to include a call to CloseCVIRTE. See the Calling InitCVIRTE and CloseCVIRTE section in Chapter 3, Windows 95 and NT Compiler/Linker Issues, in the LabWindows/CVI Programmer Reference Manual.

CodeBuilder automatically generates the necessary calls to InitCVIRTE and CloseCVIRTE in your WinMain, main, or DLLMain function. It also automatically generates a #include statement for the cvirte.h file.

### All Callbacks

Use the **All Callbacks** command to generate code for all the callback functions, and write them to the target file.

When you select **Code** » **Generate** » **All Callbacks**, LabWindows/CVI produces the #include statements and the callback function skeletons, and places them in the target file.

### Panel Callback

Use the **Panel Callback** command to generate code for a panel connected to a callback function. Before you can choose **Code** » **Generate** » **Panel Callback**, you must activate a panel.

When you select **Code** » **Generate** » **Panel Callback**, LabWindows/CVI produces the #include statements and the function skeleton for the active panel, and places them in the target file.

### Control Callbacks

Use the **Control Callbacks** command to generate code for a control connected to a callback function. Before you can choose **Generate** » **Control**, you must select at least one control.

When you select **Code** » **Generate** » **Control Callbacks**, LabWindows/CVI produces the #include statements and the function skeleton for each selected control, and places them in the target file.

You can also generate a control callback function skeleton by clicking on the control with the right mouse button, and selecting the **Generate Control Callback** command from the pop-up menu.

### Menu Callbacks...

Use the **Menu Callbacks** command to generate code for menus and menu items connected to callback functions.

Selecting **Code** » **Generate** » **Menu Callbacks** brings up the Select Menu Bar Objects dialog box. Select the menu bar objects for which you want to generate callbacks, and then select **OK**.

When you select **OK**, LabWindows/CVI produces the #include statements, the function prototypes and the opening and closing brackets for each callback function. No switch construct or case statements are produced because the usual default events do not apply to Menu Callback functions. You must add the code to implement the actions you want to take place when a menu bar item is selected.

#### View

Use the **View** command to look at code for a given callback function. Figure 2-30 shows the **View** menu.




Figure 2-30. The View Menu

To view the code for a function from the .uir file, select a panel or control and then select **View » Panel Callback** or **View » Control Callback**. The source file containing the callback function appears with the function name highlighted. You can also view the code for a control callback function by clicking on the control with the right mouse button, and selecting the **View Control Callback** command from the pop-up menu.

When you choose the **View** command for a callback function, LabWindows/CVI searches for that function in all open Source windows and in all the source files in the project, and in any other open source files. If the function is found in a closed project file, that file is opened automatically.

The **View** command is useful because the callback functions for one user interface can be in several different files, and scrolling the source code is not efficient. With the **View** command, you can move instantly from the user interface file to an object's callback function whether the source file is open or closed.

When you are finished reviewing the code, you can return instantly to the .uir file from the source file. To return to the .uir file, place the cursor on the callback function name or constant name of the User Interface object you want to go to, and select the **Find UI Object** command from the **View** menu in the Source window.

Note: You cannot use the View command for Menu Callback functions.

#### **Preferences**

Use the **Preferences** command to change the default settings for case statements generated for control callback functions and panel callback functions or to specify the target file location for generated code. Figure 2-31 shows the **Preferences** submenu.




Figure 2-31. The Preferences Menu

### Default Panel Events... and Default Control Events...

Use the **Default Panel Events** or **Default Control Events** commands to select which events LabWindows/CVI places into the switch construct of the code for panel or control callback functions, respectively. You can choose from several events, and you can choose to add the "default:" switch case. Selecting **Code** » **Preferences** » **Default Panel Events** brings up the Panel Callback Events dialog box. Selecting **Code** » **Preferences** » **Default Control Events** brings up the Control Callback Events dialog box.

To set the **Default Panel Events** or **Default Control Events**, select the events you want to be included in the code as case statements, and then select **OK**. For each option you choose, LabWindows/CVI includes a case statement that corresponds to this option in the source code.

Note: Default control events are ignored for Timer Control Callbacks, whose only event cases are EVENT\_TIMER\_TICK and EVENT\_DISCARD.

### Always Append Code to End

When this option is selected, LabWindows/CVI places the skeleton code for each callback function at the end of the target file. When this option is not selected, newly generated code is placed at the current position of the cursor in the target file.

### Run Menu

The Run Menu contains a subset of the commands that appear in the Run Menu of the source window. The commands are:

Run Project Step Into Break at First Statement

Continue Finish Function Breakpoints

**Step Over** Terminate Execution

Refer to the *LabWindows/CVI User Manual*, Chapter 4, *Source, Interactive Execution, and Standard Input/Output Windows*, in the *Run Menu* section for descriptions of each of these commands.

### **Library Menu**

The **Library** menu for the User Interface Editor Window works the same way as the Library menu in the Project Window. See the *LabWindows/CVI User Manual*, Chapter 3, *Project Window*, for information on the **Library** menu.

### Window Menu

The **Window** menu in User Interface Editor windows behaves like the **Window** menu in the Project window. See the *LabWindows/CVI User Manual*, Chapter 3, *Project Window*, for information on the Window menu.

### **Options Menu**

This section explains how to use the commands in the **Options** menu. Figure 2-32 shows the **Options** menu.




Figure 2-32. The Options Menu

### **Operate Visible Panels**

**Operate Visible Panels** allows you to operate the visible panels as you would in an application program. This command has the same effect as clicking on the icon. When you finish operating the panel, select **Operate Visible Panels** again to return to edit mode.

### **Next Tool**

The **Next Tool** command in the **Options** menu cycles the User Interface Editor through three of its four modes: editing mode , labeling mode , and coloring mode .

#### Preferences...

Selecting **Preferences** brings up the User Interface Editor Preferences dialog box, as shown in the following figure.




Figure 2-33. The User Interface Preferences Dialog Box

#### **Undo Preferences**

Use the Undo Preferences section of the User Interface Editor Preferences dialog box to set the number of undo-able actions for each file. Select the **Purge undo actions when saving file** check box if you want the Undo buffer to empty every time you save a file.

### **Color Preferences**

Use the Color Preferences section of the User Interface Editor Preferences dialog box to set the default editor and panel colors.

### **Constant Name Assignment**

Constant names link user GUI objects and your program. The User Interface Editor writes all assigned constant names to a header file corresponding to the loaded .uir file.

The Constant Name Assignment section of the User Interface Editor Preferences dialog box allows you to set preferences for constant name assignment, when you do not assign constant names yourself.

When the "Immediately assign constant names for new objects" option is in effect, the User Interface Editor generates constant names for each object as you create it. For panels and controls, the generated constant name appears in the edit dialog the first time you bring it up. For menu bars, the constant names are assigned only when you exit the menu bar editor. In all cases, you can freely modify the generated constant names.

It is recommended that you leave the "Immediately assign constant names for new objects" option in effect. This makes it easier for you to use the other LabWindows/CVI features that have been designed to help you write your program to operate your user interface.

Notice that when the "Immediately assign constant names for new objects" option is enabled, the "Assign constant names from user-defined control labels when possible" option has no effect. That is because the control labels have not been changed from the default "Untitled Control" label at the time the constant name is generated. Instead, the constant name is based on the control type.

If you choose to disable the "Immediately assign constant names for new objects" option, it is recommended that you enable the "Fill in missing constant names when saving" option.

### **Assign Missing Constants...**

The Assign Missing Constants command assigns constant names to all of the objects in the User Interface Editor Window that currently do not have constant names. A confirmation dialog appears showing the number of items that have no constant names.

### **Save In Text Format**

The Save In Text Format command saves the contents of the User Interface Editor Window in a ASCII text format. A dialog box appears prompting you to enter the pathname under which to save the text file. The extension . tui is recommended for such files. Do NOT use the .uir extension.

The ASCII text file contains descriptions of all the objects in the User Interface Editor Window.

Note: If you have a large number of objects in your User Interface Editor Window, this command may take a significant amount of time to complete (for example, 3 minutes).

### **Load From Text Format...**

The Load From Text Format command loads into a new User Interface Editor Window the objects defined in a file saved using the Save In Text Format command. A dialog box appears prompting you for the pathname of the file.

# Chapter 3

# **Programming with the User Interface Library**

This chapter describes how to use the User Interface Library in the application programs you create.

# **Developing and Running a Program**

Although there are many ways to develop your projects in LabWindows/CVI, you may want to use the following development pattern.

- 1. Open a User Interface Editor window to design a user interface for your program.
- 2. Assign constant names and/or callback functions to each control on your GUI.
- 3. Save your GUI as a user interface (.uir) file (the program automatically generates a corresponding .h include file). If you use CodeBuilder, LabWindows/CVI creates skeleton code for your source file. See the *CodeBuilder Overview* section of Chapter 2, *User Interface Editor Reference*, for more information.
- 4. Open a Source window to develop your C Language program to control the GUI.
- 5. Add the source code (.c), include (.h), and user interface (.uir) files to your project list and save as a project (.prj) file.

If you are editing the program and .uir file concurrently, you must recompile your program every time you save the .uir file. This is required because the contents of the include file generated by the User Interface Editor might change. You can make recompiling automatic by enabling the **Track Include File Dependencies** command in the **Options** menu of the Project Window. If the .uir files and image files do not contain absolute paths in the LoadMenuBar, LoadPanel, or DisplayImageFile functions, the User Interface Library will search for them in the following order.

- 1. The directory associated with the .uir or image file in the project.
- 2. The directory containing the project.

It is good practice to add your .uir and image files to the project list or save the resource files and image files in the directory that contains your project file. If you use the latter approach, your program should not contain absolute path names in the LoadMenuBar, LoadPanel or DisplayImageFile functions.

# **Creating a Graphical User Interface**

As discussed in the *Introduction to the Graphical User Interface* section of Chapter 1, *User Interface Concepts*, there are two ways to create Graphical User Interface (GUI) objects for your application program. You can create objects programmatically using function calls or interactively using the User Interface Editor.

Once you create a GUI, you can control the objects in two ways. You can assign callback functions to GUI objects. When any type of event is generated on a panel, menu, or control, the appropriate callback function executes. Alternatively, you can use an event loop that includes a call to GetUserEvent. When a commit event is generated, GetUserEvent returns the appropriate panel, menu, or control identifier, and the program conditionally executes portions of code. You can use either technique or you can combine them for added flexibility.

Naturally, one of your most important tasks in designing a GUI is to assign callback functions and IDs to every interface object.

### If you design your GUI in the User Interface Editor...

You assign callback functions and unique IDs (constant names) to objects and LabWindows/CVI automatically saves their declarations in an include file whenever you save the resource file. You must include this file in your application program using the #include preprocessor command. The #include directive allows the program to reference the resource IDs and callback functions for the user interface objects. Panel and menu bar handles are assigned at run time when you use the LoadPanel and LoadMenuBar functions.

Note: With the LabWindows/CVI Code Builder, you can create automatically complete C code that compiles and runs based on a user interface (.uir) file you are creating or editing. See the Code Builder Overview section of Chapter 2, User Interface Editor Reference, for more information.

### If you design your GUI programmatically...

Assign panel and menu bar handles with the NewPanel, and NewMenuBar functions. Assign IDs using the NewCtrl, NewMenu, NewSubMenu, and NewMenuItem functions. Assign callback functions through functions such as InstallPanelCallback, InstallCtrlCallback, and InstallMenuCallback.

## **Assigning Constant Names in the User Interface Editor**

The following rules apply when you use the User Interface Editor to assign constant names to panels and controls.

• You must assign a constant prefix to the panel. Panel constant prefixes can be up to 10 characters long and must be unique with respect to all other panel and menu bar constant

prefixes in the same resource file. Your application program references the prefix when it loads the panel from the resource file.

You may assign a constant name to each control. Control constant names can be up to 20 characters long and must be unique with respect to all other control constants defined for the same panel. The name is concatenated to the panel prefix to generate a unique constant name. For example, if the panel prefix is SCOPE and the control prefix is POWER, the complete constant name would be SCOPE\_POWER. The application program uses the complete constant name to reference the control.

The following rules apply when assigning constant names to menu bars in the User Interface Editor.

- You must assign a constant prefix to the menu bar. The prefix can be up to 10 characters long and must be unique with respect to all other panel and menu bar prefixes that you store together in a resource file. Your application program references the prefix to load the menu bar from the resource file.
- You may assign a constant prefix to each menu. The prefix can be up to 10 characters long and must be unique with respect to all other menu prefixes in the same menu bar. The program concatenates the constant prefix and the menu bar prefix to generate a unique constant name. For example, if the menu bar prefix is MAIN and the menu prefix is FILE, the complete constant name is MAIN\_FILE. Your application program uses the complete constant name to reference the menu.
- You may assign a constant name to each menu item. Menu item constant names can be up to 10 characters long and must be unique with respect to all other menu item constants in the same menu. The program concatenates the menu bar prefix and the menu prefix to generate a unique constant name. For example, if the menu bar prefix is MAIN, the menu prefix is FILE, and the menu item name is LOAD, the complete constant name is MAIN\_FILE\_LOAD. Your application program uses the complete constant name to reference the menu item.

The User Interface Editor automatically inserts the constant name separator (\_) when it generates the include file.

Note: When you use submenus, all identifiers starting with the menu bar prefix are concatenated. Choose brief identifiers so that constant names remain as short as possible.

# **Controlling a Graphical User Interface**

Certain user operations on the GUI, such as selecting a menu item on the GUI or typing a value, are called *events*. The User Interface Library provides the link between events and the code files in your project.

### **User Interface Events**

Your program can recognize events and execute the code in response to them. Table 3-1 shows all of the events that are generated from the GUI and the information that is passed to the program at event time.

Table 3-1. User Interface Events

<b>Event Type</b>	<b>Event on the GUI</b>	Information Passed to Program
control and menu event	EVENT_COMMIT	Which panel or menu bar, which control or menu item.
control event	EVENT_VAL_CHANGED	Which panel, which control.
control and panel event	EVENT_LEFT_CLICK	Which panel, which control, mouse y & x coordinates.
	EVENT_LEFT_DOUBLE_CLICK	Which panel, which control, mouse y & x coordinates.
	EVENT_RIGHT_CLICK	Which panel, which control, mouse y & x coordinates.
	EVENT_RIGHT_DOUBLE_CLICK	Which panel, which control, mouse y & x coordinates.
	EVENT_KEYPRESS	Which panel, which control, key code, pointer to key code.
	EVENT_GOT_FOCUS	Which panel, which control
	EVENT_LOST_FOCUS	Which panel, which control.
	EVENT_DISCARD	Which panel, which control.
timer control event	EVENT_TIMER_TICK	Pointer to the current time (double *), pointer to time since the callback last received an EVENT_TIMER_TICK (double *).
panel event	EVENT_CLOSE	Which panel.
	EVENT_PANEL_SIZE	Which panel.
	EVENT_PANEL_MOVE	Which panel.
main	EVENT_IDLE	Obsolete. Use timer controls instead.
callback event	EVENT_END_TASK	Microsoft Windows only. Received when Windows wants to quit. (Return a non-zero value to abort the termination.)

### **Using Callback Functions to Respond to User Interface Events**

Callback functions respond to all events listed in Table 3-1. Callback functions have prototypes (found in userint.h) for panels, menu bars, controls, or the main callback. When the user generates an event on a particular user interface object, the appropriate callback function executes. Idle events and end-task events are passed to the main callback function only. (See the discussion of InstallMainCallback in the *Special User Interface Functions* section of Chapter 3, *Programming With the User Interface Library*. Event information is passed automatically from the GUI to your program through callback functions whenever they are called. For example, callback functions are passed the user interface event type that occurred (such as EVENT\_LEFT\_CLICK), and some additional information concerning that event (such as the x and y-coordinates of the mouse cursor when the click occurred). You, as the developer of these callback functions, are free to use this information as needed when responding to events.

Callback functions are introduced in the tutorial in the *Getting Started with LabWindows/CVI* manual. Many of the sample programs described in Chapter 5, *LabWindows/CVI Sample Programs*, illustrate callback functions, too. The following diagram and example pseudo-code illustrates the callback function concept.




Figure 3-1. The Callback Function Concept

```
panel_handle = LoadPanel(...)
DisplayPanel(panel_handle, ...);
menu_handle = LoadMenuBar(...);
RunUserInterface()
int CVICALLBACK PanelResponse (int handle, int event, void *callbackdata,
                               int eventdata1, int eventdata2)
   switch (event) {
      case EVENT_PANEL_SIZE :
                 /* Code that responds to the panel
                  /* being resized
         break;
      case EVENT_PANEL_MOVE :
                  /* Code that responds to the panel
                  /* being moved
         break;
      case EVENT_KEYPRESS :
                  /* Code that responds to a keypress */
                  /* eventdata1 & eventdata2 contain
                  /* keycode information
         break;
      return(0);
int CVICALLBACK ControlResponse (int handle, int control, int event,
                                 void *callbackdata, int eventdata1,
                                 int eventdata2)
   if (control == PANEL_CONTROL1) {
      switch (event) {
         case EVENT RIGHT CLICK :
                  /* Code that responds to a right
                  /* click on CONTROL1
            break;
         case EVENT_VAL_CHANGED :
                  /* Code that responds to a value
                  /* change on CONTROL1
            break;
         case EVENT COMMIT :
                  /* Code that responds to a commit
                  /* event on CONTROL1
            break;
      }
   }
   if (control == PANEL_CONTROL2) {
      switch (event) {
         case EVENT_RIGHT_CLICK :
                  /* Code that responds to a right
                  /* click on CONTROL2
            break;
         case EVENT_COMMIT :
                  /* Code that responds to a commit
                  /* event on CONTROL2
            break;
      }
  return(0);
```

Note: If you assign callback functions to your GUI objects using the User Interface Editor, these functions are automatically installed through LoadPanel and LoadMenuBar. Otherwise, you will need to install them programatically through the Install functions (InstallPanelCallback, InstallCtrlCallback, InstallMenuCallback, and others).

Note: Do not call the longjmp function from within a callback function.

The CVICALLBACK macro should precede the function name in the declarations and function headers for all user interface callbacks. This ensures that the functions are treated by the compiler as cdecl (or stack-based in WATCOM), even when the default calling convention is stdcall. CVICALLBACK is defined in cvidefs.h, which is included by userint.h. The CVICALLBACK macro is included where necessary in the header files generated by the User Interface Editor and in source code generated by CodeBuilder.

For detailed information about the user interface callback functions, see the descriptions of PanelCallbackPtr, CtrlCallbackPtr, MenuCallbackPtr, MenuCallbackPtr, MenuDimmerCallbackPtr, MainCallbackPtr, and DeferredCallbackPtr in Chapter 4, *User Interface Library Reference*.

### Using GetUserEvent to Respond to User Interface Events

The GetUserEvent function returns only commit events (with the exception of programmer-defined events posted through QueueUserEvent). Commit events are generated when the user of the GUI actually commits to an operation such as making a menu selection or typing in a menu selection or typing in a number and pressing <Enter>. The following figure illustrates the event-loop concept of GetUserEvent.




Figure 3-2. The Event Loop Concept

A typical program could use a GetUserEvent loop with the following pseudocode algorithm.

You should read the remainder of this chapter and Chapter 3, *Programming with the User Interface Library*, before attempting to develop a program with the User Interface Library. You should also examine and execute the example programs outlined in Chapter 5, *LabWindows/CVI Sample Programs*. These examples are designed to illustrate the concepts presented in Chapters 1 and 3.

# **Programming with Panels**

This section describes how you can use the User Interface Library functions to control the elements of user interface panels.

### **Panel Functions**

Use LoadPanel to load a panel from a resource file created in the User Interface Editor into memory. When LoadPanel loads a panel from a resource file, it references the panel using the constant name that you assigned to the panel in the User Interface Editor. LoadPanel returns a handle that you use in subsequent User Interface Library functions to reference the panel. Use the first parameter of LoadPanel to specify whether the panel loads as a top-level window or as a child of another (parent) window. Loading a panel does not automatically display the panel.

Use NewPanel to create a new panel during program execution. NewPanel returns a handle that you use in subsequent User Interface Library functions to reference the panel. Use the first parameter of NewPanel to specify whether the panel is created as a top-level window or as a child of another (parent) window. You also specify the name, position, and size of the panel through parameters to NewPanel. Creating a new panel using NewPanel does not automatically display the panel.

Use DuplicatePanel to create a new panel that is a duplicate of a panel loaded by LoadPanel or created by NewPanel. DuplicatePanel returns a handle you use to reference the panel in subsequent operations. Use the first parameter of DuplicatePanel to specify whether the panel is created as a top-level window or as a child of another (parent)

window. You also specify the name and position of the panel through parameters to DuplicatePanel. Creating a new panel using DuplicatePanel does not automatically display the panel.

Use DisplayPanel to display a panel. When a panel is visible and enabled, the user can operate it. Calling DisplayPanel when a panel is already displayed causes the panel to be completely redrawn.

Use HidePanel to hide a panel. When a panel is hidden, it can still be updated. For example, you can add plots to a graph control on a hidden panel. When the panel is redisplayed, it will show the new plots. A hidden panel cannot generate events.

Use DefaultPanel to restore all panel controls to their default values. If the panel is visible, it is updated to reflect the new control values. You assign default values to controls in the User Interface Editor or through the SetCtrlAttribute function using ATTR\_DFLT\_VALUE.

Use GetActivePanel to obtain the handle of the currently active panel.

Use SetActivePanel to make a particular panel active when multiple panels are visible.

Use GetPanelAttribute to obtain a particular attribute of a panel. The *Panel Attributes* section of this chapter lists panel attributes.

Use SetPanelAttribute to set a particular attribute of a panel. The *Panel Attributes* section of this chapter lists panel attributes.

Use SetPanelPos to change the position of a panel on the screen. If the panel is visible, it is redrawn in its new position.

Use SavePanelState to save the state of a panel to a file on disk. SavePanelState saves the state of every control, including the plot data in graphs and strip charts and the current items in selection lists.

Use RecallPanelState to recall a state file from disk to a panel. Every control on the panel is set to the value stored in the state file. You must recall the state file to the same panel from which it was saved.

Use DiscardPanel to remove a panel from memory. If the panel is visible, it is removed from the screen.

### **Role of Child Panels**

You can configure the LoadPanel function so that panels appear within other panels in your user interface. When you do this, the principal panel is called the parent panel; panels within are child panels. Child panels can appear within other child panels, too.

A child panel helps developers control the appearance of the user interface. Users cannot drag a child panel outside its parent panel. And if users shrink a parent panel, a child panel may be partially or completely hidden in the shrunken panel view.

### **Processing Panel Events**

If you need to process events such as mouse clicks, panel moves, or panel sizing, you must assign a callback function to the panel. When an event is generated on the panel, the panel callback function executes. To process events generated on the controls of the panel, see the *Programming with Controls* section of this chapter.

If you create your panel in the User Interface Editor, you can assign a callback function name to the panel from within the editor. When you load the panel with LoadPanel, LabWindows/CVI automatically installs your callback function and calls it whenever an event is generated on the panel.

If you create your panel programmatically using the NewPanel function, you can install a callback function for the panel using InstallPanelCallback. Your callback function is called whenever an event is generated on the panel. You should use the PanelCallbackPtr typed from userint.h as a model to declare your panel callback function.

Callbacks must be initiated through a call to RunUserInterface or through a GetUserEvent loop.

### **Panel Attributes**

Table 3-2 lists panel attributes that you can retrieve or change through GetPanelAttribute and SetPanelAttribute.

Table 3-2. Panel Attributes

Name	Type	Description
ATTR_ACTIVE	int	Indicates whether the panel or one of its child panels is the active panel.  (GetPanelAttribute only.)
ATTR_ACTIVATE_WHEN_CLICKED_ ON	int	1 = child panel is made the active panel when clicked on 0 = child panel is not made the active panel when clicked on
ATTR_BACKCOLOR	int	RGB value—See discussion following this table.
ATTR_CALLBACK_DATA	void *	A pointer to user data that is passed to the panel callback function
ATTR_CALLBACK_FUNCTION_ POINTER	void *	A pointer to the callback function for the panel.
ATTR_CALLBACK_NAME	char *	The name of the callback function associated with the panel. (GetPanelAttribute only.)
ATTR_CALLBACK_NAME_LENGTH	int	The number of characters in the name of the panel callback. (GetPanelAttribute only.)
ATTR_CAN_MAXIMIZE	int	1 = you can maximize the top-level panel 0 = you cannot maximize the top-level panel (Windows only)
ATTR_CAN_MINIMIZE	int	1 = you can minimize the top-level panel 0 = you cannot minimize the top-level panel (Windows only)
ATTR_CLOSE_CTRL	int	control ID that receives commit events when a user selects the Close command in the System Menu (Top-level panels only.)
ATTR_CLOSE_ITEM_VISIBLE	int	Specify whether the panel Close item is available in the top-level panel.  0 = Dimmed Close Item  1 = Enable Close Item  (Windows only)

Table 3-2. Panel Attributes (Continued)

Name	Type	Description
ATTR_CONFORM_TO_SYSTEM	int	Specifies whether the panel and its controls use the system colors. Subsequent new controls also use the system colors. (This is useful only on Windows 95. Other platforms always use panel gray and black as the system colors.)
ATTR_CONSTANT_NAME	char *	The constant name assigned to the panel in the User Interface Editor. (GetPanelAttribute only.)
ATTR_CONSTANT_NAME_LENGTH	int	The number of characters in the constant name of the panel. (GetPanelAttribute only.)
ATTR_DIMMED	int	1 = panel disabled 0 = panel enabled
ATTR_FIRST_CHILD	int	The first child panel for the parent panel. (GetPanelAttribute only.)
ATTR_FLOATING	int	Specifies whether the panel floats above all non-floating panels. Applies to top-level panels in Microsoft Windows.
ATTR_FRAME_COLOR	int	RGB value—See discussion following this table. (Child panels only.)
ATTR_FRAME_STYLE	int	The frame style of the panel. (Child panels only.)
ATTR_FRAME_THICKNESS	int	Thickness of panel frame. range = 1 to 10 (see Figure 3-3) (Child panels only.)
ATTR_HEIGHT	int	Height of panel, range = 1 to 32767 (see Figure 3-3)
ATTR_HSCROLL_OFFSET	int	The offset of the horizontal scroll bar (in pixels)
ATTR_HSCROLL_OFFSET_MAX	int	The number of pixels you have to scroll to reach the right edge of the right-most object on the panel (GetPanelAttribute only)

Table 3-2. Panel Attributes (Continued)

Name	Type	Description
ATTR_LEFT	int	Left position of panel, range = 1 to 32767 or VAL_AUTO_CENTER (see Figure 3-3)
ATTR_MENU_BAR_VISIBLE	int	1 = menu bar visible 0 = menu bar invisible
ATTR_MENU_HEIGHT	int	Height of menu bar, range = 1 to 32767 (See Figure 3-3.) (GetPanelAttribute only)
ATTR_MOUSE_CURSOR	int	The mouse cursor style. (See Table 3-4.)
ATTR_MOVABLE	int	1 = movable panel 0 = immovable panel (child panels only)
ATTR_NEXT_PANEL	int	The next child panel for the parent panel (GetPanelAttribute only.)
ATTR_NUM_CHILDREN	int	The number of child panels for the parent panel. (GetPanelAttribute only.)
ATTR_NUM_CTRLS	int	The number of controls on the panel (GetPanelAttribute only).
ATTR_PANEL_FIRST_CTRL	int	The first control on the panel. (GetPanelAttribute only.)
ATTR_PANEL_MENU_BAR_CONSTANT	char *	The menubar control ID name for the panel. (GetPanelAttribute only.)
ATTR_PANEL_MENU_BAR_CONSTANT_ LENGTH	int	The number of characters in the menubar control ID name. (GetPanelAttribute only.)
ATTR_PANEL_PARENT	int	The panel constant ID of the parent of the child panel. (GetPanelAttribute only.)
ATTR_PARENT_SHARES_SHORTCUT_ KEYS	int	1 = share shortcut keys 0 = do not share shortcut keys
ATTR_SCROLL_BAR_COLOR	int	RGB value—See discussion following this table.

Table 3-2. Panel Attributes (Continued)

Name	Type	Description
ATTR_SCROLL_BARS	int	VAL_NO_SCROLL_BARS or VAL_HORIZ_SCROLL_BAR or VAL_VERT_SCROLL_BAR or VAL_BOTH_SCROLL_BARS
ATTR_SIZABLE	int	1 = panel sizable 0 = panel not sizable (Child panels only)
ATTR_SYSTEM_MENU_VISIBLE	int	1 = The system menu is visible 0 = The system menu is not visible
ATTR_SYSTEM_WINDOW_HANDLE	int	Returns a number that can be cast to obtain the system specific window handle for a top-level window. (GetPanelAttribute only—see following discussion)
ATTR_TITLE	char *	The title of the panel
ATTR_TITLE_BACKCOLOR	int	RGB value—See discussion following this table. (Child panels only.)
ATTR_TITLE_BOLD	int	1 = title is bold 0 = title is not bold (Child panels only.)
ATTR_TITLE_COLOR	int	RGB value—See discussion following this table. (Child panels only.)
ATTR_TITLE_FONT	char *	The font of the panel title (see Table 3-5) (Child panels only.)
ATTR_TITLE_FONT_NAME_LENGTH	int	Number of characters in the name of the title font (GetPanelAttribute only) (Child panels only.)
ATTR_TITLE_ITALIC	int	<ul><li>1 = title in italics</li><li>0 = title not in italics</li><li>(Child panel only.)</li></ul>
ATTR_TITLE_LENGTH	int	The number of characters in panel title (GetPanelAttribute only).
ATTR_TITLE_POINT_SIZE	int	Point size of the title range = 1 to 32767

Table 3-2. Panel Attributes (Continued)

Name	Type	Description	
ATTR_TITLE_SIZE_TO_FONT	int	Specify whether the child panel title is sized to the font.  0 = not sized  1 = sized	
ATTR_TITLE_STRIKEOUT	int	<ul><li>1 = title has strikeout</li><li>0 = title does not have strikeout</li><li>(Child panels only.)</li></ul>	
ATTR_TITLE_UNDERLINE	int	<ul><li>1 = title underlined</li><li>0 = title not underlined</li><li>(Child panels only.)</li></ul>	
ATTR_TITLEBAR_THICKNESS	int	Thickness of panel title bar, range = 1 to 32767 (see Figure 3-3) (Child panels only.)	
ATTR_TITLEBAR_VISIBLE	int	<ul><li>1 = title bar visible</li><li>0 = title bar invisible</li></ul>	
ATTR_TOP	int	Top position of panel, range = 1 to 32767 or VAL_AUTO_CENTER. (See Figure 3-3.)	
ATTR_VISIBLE	int	<ul><li>1 = panel visible</li><li>0 = panel invisible</li></ul>	
ATTR_VSCROLL_OFFSET	int	The offset of the vertical scroll bar (in pixels)	
ATTR_VSCROLL_OFFSET_MAX	int	The number of pixels you have to scroll to reach the bottom edge of the lowest object on the panel .(GetPanelAttribute only)	
ATTR_WIDTH	int	The width of the panel in pixels. Valid range: 0 to 32767.	
ATTR_WINDOW_ZOOM	int	VAL_MAXIMIZE, VAL_MINIMIZE, or VAL_NO_ZOOM (Windows only—See following discussion.)	
ATTR_ZPLANE_POSITION	int	The drawing order of the panel. The lowest ordered control (0) is on top. Valid Range: 0 to (Number of Panels – 1) (For child panels only.)	

#### **Panel Attribute Discussion**

ATTR CAN MAXIMIZE, ATTR CAN MAXIMIZE, and ATTR CLOSE ITEM VISIBLE are only implemented for top level windows on Windows. Setting these attributes on child panels or on top level XWindows panels has no effect and does not return errors.

ATTR\_SYSTEM\_WINDOW\_HANDLE returns an integer that can be cast to obtain the system specific window handle for a panel. The attribute returns 0 for child panels. The actual type of the value is HWND on Windows, and Window on XWindows. Setting another panel attribute (example: ATTR\_TITLEBAR\_VISIBLE) may cause the value of ATTR SYSTEM WINDOW HANDLE to change since the panel has to destroy and recreate its window to change certain attributes. Installing and uninstalling a panel as a pop-up can also change the window handle. So, obtain the window handle again after taking any of these actions.

ATTR\_WINDOW\_ZOOM is only implemented for top level windows on Windows. Setting it on a child panel or on a top level XWindows panel has no effect and does not return an error.

Setting the ATTR\_WINDOW\_ZOOM attribute automatically makes the panel visible. If the attribute is set to VAL NO ZOOM or VAL MAXIMIZE, the panel is activated. If the attribute is set to VAL\_MINIMIZE, the panel is deactivated. Making the panel invisible automatically resets the ATTR\_WINDOW\_ZOOM attribute to VAL\_NO\_ZOOM.

An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. Common colors appear in the following table. The first sixteen colors listed are the sixteen standard colors.

Table 3-3. Common Color Values

Value	Code
VAL_RED	0xFF0000L
VAL_GREEN	0x00FF00L
VAL_BLUE	0x0000FFL
VAL_CYAN	0x00FFFFL
VAL_MAGENTA	0xFF00FFL
VAL_YELLOW	0xFFFF00L
VAL_DK_RED	0x800000L
VAL_DK_BLUE	0x000080L
VAL_DK_GREEN	0x008000L
VAL_DK_CYAN	0x008080L
VAL_DK_MAGENTA	0x800080L

Value	Code
VAL_DK_YELLOW	0x808000L
VAL_LT_GRAY	0xCCCCCCL
VAL_DK_GRAY	0x808080L
VAL_BLACK	0x000000L
VAL_WHITE	0xffffffL
VAL_PANEL_GRAY	0xCCCCCCL
VAL_GRAY	0xA0A0A0L
VAL_OFFWHITE	0xE5E5E5L
VAL TRANSPARENT	0×1000000T

Table 3-3. Common Color Values (Continued)

You can also use the User Interface Library function, MakeColor, to create an RGB value from red, green, and blue color components.

The following list presents ATTR\_FRAME\_STYLE values.

VAL\_OUTLINED\_FRAME
VAL\_BEVELLED\_FRAME
VAL\_RAISED\_FRAME
VAL\_HIDDEN\_FRAME
VAL\_STEP\_FRAME
VAL\_RAISED\_OUTLINE\_FRAME

To see the different panel frame styles, edit a panel in the User Interface Editor and select the various frame styles.

Figure 3-3 shows the geometric attributes of a panel.




Figure 3-3. The Geometric Attributes of a Panel

Note: Always set ATTR\_FRAME\_STYLE before setting ATTR\_FRAME\_THICKNESS.

Table 3-4 lists the values and cursor styles corresponding to ATTR\_MOUSE\_CURSOR.

Table 3-4. Values and Cursor Styles for ATTR\_MOUSE\_CURSOR

Value	<b>Cursor Style</b>
VAL_DEFAULT_CURSOR	13
VAL_CHECK_CURSOR	_
VAL_CROSS_HAIR_CURSOR	+
VAL_BOX_CURSOR	
VAL_POINTING_FINGER_CURSOR	4pJ
VAL_OPEN_HAND_CURSOR	ξ <sup>ιη</sup> γ
VAL_QUESTION_MARK_CURSOR	?
VAL_HOUR_GLASS_CURSOR	$\overline{\mathbb{Z}}$
VAL_HIDDEN_CURSOR	
VAL_SIZE_NS_CURSOR	$\mathfrak{F}$
VAL_SIZE_EW_CURSOR	↔
VAL_SIZE_NW_SE_CURSOR	<b>⊘</b>
VAL_SIZE_NE_SW_CURSOR	S

Table 3-5 lists valid font values.

Table 3-5. Font Values

Туре	Value	
Platform independent fonts	VAL_MENU_FONT	
	VAL_MESSAGE_BOX_FONT	
	VAL_DIALOG_FONT	
	VAL_EDITOR_FONT	
	VAL_APP_FONT	
Platform independent metafonts	VAL_MENU_META_FONT	
	VAL_MESSAGE_BOX_META_FONT	
	VAL_DIALOG_META_FONT	
	VAL_EDITOR_META_FONT	
	VAL_APP_META_FONT	
LabWindows/CVI supplied	VAL_7SEG_META_FONT	
metafonts	VAL_SYSTEM_META_FONT	
Host fonts	See discussion following this table.	
User-defined metafonts	See discussion following this table.	

### **Platform Independent Fonts That Are Resident on PCs and UNIX**

These fonts contain typeface information only and use typefaces native to each platform supported by LabWindows/CVI. LabWindows/CVI uses VAL\_MESSAGE\_BOX\_META\_FONT for message boxes. Under Windows 95, this font is for message boxes. On other platforms, this font is the same as VAL\_DIALOG\_META\_FONT.

### Platform-Independent Metafonts That Are Resident on PCs and UNIX

Metafonts contain typeface information, point size, and text styles such as bold, underline, italic, and strikeout. The platform independent metafonts listed in Table 3-5 use typefaces that are native to each platform. They have been designed so that the height and width of the font is as similar as possible across platforms. These metafonts are used in the LabWindows/CVI environment. VAL\_MENU\_META\_FONT is bold and is used for menu and menu item names. VAL\_DIALOG\_META\_FONT is bold and is used for labels in dialog boxes and function panels.

VAL\_EDITOR\_META\_FONT is a monospaced metafont that is the default font in the Source windows. VAL\_APP\_META\_FONT is a smaller, non-bold alternative to VAL\_DIALOG\_META\_FONT and is the default font in the Project window.

### Metafonts Supplied by LabWindows/CVI

These metafonts are included in LabWindows/CVI, but use typefaces that are not native to PC or UNIX systems. VAL\_7SEG\_META\_FONT provides compatibility with LabWindows for DOS. VAL\_SYSTEM\_META\_FONT provides compatibility with function panel help text and user interface panels from LabWindows for DOS that use extended IBM PC characters. Although the extended IBM characters are provided, their use is discouraged since other fonts do not contain them. (Cut/Paste operations with extended IBM characters fail across applications that use other fonts.)

#### **Host Fonts**

In addition to the fonts provided with LabWindows/CVI, you can use any host font supported on your system. For example, Arial, Courier, and Roman are available under Windows.

Note: When you change the font and point size of text, always set the font before setting the point size or style attributes.

### **User Defined Metafont**

You can create metafonts with the CreateMetaFont function. You can then apply the metafont to any control or panel attribute that takes a font value. The typeface, point size, and text styles defined by the metafont are all set at once. In addition, the PlotText and GetTextDisplaySize functions require a metafont as an input parameter.

# **Programming with Menu Bars**

This section describes how to use User Interface Library functions to control the elements of user interface menu bars.

### **Menu Bar Functions**

Use LoadMenuBar to load a menu bar from a resource file created in the User Interface Editor and display it on a panel. When LoadMenuBar loads a menu bar from a resource file, it references the menu bar using the constant name that you assigned to the menu bar in the User Interface Editor. LoadMenuBar returns a handle that you use in subsequent User Interface Library functions to reference the menu bar. After a menu bar has been loaded, it generates a user event whenever the user selects a menu bar command. Refer to the *Processing Menu Bar Events* section of this chapter for additional information.

Use NewMenuBar to create a new menu bar during program execution. NewMenuBar returns a handle that you use to reference the menu bar in subsequent operations. Use the single parameter of NewMenuBar to specify the panel on which you want to locate the menu bar. Use NewMenu, NewSubMenu, and NewMenuItem to construct the pull-down menu system.

Use SetPanelMenuBar to assign a menu bar to a panel. You can assign a single panel only one menu bar at a time. Multiple panels can share the same menu bar.

Use GetPanelMenuBar to get the menu bar handle associated with a panel.

Use GetSharedMenuBarEventPanel to get the handle of the panel on which a menu bar event occurred when multiple panels share a menu bar. You need this function only when using GetUserEvent; the panel handle is passed as a parameter to a menu callback function.

Use GetMenuBarAttribute to obtain a particular menu bar or menu item attribute.

Use SetMenuBarAttribute to set a particular menu bar or menu item attribute.

Use InsertSeparator to programmatically place a dividing line between menu items.

Use NewMenu / DiscardMenu, NewMenuItem / DiscardMenuItem, and NewSubMenu / DiscardSubMenu to programmatically alter a menu system.

Use EmptyMenu to remove the contents of a particular menu or sub-menu.

Use EmptyMenuBar to remove the menu bar from the screen and remove its contents from memory but retain the menu bar handle.

Use DiscardMenuBar to remove the menu bar from the screen and free its handle from memory.

## **Processing Menu Bar Events**

There are two ways to process menu bar events. One way is to assign callback functions to menu items and immediate action menus. When a commit event is generated, the appropriate callback function executes. Alternatively you can use an event loop that includes a call to GetUserEvent. When a commit event is generated, GetUserEvent returns the appropriate menu bar handle and menu item ID, and the program conditionally executes portions of code. Commit events are generated when the user selects a menu item or immediate action menu item.

### **Using Callback Functions...**

If you create your menu bar in the User Interface Editor, you can assign callback function names to menu items and immediate action menus from within the editor. When LoadMenuBar loads the menu bar, LabWindows/CVI automatically installs your callback functions and calls them whenever commit events are generated on menu items and immediate action menus.

If you create your menu bar programmatically via NewMenuBar, you can use InstallMenuCallback to install callback functions for immediate action menus. Menu item callbacks are installed as a parameter to NewMenuItem. Your callback functions are then called whenever commit events are generated on menu items or immediate action menus. You should use the MenuCallbackPtr typedef from userint.h as a model to declare your menu callback functions in your program.

You can also use InstallMenuDimmerCallback to install a callback function that is called just before a pull-down menu appears when the user clicks a menu bar or presses a menu short-cut key. This callback function can update the state of dimmed menu items before the pull-down menu is displayed to the user. You should use the MenuDimmerCallbackPtr typedef from userint.h as a model to declare this callback function in your program.

Callbacks must be initiated through a call to RunUserInterface or a GetUserEvent loop.

### Using an Event Loop...

When the user generates a commit event on a menu item or immediate action menu, the GetUserEvent function returns the appropriate menu bar handle and menu ID as parameters. GetUserEvent can operate in one of two ways.

- GetUserEvent waits for the user to generate an event before returning to the calling program.
- GetUserEvent returns immediately whether or not an event has occurred. If a menu event occurred, GetUserEvent returns a valid menu or menu item ID.

### **Menu Bar Attributes**

Table 3-6 lists menu and menu item attributes that you can retrieve or change through GetMenuBarAttribute and SetMenuBarAttribute.

Table 3-6. Menu and Menu Item Attributes

Attribute	Name	Type	Description
Menu and Menu Item Attribute	ATTR_DIMMED	int	1 = menu/item is disabled 0 = menu/item is enabled Pass 0 (zero) if the attribute corresponds to the entire menu bar.
	ATTR_CALLBACK_DATA	void *	A pointer to user data area that will be passed to the menu or menu item callback function.
	ATTR_CALLBACK_FUNCTION _POINTER	void *	A pointer to the callback function for the menu or menu item.
	ATTR_CALLBACK_NAME	char *	The name of the callback function associated with the menu or menu item (GetMenuBarAttribute only).
	ATTR_CALLBACK_NAME_ LENGTH	int	The number of characters in the name of the menu or menu item callback name (GetMenuBarAttribute only).
	ATTR_CONSTANT_NAME	char *	The constant name assigned to the menu or menu item in the .uir file when created by the user interface editor (GetMenuBarAttribute only).
	ATTR_CONSTANT_NAME_LEN GTH	int	The number of characters in the constant name of the menu or menu item (GetMenuBarAttribute only).

Table 3-6. Menu and Menu Item Attributes (Continued)

Attribute	Name	Type	Description
Menu	ATTR_MENU_NAME	char *	The name of the menu item.
	ATTR_MENU_NAME_LENGTH	int	The number of characters in the menu item (GetMenuBarAttribute only).
Menu Bar Only	ATTR_DRAW_LIGHT_BEVEL	int	Indicates whether the menubar draws with a light or dark bevel at the bottom.  (Applies only to Windows 95.)  0 = Dark Bevel (the default)  1 = Light Bevel
	ATTR_NUM_MENUS	int	The number of menus for the menu bar.
Menu Item	ATTR_CHECKED	int	1 = a check mark by the menu item 0 = no check mark by the menu item
	ATTR_IS_SEPARATOR	int	1 = the menu item is a separator, 0 = the menu item is not a separator (GetMenuBarAttribute only).
	ATTR_ITEM_NAME	char *	The name of the menu item
	ATTR_ITEM_NAME_LENGTH	int	The number of characters in the menu item name (GetMenuBarAttribute only).
	ATTR_NUM_MENU_ITEMS	int	The number of menu items for the menu.
	ATTR_SHORTCUT_KEY	int	Key code for the menu item shortcut key (see Table 3-7)
	ATTR_SUBMENU_ID	int	The constant ID for the submenu (GetMenuBarAttribute only).

### **Menu Bar Attribute Discussion**

In source code, a shortcut key is represented by a 4-byte integer consisting of three bit fields, 0x00MMVVAA, where:

MM =the modifier key

 $\nabla V =$ the virtual key

AA =the ASCII key

When you construct a shortcut key, a modifier key is bit-wise OR'ed with a virtual key or an ASCII key. Either the ASCII field or the virtual key field will be all zeros. For example, VAL\_SHIFT\_MODIFIER | VAL\_F1\_VKEY produces a shortcut key of <Shift-F1>, and VAL\_MENUKEY\_MODIFIER | 'D' produces a shortcut key of <Ctrl-D>.

Virtual keys do not require modifiers but ASCII keys require at least one modifier.

Table 3-7 shows the modifiers and virtual keys for shortcut keys.

Type

Value

VAL\_SHIFT\_MODIFIER

VAL\_SHIFT\_AND\_MENUKEY

VAL\_MENUKEY\_MODIFIER

<Ctrl> on the PC and <Ctrl> or <Meta> on the SPARCstation.

VAL\_UNDERLINE\_MODIFIER

<Alt> on the PC and the SPARCstation.

Also, optionally, <META> on the SPARCstation.

Table 3-7. Key Modifiers and Virtual Keys

Table 3-7. Key Modifiers and Virtual Keys (Continued)

Type	Value
Virtual key codes	VAL_FWD_DELETE_VKEY not available on SPARCstation keyboards.  VAL_BACKSPACE_VKEY <del> and <back space=""> on the SPARCstation.</back></del>
	VAL_ESC_VKEY
	VAL_TAB_VKEY
	VAL_ENTER_VKEY
	VAL_UP_ARROW_VKEY
	VAL_DOWN_ARROW_VKEY
	VAL_LEFT_ARROW_VKEY
	VAL_RIGHT_ARROW_VKEY
	VAL_INSERT_VKEY
	VAL_HOME_VKEY
	VAL_END_VKEY
	VAL_PAGE_UP_VKEY
	VAL_PAGE_DOWN_VKEY
	VAL_F1_VKEY
	VAL_F2_VKEY
	VAL_F3_VKEY
	VAL_F4_VKEY
	VAL_F5_VKEY
	VAL_F6_VKEY
	VAL_F7_VKEY
	VAL_F8_VKEY
	VAL_F9_VKEY
	VAL_F10_VKEY
	VAL_F11_VKEY
	VAL_F12_VKEY

When you use GetMenuBarAttribute, the three constants shown in Table 3-8 are available to mask the three bit fields of a shortcut key.

Table 3-8. Constants for Masking Three Bit Fields in GetMenuBarAttribute

Value	Mask
VAL_MODIFIER_MASK	0x00FF0000
VAL_VKEY_MASK	0x0000FF00
VAL_ASCII_KEY_MASK	0x000000FF

To separate each field of a key code, perform a bit-wise AND operation on the key code using each of the three masks.

# **Programming with Controls**

This section describes how to use the User Interface Library functions to control the elements of user interface controls.

### **Control Functions for All Controls**

When you use LoadPanel to load a panel from a resource file created in the user interface editor into memory, it also loads the controls on that panel. Use the defined constant names (IDs) assigned to the controls on the panel in the User Interface Editor to reference the controls in the control functions.

Use NewCtrl to create a new control during program execution. NewCtrl returns an ID you use to reference the control in subsequent operations. Use the first parameter of NewCtrl to specify the panel on which the control is to appear. The second parameter of NewCtrl specifies the control style. (Table 3-10 lists control styles.) You also specify the name and position of the control through parameters to NewCtrl.

Use DuplicateCtrl to create a new control that is a duplicate of a control that was loaded by LoadPanel or created by NewCtrl. DuplicateCtrl returns an ID that you use to reference the control in subsequent operations. You specify the destination panel, name, and position of the control through parameters to DuplicateCtrl.

Use SetCtrlVal to set a control to a particular value. *This function is not valid for Graph and Strip Chart controls.* 

Use GetCtrlVal to obtain the current value of a control. *This function is not valid for Graph and Strip Chart controls.* 

Use GetActiveCtrl to obtain the control that receives keyboard events when its panel is the active panel.

Use SetActiveCtrl to establish the control that receives keyboard events when its panel is the active panel. The label of the active control is inset when its panel is the active panel.

Use DefaultCtrl to restore a control to its default value. If the control is visible, the program updates it to reflect its default value. You assign default values to controls in the User Interface Editor or through SetCtrlAttribute. This function is not valid for Graph and Strip Chart controls.

Use GetCtrlBoundingRect to obtain the top, left, height, and width of the rectangle bounding the control and its label.

Use GetCtrlAttribute to obtain a particular attribute of a control.

Use SetCtrlAttribute to set a particular attribute of a control. When changing control attributes that affect the font of a control, ATTR\_TEXT\_FONT should be the first attribute you modify.

Use DiscardCtrl to remove a control from memory. If its panel is visible, the control is removed from the screen. LabWindows/CVI allows you to call DiscardCtrl only from an EVENT\_COMMIT event. A call to DiscardCtrl from any other type of event may cause unpredictable behavior.

#### **Control Functions for List Controls (List Boxes and Rings)**

List controls are unique because they contain an indexed set of label/value pairs. Labels are strings that appear on the ring, and values can be of any type. For more information on a special type of ring control, the picture ring control, see the *Programming Picture Controls* section.

#### List Boxes and Rings...

Use InsertListItem to add an item to the list.

Use DeleteListItem to delete one or more items from the list.

Use ReplaceListItem to replace a given list item with a new item. To preserve the existing label and change only the value, pass "0" as the label parameter.

Use GetCtrlVal to obtain the value of the currently active list item.

Use SetCtrlVal to set the currently active list item based on a given value.

Use GetCtrlIndex to obtain the zero-based index of the currently active list item.

Use SetCtrlIndex to set the currently active list item based on a given zero-based index.

Use GetValueFromIndex to obtain the value of a list control corresponding to a given zero-based index of the list.

Use GetValueLengthFromIndex to obtain the length of the value (strings only) of a list control corresponding to a given zero-based index of the list.

Use GetIndexFromValue to obtain a zero-based index of a list control corresponding to a given value.

Use GetNumListItems to obtain the number of items contained in a list control.

Use GetLabelFromIndex to obtain the label of a list item given a zero-based index.

Use GetLabelLengthFromIndex to obtain the length of the label of a list item given a zero-based index.

Use ClearListCtrl to clear the contents of a list control.

#### List Boxes only...

Use SetListItemImage to set the image associated with a particular list item. (List item images are the folder icons that appear in the **Open /Save File** dialog box in LabWindows/CVI.)

Use GetListItemImage to obtain the image associated with a particular list item. (List item images are the folder icons that appear in the **Open/Save File** dialog box in LabWindows/CVI.)

Use IsListItemChecked to determine if a particular list item is checked.

Use CheckListItem to programmatically check a list item.

Use GetNumCheckedItems to determine the number of checked list items.

#### **Control Functions for Text Boxes**

Text boxes in the User Interface library can contain a finite number of lines. If the number of lines multiplied by the pixel height of the font exceeds 32767, the text box does not scroll. If you use NIDialogMetaFont or the NIEditorMetaFont, your text box can contain a maximum of approximately 2500 lines.

Use GetCtrlVal to obtain the text in the text box.

Use SetCtrlVal to append text to a text box.

Use InsertTextBoxLine to add text into a text box starting at a given line.

Use DeleteTextBoxLine to delete one or more lines from a text box.

Use ReplaceTextBoxLine to replace a given line with new text.

Use GetNumTextBoxLines to obtain the number of lines used in a text box.

Use GetTextBoxLineLength to obtain the length of a particular line in a text box.

Use GetTextBoxLine to obtain parameters a particular line in a text box.

Use ResetTextBox to replace the contents of a text box.

#### **Processing Control Events**

Once a panel is displayed, there are two ways to process events from the controls on that panel. You can assign callback functions to the controls. When any type of event occurs on a control, the appropriate callback function executes. Alternatively, you can use an event loop that includes a call to GetUserEvent. When the user generates a commit event on a control, GetUserEvent returns the appropriate control ID, and your program can conditionally execute portions of code. Commit events occur on a control when a user changes the value on a control and presses <Enter> or <Tab> or clicks on another control with the mouse.

#### **Using Callback Functions...**

If you create your controls in the User Interface Editor, you can assign callback function names to the controls from within the editor. When LoadPanel loads the panel, LabWindows/CVI automatically installs your callback functions and calls them whenever events are generated on the controls.

If you create your controls programmatically via NewCtrl, you can use InstallCtrlCallback to assign callback function names to the controls. Your callback function is then called whenever an event is generated on the panel. You should use the CtrlCallbackPtr typedef from userint.h as a model to declare your control callback functions in your program.

Callbacks must be initiated through a call to RunUserInterface or to a GetUserEvent loop.

Note: Do not call DiscardCtrl from within the callback function of the control you want to discard. Doing this gives unpredictable results.

#### Using an Event Loop...

When the user generates a commit event on a control, the GetUserEvent function returns the appropriate ID of the control as a parameter. GetUserEvent can operate in one of two ways.

- GetUserEvent waits for the user to generate an event before returning to the calling program.
- GetUserEvent returns immediately whether or not an event occurs. If no event occurs, the control ID parameter is -1.

#### **Control Attributes**

Table 3-9 lists control attributes that you can retrieve or change through GetCtrlAttribute and SetCtrlAttribute.

Table 3-9. Control Attributes

#### For all controls

Name	Type	Description
ATTR_CALLBACK_DATA	void *	A pointer to user data that is passed to the panel callback function
ATTR_CALLBACK_FUNCTION_POINT ER	void *	A pointer to the callback function for the control.
ATTR_CALLBACK_NAME	char *	The name of the callback function associated with the control (GetCtrlAttribute only).
ATTR_CALLBACK_NAME_LENGTH	int	The number of characters in the name of the control callback name (GetCtrlAttribute only).
ATTR_CONSTANT_NAME	char *	The constant name assigned to the control in the .uir file when created by the User Interface Editor (GetCtrlAttribute only).
ATTR_CONSTANT_NAME_LENGTH	int	The number of characters in the constant name of the control (GetCtrlAttribute only).
ATTR_CTRL_STYLE	int	The control style, see Table 3-10 (GetCtrlAttribute only)
ATTR_DIMMED	int	1 = control disabled 0 = control enabled

## For all controls (Continued)

Name	Туре	Description
ATTR_LEFT	int	-32768 to 32767
ATTR_NEXT_CTRL	int	The next control on the panel (GetCtrlAttribute only).
ATTR_OVERLAPPED	int	Indicates whether the control is overlapped by another control (or its own parts).  (GetCtrlAttribute only)
ATTR_TOP	int	-32768 to 32767
ATTR_VISIBLE	int	1 = control visible 0 = control invisible
ATTR_WIDTH	int	0 to 32767
ATTR_ZPLANE_POSITION	int	The order of the control in the z-plane. The lowest ordered control (0) is on top.

#### For all controls except simple strings, simple numerics, and simple rings

Name	Type	Description
ATTR_HEIGHT	int	0 to 32767

# For all controls except indicator-only controls (indicator-only controls are: decorations, strip charts, text messages, timers, and pictures)

Name	Type	Description
ATTR_CTRL_MODE		VAL_HOT or VAL_NORMAL or VAL_VALIDATE or VAL_INDICATOR
ATTR_CTRL_TAB_POSITION	int	The tab order of the control.

#### For all controls except decorations, canvases, graphs and strip charts

Name	Type	Description
		Same functionality as GetCtrlVal and SetCtrlVal.

# For all controls with frames (this includes text boxes, strings, numerics, simple rings, ring meters, ring gauges, list boxes, decorations, and pictures)

Name	Type	Description
ATTR_FRAME_COLOR		RGB value—see discussion following this table.

## For controls with labels (all controls except decorations, and text messages)

Name	Туре	Description
ATTR_LABEL_BOLD	int	1 = label is bold 0 = label is not bold
ATTR_LABEL_COLOR	int	RGB value—see discussion following this table.
ATTR_LABEL_FONT	char *	The font of the control label (see Table 3-5).
ATTR_LABEL_FONT_NAME_LENGTH	int	Number of characters in the name of the label font (GetCtrlAttribute only).
ATTR_LABEL_ITALIC	int	1 = label in italics 0 = label not in italics
ATTR_LABEL_POINT_SIZE	int	Point size of the label; range = 1 to 32767.
ATTR_LABEL_STRIKEOUT	int	1 = label has strikeout 0 = label does not have strikeout
ATTR_LABEL_TEXT	char *	The label of the control.
ATTR_LABEL_TEXT_LENGTH	int	Number of characters in the label (GetCtrlAttribute only).
ATTR_LABEL_UNDERLINE	int	1 = label underlined 0 = label not underlined
ATTR_LABEL_VISIBLE	int	1 = label is visible 0 = label is invisible

## For controls with labels except non-picture command buttons

Name	Туре	Description
ATTR_LABEL_BGCOLOR	int	Label background color, RGB value.
ATTR_LABEL_HEIGHT	int	Height of label; range = 0 to 32767.
ATTR_LABEL_JUSTIFY	int	VAL_LEFT_JUSTIFIED or VAL_RIGHT_JUSTIFIED or VAL_CENTER_JUSTIFIED
ATTR_LABEL_LEFT	int	Left position of label, range = -32768 to 32767 or use VAL_AUTO_CENTER.
ATTR_LABEL_RAISED	int	1 = label is raised 0 = label is not raised
ATTR_LABEL_SIZE_TO_TEXT	int	1 = label border restricted to label text size 0 = label border not restricted to label text size
ATTR_LABEL_TOP	int	Top position of label, range = -32768 to 32767 or use VAL_AUTO_CENTER or VAL_RIGHT_ANCHOR or VAL_LEFT_ANCHOR.
ATTR_LABEL_WIDTH	int	Width of label, range = 0 to 32767.

# For controls with text except graphs and strip charts (controls with text are all controls except: decorations, pictures, canvases, LEDs, and buttons without on/off text)

Name	Type	Description
ATTR_TEXT_BOLD	int	1 = text is bold 0 = text is not bold
ATTR_TEXT_COLOR	int	RGB value—see discussion below.
ATTR_TEXT_FONT	char *	The font of the text (see Table 3-5).

# For controls with text except graphs and strip charts (controls with text are all controls except: decorations, pictures, canvases, LEDs, and buttons without on/off text)

Name	Type	Description
ATTR_TEXT_FONT_NAME_LENGTH	int	Number of characters in the name of the text font (GetCtrlAttribute only).
ATTR_TEXT_ITALIC	int	1 = text in italics 0 = text not in italics
ATTR_TEXT_POINT_SIZE	int	Point size of the text, range = 1 to 32767.
ATTR_TEXT_STRIKEOUT	int	<ul><li>1 = text has strikeout</li><li>0 = text does not have strikeout</li></ul>
ATTR_TEXT_UNDERLINE	int	1 = text underlined 0 = text not underlined

# For controls with text except graphs, strip charts, ring slides, binary switches, and text buttons

Name	Type	Description
ATTR_TEXT_BGCOLOR	int	RGB value—see discussion below.

# For controls with text except graphs, strip charts, ring slides, pop-up rings, binary switches, and text buttons

Name	Type	Description
ATTR_TEXT_JUSTIFY		VAL_LEFT_JUSTIFIED or VAL_RIGHT_JUSTIFIED or VAL_CENTER_JUSTIFIED

# For controls with variable data types (this includes numerics, rings, binary switches, and list boxes)

Name	Type	Description
ATTR_DATA_TYPE	int	See Table 3-11.

## For label/value controls (slides, rings, binary switches, and list boxes)

Name	Type	Description
ATTR_CTRL_INDEX	int	0 to 32767
ATTR_DFLT_INDEX	int	0 to 32767

## For numerics

Name	Туре	Description
ATTR_CHECK_RANGE	int	VAL_COERCE or VAL_IGNORE or VAL_NOTIFY (see Table 3-13).
ATTR_DFLT_VALUE	same as control type	Default value of the control.
ATTR_FORMAT	int	See Table 3-12.
ATTR_INCR_VALUE	same as control type	Increments for INC/DEC arrows of the control.
ATTR_MAX_VALUE	same as control type	Maximum value of the control.
ATTR_MIN_VALUE	same as control type	Minimum value of the control.
ATTR_PRECISION	int	The numeric precision (0 to 15).
ATTR_NSCROLL_OFFSET_MAX	int	The maximum horizontal scroll bar offset in pixels; range 0 to 32767.
ATTR_SHOW_RADIX	int	1 = radix is shown 0 = radix is not shown

## For picture and slide rings and numerics

Name	Type	Description
ATTR_SHOW_INCDEC_ARROWS		1 = INC/DEC arrows are shown 0 = INC/DEC arrows are not shown

## For strings and text boxes

Name	Туре	Description
ATTR_MAX_ENTRY_LENGTH	int	Maximum # of characters; -1 means no limit.
ATTR_TEXT_SELECTION_LENGTH	int	0 to 32767
ATTR_TEXT_SELECTION_START	int	0 to 32767

## For text messages, strings, and text boxes

Name	Type	Description
ATTR_STRING_TEXT_LENGTH	int	0 to 32767 (GetCtrlAttribute only).

#### For text boxes

Name	Type	Description
ATTR_ENTER_IS_NEWLINE	int	The <enter> key causes a newline, otherwise a <ctrl-enter> is used.  1 = <enter> for newline.  0 = <ctrl-enter> for newline.</ctrl-enter></enter></ctrl-enter></enter>
ATTR_EXTRA_LINES	int	Number of lines retained off-screen (0 to 32767); -1 = unlimited number of lines retained off screen
ATTR_HSCROLL_OFFSET	int	Horizontal scroll offset; range = 0 to 32767 pixels.
ATTR_TOTAL_LINES	int	Number of lines used (GetCtrlAttribute only).
ATTR_WRAP_MODE	int	VAL_CHAR_WRAP or VAL_LINE_WRAP or VAL_WORD_WRAP

## For text boxes and list boxes

Name	Туре	Description
ATTR_FIRST_VISIBLE_LINE	int	Index of first visible line (zero-based).
ATTR_SCROLL_BAR_COLOR	int	Any valid RGB value.
ATTR_SCROLL_BAR_SIZE	int	VAL_SMALL_SCROLL_BARS or VAL_LARGE_SCROLL_BARS
ATTR_SCROLL_BARS	int	VAL_NO_SCROLL_BARS or VAL_HORIZ_SCROLL_BAR or VAL_VERT_SCROLL_BAR or VAL_BOTH_SCROLL_BARS (Horizontal scroll bars not valid for list boxes.)
ATTR_VISIBLE_LINES	int	Number of visible lines (0 to 32767).
ATTR_TEXT_CLICK_TOGGLES_ CHECK	int	1 = clicking on the text area toggle the checkmark 0 = clicking on the text area does not toggle the checkmark

## For list boxes

Name	Туре	Description
ATTR_ALLOW_ROOM_FOR_IMAGES	int	Specifies whether, when calculating the list box height, to assume that one or more list box labels may contain an image. Normally, the calculation of the list box height takes into account the image height only if there currently is an image in the list box. To make sure that the list box height always takes into account the height of an image, set this attribute to TRUE (1).
ATTR_CHECK_MODE	int	1 = enable checking 0 = disable checking

## **For list boxes (Continued)**

Name	Туре	Description
ATTR_CHECK_STYLE	int	VAL_CHECK_MARK or VAL_CHECK_BOX
ATTR_HILITE_CURRENT_ITEM	int	Specifies whether to highlight the currently selected item in a list box. (The highlight is shown in reversed colors when list box is active, a dashed box when inactive.)
ATTR_TEXT_CLICK_TOGGLES_CHECK	int	1 = clicking on the text area toggles the check mark 0 = clicking on the text area does not toggle the check mark

## For strings, numerics, and text boxes

Name	Type	Description
ATTR_NO_EDIT_TEXT		1 = enable text editing 0 = disable text editing

## For text messages

Name	Туре	Description
ATTR_TEXT_RAISED		1 = text is raised 0 = text is not raised
ATTR_SIZE_TO_TEXT		1 = message border restricted to text size 0 = message border not restricted to text size

#### For command buttons

Name	Type	Description
ATTR_CMD_BUTTON_COLOR	int	RGB value—see discussion that follows this table.
ATTR_SHORTCUT_KEY		See discussion of shortcut keys in <i>Menu Bar Attributes</i> section of this chapter.

## For binary switches

Name	Туре	Description
ATTR_BINARY_SWITCH_COLOR	int	RGB value—see discussion that follows this table.
ATTR_OFF_VALUE	same as control type	Value of control when OFF.
ATTR_OFF_VALUE_LENGTH	int	Only if string value (GetCtrlAttribute only).
ATTR_ON_VALUE	same as control type	Value of control when ON.
ATTR_ON_VALUE_LENGTH	int	Only if string value (GetCtrlAttribute only).

## For LEDs and buttons except command buttons

Name	Type	Description
ATTR_OFF_COLOR	int	RGB value—see discussion that follows this table.
ATTR_ON_COLOR	int	RGB value—see discussion that follows this table.

## For text buttons and binary switches

Name	Туре	Description
ATTR_OFF_TEXT	char *	Text displayed in OFF position.
ATTR_OFF_TEXT_LENGTH	int	Number of characters in the OFF text (GetCtrlAttribute only).
ATTR_ON_TEXT	char *	Text displayed in ON position.
ATTR_ON_TEXT_LENGTH	int	Number of characters in the ON text (GetCtrlAttribute only).

## For numerics with digital displays (slides, knobs, dials, meters, and gauges)

Name	Туре	Description
ATTR_DIG_DISP_LEFT	int	Left position of the digital display; range = -32768 to 32767.
ATTR_DIG_DISP_TOP	int	Top position of the digital display; range = -32768 to 32767.
ATTR_DIG_DISP_HEIGHT	int	Height of the digital display, range 0 to 32767.
ATTR_DIG_DISP_WIDTH	int	Width of the digital display; range = 0 to 32767.
ATTR_SHOW_DIG_DISP	int	1 = show digital display 0 = hide digital display

## For numerics and ring slides, knobs, dials, meters, and gauges

Name	Туре	Description
ATTR_FILL_COLOR	int	RGB value—see discussion that follows this table.
ATTR_MARKER_STYLE	int	VAL_NO_MARKERS or VAL_NO_INNER_MARKERS or VAL_FULL_MARKERS
ATTR_NEEDLE_COLOR	int	RGB value—see discussion that follows this table.
ATTR_SLIDER_COLOR	int	RGB value—see discussion that follows this table.
ATTR_TICK_STYLE	int	VAL_NO_TICKS or VAL_NO_MINOR_TICKS or VAL_FULL_TICKS

## For numeric and ring slides

Name	Туре	Description
ATTR_FILL_HOUSING_COLOR	int	RGB value—see discussion that follows this table.
ATTR_FILL_OPTION	int	VAL_NO_FILL, VAL_TOP_FILL, VAL_BOTTOM_FILL, VAL_RIGHT_FILL, or VAL_LEFT_FILL
ATTR_SLIDER_HEIGHT	int	0 to 32767
ATTR_SLIDER_WIDTH	int	0 to 32767

## For numeric and ring knobs, dials, and gauges

Name	Type	Description
ATTR_MARKER_END_ANGLE	int	Range = 0 to 359
ATTR_MARKER_START_ANGLE	int	Range = $0$ to $359$

## For color numerics

Name	Type	Description
ATTR_SHOW_MORE_BUTTON		1/0 = show/do not show the MORE button on the color numeric pop-up.
ATTR_SHOW_TRANSPARENT		1/0 = show/do not show the transparent icon on the color numeric pop-up.

## For menu rings

Name	Type	Description
ATTR_MENU_ARROW_COLOR	int	RGB value—see discussion that follows this table.

#### For timer controls

Name	Туре	Description
ATTR_INTERVAL		The interval at which the timer control callback function will be called (in seconds).
ATTR_ENABLED		0 = Timer callback is disabled 1 = Timer callback is enabled

## For picture controls, rings, and buttons

ype	Description
	VAL_SIZE_TO_IMAGE or VAL_SIZE_TO_PICTURE or VAL_PICT_CORNER or VAL_PICT_CENTER or VAL_PICT_TILE
_	t

## For picture controls and rings

Name	Type	Description
ATTR_FRAME_VISIBLE		1 = show picture frame 0 = hide picture frame

## For picture controls, rings, and canvas controls

Name	Type	Description
ATTR_PICT_BGCOLOR		RGB value—see discussion that follows this table. Also applies to canvas controls

For	nicture	huttons (	command	and	toggle)
LUI	picture	Duttons (	Commanu	anu	(UZZIC)

Name	Туре	Description
ATTR_IMAGE_FILE	char *	The filename of the image file to load into control. A NULL results in no image.
ATTR_IMAGE_FILE_LENGTH	int	The length of the image file length.
ATTR_SUBIMAGE_HEIGHT	int	Pixel height of subimage. See discussion following this table.
ATTR_SUBIMAGE_TOP	int	Top pixel coordinate of subimage. See discussion following this table.
ATTR_SUBIMAGE_LEFT	int	Left pixel coordinate of subimage. See discussion following this table.
ATTR_SUBIMAGE_WIDTH	int	Pixel width of subimage. See discussion following this table.
ATTR_USE_SUBIMAGE	int	1 = enable subimage display. 0 = disable subimage display. See discussion following this table.

#### **Picture Button Subimage Discussion**

ATTR\_USE\_SUBIMAGE allows the picture button to display a subset of its loaded image. The subset of the image that is sized to the picture button is specified by the following attributes.

ATTR\_SUBIMAGE\_TOP ATTR\_SUBIMAGE\_LEFT ATTR\_SUBIMAGE\_WIDTH ATTR\_SUBIMAGE\_HEIGHT

ATTR\_SUBIMAGE\_TOP and ATTR\_SUBIMAGE\_LEFT define the horizontal and vertical offsets in pixels of the picture button's bitmap image that will be displayed relative to the origin of the bitmap. The bitmap subimage origin (0,0) is the top-left corner of the bitmap.

ATTR\_SUBIMAGE\_WIDTH and ATTR\_SUBIMAGE\_HEIGHT define the width and height in pixels for the displayed subimage.

ATTR\_USE\_SUBIMAGE does not work with images loaded from Windows metafiles (.WMF).

#### **Control Attribute Discussion**

An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. You can use the User Interface Library function, MakeColor, to create an RGB value from red, green, and blue color components. See Table 3-3 for a list of common color values.

Table 3-10 contains the control types that can be used with the ATTR\_CTRL\_STYLE attribute.

Table 3-10. Control Styles for ATTR\_CTRL\_STYLE

Type	Value	Icon
Numerics	CTRL_NUMERIC	<b>1.23</b>
	CTRL_NUMERIC_THERMOMETER	10.0 - 5.0 - 0.0 -
	CTRL_NUMERIC_TANK	10.0· 5.0· 0.0·
	CTRL_NUMERIC_GAUGE	3
	CTRL_NUMERIC_METER	· 2/10
	CTRL_NUMERIC_KNOB	2- 0-8 10
	CTRL_NUMERIC_DIAL	2 0 10
	CTRL_NUMERIC_VSLIDE	10.0 - 1 5.0 - 1 0.0 - 1
	CTRL_NUMERIC_HSLIDE	◆ <b>2310.</b> 0
	CTRL_NUMERIC_FLAT_VSLIDE	10.0 - 5.0 - 0.0 -
	CTRL_NUMERIC_FLAT_HSLIDE	48333 + 0.0 10.0
	CTRL_NUMERIC_LEVEL_VSLIDE	10.0 - 5.0 - 0.0 -
	CTRL_NUMERIC_LEVEL_HSLIDE	0:0 10:0
	CTRL_NUMERIC_POINTER_VSLIDE	10.0 - 1 5.0 - 1 0.0 - 1
	CTRL_NUMERIC_POINTER_HSLIDE	0.0 10.0
	CTRL_COLOR_NUMERIC	<b>3</b>

Table 3-10. Control Styles for ATTR\_CTRL\_STYLE (Continued)

Type	Value	Icon
String	CTRL_STRING	
Text message	CTRL_TEXT_MSG	
Text box	CTRL_TEXT_BOX	
Command buttons	CTRL_SQUARE_COMMAND_BUTTON	OK
	CTRL_OBLONG_COMMAND_BUTTON	OK OK
	CTRL_ROUND_COMMAND_BUTTON	<b>®</b>
	CTRL_PICTURE_COMMAND_BUTTON	80
	CTRL_ROUNDED_COMMAND_BUTTON	ОК
Buttons	CTRL_ROUND_BUTTON	
	CTRL_SQUARE_BUTTON	
	CTRL_ROUND_FLAT_BUTTON	0
	CTRL_SQUARE_FLAT_BUTTON	
	CTRL_ROUND_RADIO_BUTTON	•
	CTRL_SQUARE_RADIO_BUTTON	
	CTRL_CHECK_BOX	$\boxtimes$
	CTRL_ROUND_PUSH_BUTTON	9
	CTRL_SQUARE_PUSH_BUTTON	
	CTRL_ROUND_PUSH_BUTTON2	0
	CTRL_SQUARE_PUSH_BUTTON2	
	CTRL_SQUARE_TEXT_BUTTON	ON
	CTRL_OBLONG_TEXT_BUTTON	ÖN
	CTRL_ROUND_TEXT_BUTTON	(OH)
	CTRL_ROUNDED_TEXT_BUTTON	ON
	CTRL_PICTURE_TOGGLE_BUTTON	°~

Table 3-10. Control Styles for ATTR\_CTRL\_STYLE (Continued)

Туре	Value	Icon
LEDs	CTRL_ROUND_LIGHT	₩
	CTRL_SQUARE_LIGHT	米
	CTRL_ROUND_LED	
	CTRL_SQUARE_LED	
Binary switches	CTRL_HSWITCH	[III]
	CTRL_VSWITCH	
	CTRL_GROOVED_HSWITCH	<b>**</b>
	CTRL_GROOVED_VSWITCH	<b></b>
	CTRL_TOGGLE_HSWITCH	
	CTRL_TOGGLE_VSWITCH	4
Rings	CTRL_RING	<b>₽</b> Ring
	CTRL_RECESSED_MENU_RING	Ring▼
	CTRL_MENU_RING	Ring ▼
	CTRL_POPUP_MENU_RING	▼
	CTRL_RING_VSLIDE	#- <u> </u>    
	CTRL_RING_HSLIDE	
	CTRL_RING_FLAT_VSLIDE	#- 8-
	CTRL_RING_FLAT_HSLIDE	À È Ċ
	CTRL_RING_LEVEL_VSLIDE	#- <u>-</u>
	CTRL_RING_LEVEL_HSLIDE	<u> </u>
	CTRL_RING_POINTER_VSLIDE	#- в- с-
	CTRL_RING_POINTER_HSLIDE	—⊽— À È Ċ

Table 3-10. Control Styles for ATTR\_CTRL\_STYLE (Continued)

Type	Value	Icon
	CTRL_RING_THERMOMETER	A - N
	CTRL_RING_TANK	#:
	CTRL_RING_GAUGE	0
	CTRL_RING_METER	A Zor
	CTRL_RING_KNOB	
	CTRL_RING_DIAL	
	CTRL_PICTURE_RING	<u></u>
List box	CTRL_LIST	
Decorations	CTRL_RAISED_BOX	
	CTRL_RECESSED_BOX	
	CTRL_FLAT_BOX	
	CTRL_RAISED_CIRCLE	$\circ$
	CTRL_RECESSED_CIRCLE	
	CTRL_FLAT_CIRCLE	$\circ$
	CTRL_RAISED_FRAME	
	CTRL_RECESSED_FRAME	
	CTRL_FLAT_FRAME	
	CTRL_RAISED_ROUND_FRAME	0
	CTRL_RECESSED_ROUND_FRAME	0
	CTRL_FLAT_ROUND_FRAME	$\bigcirc \bigcirc \bigcirc \bigcirc \bigcirc$
	CTRL_RAISED_ROUNDED_BOX	
	CTRL_RECESSED_ROUNDED_BOX	
	CTRL_FLAT_ROUNDED_BOX	

Table 3-10. Control Styles for ATTR\_CTRL\_STYLE (Continued)

Туре	Value	Icon
Graph	CTRL_GRAPH	
Strip chart	CTRL_STRIP_CHART	2 1 1 0 0 0 1 0
Picture	CTRL_PICTURE	
Timer	CTRL_TIMER	Ö
Canvas	CTRL_CANVAS	

The following list presents the control data types that correspond to the ATTR\_DATA\_TYPE attribute.

Table 3-11. Control Data Types for the ATTR\_DATA\_TYPE attribute

Values
VAL_CHAR
VAL_INTEGER
VAL_SHORT_INTEGER
VAL_FLOAT
VAL_DOUBLE
VAL_STRING
VAL_UNSIGNED_SHORT_INTEGER
VAL_UNSIGNED_INTEGER
VAL_UNSIGNED_CHAR

You should set ATTR\_DATA\_TYPE before you set any other value attribute such as ATTR\_CTRL\_VAL, ATTR\_MAX\_VALUE, ATTR\_MIN\_VALUE, and others.

Table 3-12 contains the numeric formats you can use with ATTR\_FORMAT.

Table 3-12. Numeric Formats

Numeric Formats	Example
VAL_FLOATING_PT_FORMAT	123.000
VAL_SCIENTIFIC_FORMAT	1.23E+2
VAL_ENGINEERING_FORMAT	123.00E+0
VAL_DECIMAL_FORMAT*	123
VAL_HEX_FORMAT*	7B
VAL_OCTAL_FORMAT*	173
VAL_BINARY_FORMAT*	1111011

<sup>\*</sup> not valid for graphs and strip charts

The ATTR\_CHECK\_RANGE attribute establishes the behavior of LabWindows/CVI when you try to set a control to a value outside of its specified range. The three possible attribute values are shown in the following table.

Table 3-13. ATTR\_CHECK\_RANGE Values

<b>Numeric Formats</b>	LabWindows/CVI Action
VAL_COERCE	The value is coerced to the upper or lower range boundary, whichever is closer.
VAL_IGNORE	The value remains unchanged.
VAL_NOTIFY	The user interface operator is notified with an Out of Range dialog box when the control is active.

# **Programming with Picture Controls**

This section describes the simple picture control and the picture control versions of command buttons, toggle buttons, and ring controls onto which you can place images. Picture controls can help users understand your GUI more quickly and can be used to display useful diagrams or

charts. Picture controls can include logos and other images that match the style of your organization.

You can use commit events on any picture control in your program. However, the simple picture control is best suited for displaying images only. The other picture controls have a powerful editing window that helps you quickly set their appearance and their behavior in response to user events.

The following image formats work with picture controls:

- PCX (Windows and UNIX)
- BMP, DIB, RLE, ICO (Windows only)
- WMF (Windows 95 and NT only)
- XWD (UNIX only)

#### **Simple Picture Control**

You access the simple picture control through the **Picture** menu item in the **Create** menu. Alternatively, you can right-click on a panel in a .uir file and select **Picture** from the pop-up menu that appears. It allows you to place images on panels, such as logos and diagrams.

You can program the simple picture control to recognize user events, but it does not automatically change appearance in response to the event. The simple picture control can also serve as an indicator that, for example, is dim at startup and becomes fully colored at some point during run-time. You can programatically change the contents of a picture control by calling SetCtrlAttribute with the ATTR\_IMAGE\_FILE attribute.

#### **Picture Control Attributes**

You access the picture command button, picture toggle button, and picture ring control under the **Control** menu, within the sub-menus **Command Button**, **Toggle Button**, and **Ring**. The picture versions of these controls have nearly all the features of other controls.

You can use the SetCtrlVal function to change the image in a picture button or picture ring, when, for example, you want to simulate a mouse click. For picture ring controls, you also can use the SetCtrlIndex function to change the image.

You can use the SetCtrlBitmap function to select images directly from memory, instead of through a path to a standard image filename. SetCtrlBitmap is an alternative to ATTR\_IMAGE\_FILE, DisplayImageFile and ReplaceListItem. For more information, see the *Using Bitmap Objects* section in this chapter.

#### **Appearance of Picture Controls**

The picture controls appear on screen like other controls, with the following minor differences.

- Picture command buttons and picture toggle buttons have an external label only.
- In picture command buttons and picture toggle buttons, the background color of your buttons may not be visible, depending on the size of your image and the Fit Mode you choose. When the background color of a button is not visible, users do not see the color shift that normally takes place in response to a mouse click. However, they do see two smaller changes in the button: the image moves down and over several pixels, and the colors of the border around the button change. You can give these controls more visual impact by making the background of the control visible and coloring it appropriately.
- In a picture ring control, you cannot click on one of the images and view all the selections at once. However, as with other ring controls, you can cycle through the options in the ring control by using increment/decrement arrows.

#### **Giving Picture Controls More Visual Impact**

Whether the state of the control is on, off, or "clicked-on with the mouse," users see the same image. If you want your picture control to reflect its state more vividly, make the background area of the control visible by choosing the Fit Modes **Stick Image to Corner** or **Center Image** when you paste the image into the control. As long as your image is smaller than the size of your control, the image has a visible background area that you can color vividly to call attention to the state of a picture control. Either resize the control or resize the image until enough background appears on your control.

# **Programming with Canvas Controls**

Use a canvas control to add an arbitrary drawing surface to your project. You can draw text, shapes, and bitmap images. This section describes how you can use the User Interface Library functions and attributes with canvas controls.

## **Functions for Drawing on Canvas**

Use the following functions to draw on a canvas.

- CanvasDrawPoint to draw a point.
- CanvasDrawLine to draw a line.
- CanvasDrawLineTo to draw a line from the current pen position.
- CanvasDrawRect to draw a rectangle.

- CanvasDimRect to overlay a checkerboard pattern in a rectangular area.
- CanvasDrawRoundedRect to draw a rectangle with rounded corners.
- CanvasDrawOval to draw an oval.
- CanvasDrawArc to draw an arc.
- CanvasDrawPoly to draw a polygon.
- CanvasDrawText to draw text within a rectangular area.
- CanvasDrawTextAtAPoint to draw text at an anchor point.
- CanvasDrawBitmap to draw a bitmap image.
- CanvasScroll to scroll a rectangular area.
- CanvasInvertRect to invert the colors in a rectangular area.
- CanvasClear to restore a rectangular area to the canvas background color.

### **Batch Drawing**

Although, the drawing functions can be called at any time, they are most efficient when called from within a batch drawing operation. A batch drawing operation consists of a call to CanvasStartBatchDraw, followed by one or more calls to the canvas drawing functions, followed by a call to CanvasEndBatchDraw.

For optimal performance, users are encouraged to include as many drawing primitives as possible within a batch drawing operation. When a drawing function is called outside of a batch operation, the function is implicitly surrounded by calls to CanvasStartBatchDraw and CanvasEndBatchDraw.

## **Canvas Coordinate System**

A canvas has a built-in pixel-based Cartesian coordinate system, where (0,0) represents the top, left corner of the canvas. All drawing is specified relative to this coordinate system. The coordinate system can be modified using the following four attributes:

```
ATTR_CANVAS_XCOORD_AT_ORIGIN
ATTR_CANVAS_YCOORD_AT_ORIGIN
ATTR_CANVAS_XSCALING
ATTR_CANVAS_YSCALING
```

All canvas control functions use this coordinate system, except for CanvasGetPixel and CanvasGetPixels, which use unscaled pixel coordinates rather than the canvas coordinate system.

## Offscreen Bitmap

Each canvas has an offscreen bitmap which is used to restore the appearance of the canvas when the region is exposed. You can choose to draw directly to the screen, bypassing the offscreen bitmap. If you draw to the offscreen bitmap, you can choose whether to update the screen immediately or wait until draw events are processed. This is controlled by the ATTR\_DRAW\_POLICY attribute.

The CanvasUpdate function immediately copies the canvas offscreen bitmap to the screen, within a specified rectangular area.

The ATTR\_OVERLAP\_POLICY attribute controls what occurs when you draw to a canvas which is overlapped by another control.

## **Clipping**

The drawing functions are constrained by the clipping set using CanvasSetClipRect. Any drawing outside the clipping rectangle is not rendered. You can obtain the current clipping rectangle by calling CanvasSetClipRect.

## **Background Color**

The background color of the canvas is controlled by the ATTR\_PICT\_BGCOLOR attribute. When ATTR\_PICT\_BGCOLOR is changed, the entire canvas area is cleared.

#### **Pens**

Each canvas has a pen. The canvas pen attributes can be set individually using SetCtrlAttribute. They are:

ATTR\_PEN\_WIDTH
ATTR\_PEN\_STYLE
ATTR\_PEN\_COLOR
ATTR\_PEN\_FILL\_COLOR
ATTR\_PEN\_MODE
ATTR\_PEN\_PATTERN

The CanvasDefaultPen function resets all these attributes to their default values.

The location of the pen affects the starting position of the line drawn by the CanvasDrawLineTo function. The location of the pen is affected only by the CanvasSetPenPosition and the CanvasDrawLineTo functions. You can obtain the location of the pen by calling CanvasGetPenPosition.

#### **Pixel Values**

You can obtain the color values of pixels in the canvas. Call CanvasGetPixel to obtain the color of one pixel. Call CanvasGetPixels to obtain the values of the pixels within a rectangular area. The color values are obtained from the offscreen bitmap, not the screen.

Unlike other canvas control functions, CanvasGetPixel and CanvasGetPixels use unscaled pixel coordinates rather than the canvas coordinate system.

#### **Canvas Attribute Discussion**

The following table lists the attributes for Canvas Controls.

Table 3-14. Control Attributes for Canvas Controls

Name	Type	Description
ATTR_DRAW_POLICY	int	Determines when drawing operations are rendered on the offscreen bitmap and the screen. See discussion that follows this table.
ATTR_OVERLAPPED_POLICY	int	Determines what occurs when you draw to a canvas which is overlapped by another control. See discussion that follows this table.
ATTR_PEN_COLOR	int	The RGB color value used to draw points, lines, frames, and text on the canvas.
ATTR_PEN_FILL_COLOR	int	The RGB color value used to fill interior areas of shapes, text backgrounds, and areas exposed by scrolling.
ATTR_PEN_MODE	int	Determines the effect of drawing with the pen color (or pen fill color), given the current color on the screen. See discussion following this table.
ATTR_PEN_PATTERN	unsigned char[8]	Determines the pattern used to fill interior areas of shapes. See discussion following this table.
ATTR_PEN_STYLE	int	The style used when drawing lines and frames. In Windows, applies only if pen width is 1; if pen width is greater than 1, the style is always VAL_SOLID. See Table 3-23.

Table 3-14. Control Attributes for Canvas Controls (Continued)

Name	Type	Description
ATTR_PEN_WIDTH	int	The number of pixels in the width of a pen stroke. Applies to lines, frames, and points. Valid range: 1 to 255. Default: 1.
ATTR_XCOORD_AT_ORIGIN	double	The horizontal coordinate mapped to the left edge of the canvas. (Is multiplied by ATTR_XSCALING to arrive at a pixel offset.) Default value: 0.0.
ATTR_XSCALING	double	The factor used to scale user-supplied horizontal coordinates and widths into pixel-based coordinates and widths.  Default value: 1.0.
ATTR_YCOORD_AT_ORIGIN	double	The vertical coordinate mapped to the top edge of the canvas. (Is multiplied by ATTR_YSCALING to arrive at a pixel offset.) Default value: 0.0.
ATTR_YSCALING	double	The factor used to scale user-supplied vertical coordinates and heights into pixel-based coordinates and heights. Default value: 1.0.

The following table lists the values associated with the ATTR\_DRAW\_POLICY attribute.

Table 3-15. Values for ATTR\_DRAW\_POLICY

Value	Description
VAL_UPDATE_IMMEDIATELY	Drawing takes place offscreen. The section of the bitmap corresponding to the area of the drawing operation is copied into the canvas display immediately. (This is the default.)
VAL_MARK_FOR_UPDATE	Drawing takes place offscreen. The area on the canvas corresponding to the area of the drawing operation is marked for update. The new drawing becomes visible when draw events are processed.
VAL_DIRECT_TO_SCREEN	Drawing goes directly to the screen. The offscreen bitmap is not updated. Although this may result in a faster drawing time, whatever is drawn in this mode is lost when the canvas is redrawn.

VAL\_DRAW\_ON\_TOP

The following table lists the values associated with the ATTR\_OVERLAPPED\_POLICY attribute.

VAL\_DEFER\_DRAWING

VAL\_UPDATE\_IMMEDIATELY, new drawing does not become visible until draw events are processed. If the draw policy is VAL\_DIRECT\_TO\_SCREEN, no drawing takes place at all. (This is

If the control is overlapped and the draw policy is *not* VAL\_MARK\_FOR\_UPDATE, drawing occurs on top of the

Table 3-16. Values for ATTR\_OVERLAPPED\_POLICY

The ATTR\_PEN\_MODE attribute determines the effect of drawing with the pen color (or pen fill color), given the current color on the screen. With the default setting, VAL\_COPY\_MODE, the current screen color is replaced with the pen color (or pen fill color). The other settings specify bitwise logical operations on pen color (or pen fill color) and the screen color.

Note: If a system color palette is in use, the logical operations might be performed on the palette indices rather than the RGB values, depending on the operating system.

The following table lists the values associated with the ATTR\_PEN\_MODE attribute.

the default.)

overlapping controls.

Value	Description
VAL_COPY_MODE	pen color (the default)
VAL_OR_MODE	pen color   screen color
VAL_XOR_MODE	pen color ^ screen color
VAL_AND_NOT_MODE	~(pen color) & screen color
VAL_NOT_COPY_MODE	~(pen color)
VAL_OR_NOT_MODE	~(pen color)   screen color
VAL_NOT_XOR_MODE	~(pen color ^ screen color)
VAL_AND_MODE	pen color & screen color

Table 3-17. Values for ATTR\_PEN\_MODE

The ATTR\_PEN\_PATTERN attribute determines the pattern used to fill interior areas of shapes. The value is an 8-byte unsigned character array representing a repeating 8-by-8 grid of pixels through which filling operations are filtered. A pixel of value 1 means that the pen fill color is

used for that pixel. A pixel value of 0 means that black is used for that pixel. The default value for the attribute is the solid pattern, in which each byte of the array is 0xFF.

To make a pixel value of 0 mean "screen color" instead of "black", do the following.

- 1. Set ATTR\_PEN\_PATTERN to the complement of the pattern you wish to use.
- 2. Set ATTR\_PEN\_MODE to VAL\_AND\_MODE.
- 3. Set ATTR\_PEN\_FILL\_COLOR to VAL\_WHITE.
- 4. Use a canvas draw function, (for example, CanvasDrawRect) to fill the area.
- 5. Set ATTR\_PEN\_PATTERN to the desired pattern.
- 6. Change the ATTR\_PEN\_MODE to VAL\_OR\_MODE.
- 7. Change the ATTR\_PEN\_FILL\_COLOR to the desired pattern color.
- 8. Draw again.

# **Using Rect and Point Structures**

Two structures, Rect and Point are defined in the userint.h include file. These structures are used to specify locations and areas in Cartesian coordinate systems, such as those used in canvas controls and bitmaps. Many canvas control functions use these structures.

The Rect structure specifies the location and size of a rectangle. It is defined as follows.

```
typedef struct
    {
    int top;
    int left;
    int height;
    int width;
    } Rect;
```

A Point structure specifies the location of a point. It is defined as follows.

```
typedef struct
    {
    int x;
    int y;
    } Point;
```

#### **Functions and Macros for Making Rects and Points**

You might need to create a Rect or Point just to pass it to a function. You can avoid creating a variable for this by using one of the following functions.

```
Rect MakeRect (int top, int left, int height, int width);
Point MakePoint (int x, int y);
```

For example,

```
CanvasDrawPoint (panel, ctrl, MakePoint (30, 40));
```

You can also use these function to initialize variables. For example,

```
Rect r = MakeRect (10, 20, 100, 130);
```

There are special values for the Rect height and width. Also, there are some macros for creating commonly used rectangles. The documentation for each function indicates when these values and macros are applicable. See the following table.

Name	Value or Definition	Description
VAL_TO_EDGE	-1	Set the Rect width (or height) to the distance from the Rect left (or top) to the right (or bottom) edge of the object.
VAL_KEEP_SAME_SIZE	-2	When copying objects (such as bitmaps), make the destination object the same size as the source object.
VAL_EMPTY_RECT	MakeRect (0, 0, 0, 0)	An empty rectangle.
VAL_ENTIRE_OBJECT	MakeRect (0, 0, VAL_TO_EDGE, VAL_TO_EDGE)	Make the Rect the size of the object (for example, the canvas or bitmap).

Table 3-18. Values and Macros for Rect Structures

## **Functions for Modifying Rects and Points**

Use the following functions to set or modify the values in a Rect or Point structure.

- RectSet to set each of the four values of an existing Rect structure.
- RectSetFromPoints to set a Rect so that it defines the smallest rectangle that encloses two points.
- RectSetBottom to set the height of a Rect so that the bottom is a given value. (The bottom is *not* enclosed by the rectangle.)

- RectSetRight to set the height of a Rect so that the right edge is a given value. (The right edge is *not* enclosed by the rectangle.)
- RectSetCenter to set the top and left of a Rect so that it is centered around a give value, while keeping the same size.
- RectOffset to modify the top and left of a Rect so as to shift the location of the rectangle.
- RectMove to set the top and left of Rect to a given Point.
- RectGrow to modify the values in a Rect so that the rectangle grows or shrinks around its current center point.
- PointSet to set the two values in an existing Point structure.

#### **Functions for Comparing or Obtaining Values from Rects and Points**

Use the following functions to compare or obtain values from a Rect or Point structure.

- RectBottom to obtain the location of the bottom of a rectangle.
- RectRight to obtain the location of the right edge of a rectangle.
- RectCenter to obtain the location of the center of a rectangle.
- RectEqual to determine if two rectangles are identical.
- RectEmpty to determine if a rectangle is empty.
- RectContainsPoint to determine if a rectangle encloses a given point.
- RectContainsRect to determine if a rectangle completely encloses another rectangle.
- RectSameSize to determine if two rectangles are the same size.
- RectUnion to set a Rect to the smallest rectangle that encloses two given rectangles.
- RectIntersection to set a Rect to the largest rectangle that is enclosed by two given rectangles.
- PointEqual to determine if two points are at the same location.
- PointPinnedToRect to modify a Point structure, if needed, to ensure that it is within a give rectangle.

# **Using Bitmap Objects**

A bitmap is a two-dimensional grid of pixels representing an image. There are some functions, such as PlotBitmap (for graph controls) and DisplayImageFile (for picture controls) which read an image out of a file and directly display it on a control.

There are other functions, however, which create or extract a bitmap, store them in memory, and return a bitmap ID. You can then use the bitmap ID in other functions.

## **Functions for Creating, Extracting, or Discarding Bitmap Objects**

Use the following functions to create, extract, or discard bitmap objects.

- NewBitmap to create a bitmap object from scratch.
- GetBitmapFromFile to create a bitmap object using image data read from a file.
- GetCtrlBitmap to create a bitmap object from an image contained in a picture, picture ring, picture button, canvas, or graph control.
- GetCtrlDisplayBitmap to create a bitmap object from the current appearance of a control.
- GetPanelDisplayBitmap to create a bitmap object from the current appearance of a specified rectangular area of a panel.
- ClipboardGetBitmap to create a bitmap object from an image (if any) in the system clipboard
- DiscardBitmap to remove a bitmap from memory.

If you want to display images that are not rectangular or that have "holes" in them, you can use bitmaps that have a transparent background. If you are creating your bitmap image from scratch, you can achieve transparency by using the **mask** parameter to the NewBitmap function.

#### **Windows Metafiles**

A Windows metafile (.WMF) contains a description of an image that is scaleable without distortion. The description consists of a set of drawing commands rather than a bitmap. Windows metafiles are available only on Windows 95 and NT. You can load them using the GetBitmapFromFile function.

## **Functions for Displaying or Copying Bitmap Objects**

Use the following functions to display a bitmap object in a control or copy an image from a bitmap object to a control.

- CanvasDrawBitmap to display a bitmap in a canvas control.
- SetCtrlBitmap to set an image in a picture, picture ring, picture button, or graph control from a bitmap object. Can be used to replace an existing image create a new image.
- ClipboardPutBitmap to copy image data from a bitmap object to the system clipboard.

#### **Functions for Retrieving Image Data from Bitmap Objects**

Use the following functions to retrieve image data from bitmap objects.

- GetBitmapInfo to obtain size information about the image associated with a bitmap. This information can then be used in allocating the buffers to be passed to GetBitmapData.
- AllocBitmapData to allocate the buffers necessary for calling GetBitmapData. This is an alternative to calling GetBitmapInfo and allocating the buffers yourself.
- GetBitmapData to obtain the bit values that define the image associated with a bitmap.

## **Programming with Timer Controls**

This section describes the functions and attributes that you can use to manipulate timer control activity.

#### **Timer Control Functions**

You can create timer controls with the User Interface Editor or by using the function NewCtrl. There is no limit to the number of timer controls you can use, but timer callbacks are called sequentially. If two or more timers have identical time intervals, their callbacks are called in an undefined, but consistent order.

Use SuspendTimerCallbacks to stop calls to all the timer control callbacks until ResumeTimerCallbacks restores timer control activity. These functions do not affect the interval schedules or set the enabled/disabled state of individual timer controls, but rather activate and deactivate a blanket suspension over *all* timer callbacks.

Use ResetTimer to reset the interval start times of individual timer controls, all timer controls on a panel, or all timer controls on all panels.

#### **Using Timer Callbacks**

The timer callback has the same prototype as other control callbacks.

eventData1 is a pointer to a double that represents the current time in seconds. The time base is the same as that used by the Timer function in the Utility Library. eventData2 is a pointer to a double that represents the time that has elapsed since the last call to the timer callback. The elapsed time is set to zero if the callback has not been called previously.

When the callback function is called at the end of an interval, event is EVENT\_TIMER\_TICK.

#### **Timer Control Attributes**

Table 3-19 lists the timer control attributes you can retrieve or change using SetCtrlAttribute and GetCtrlAttribute.

 Name
 Type
 Description

 ATTR\_INTERVAL
 double
 The time interval of the timer control in seconds.

 ATTR\_ENABLED
 int
 0 = timer control is disabled

 1 = timer control is enabled

Table 3-19. Timer Control Attributes

#### **Timer Control Attribute Discussion**

ATTR\_INTERVAL sets the time interval of the timer control in seconds. An interval of zero results in timer events occurring as fast as CVI can generate them. Setting the interval less than the system clock resolution results in an interval equivalent to the system clock resolution. If the timer has already been started, setting ATTR\_INTERVAL resets the timer. The ATTR\_INTERVAL default value is one second.

Note: The time intervals you specify are minimum values. System activity, including processing of user callbacks, can cause timer callbacks to be late or skipped. If you have a need for real time response, do not write into your program operations that take significant amounts of time without giving CVI a chance to process events.

ATTR\_ENABLED determines whether a timer control's callback is called at each interval. The ATTR\_ENABLED default value is TRUE.

#### **Details of Timer Control Operations**

After a timer control is created or loaded, the timer does not start until a call is made to RunUserInterface, GetUserEvent, or ProcessSystemEvents. This ensures that you can create or load several timer controls and have them start at the same time.

The timer interval schedules are not affected by SuspendTimerCallbacks, ResumeTimerCallbacks, or by changing the value of ATTR\_ENABLED. You can reset timer interval schedules by calling ResetTimer. The length of the timer intervals can be changed using the ATTR\_INTERVAL attribute. Changing the ATTR\_INTERVAL value also causes the interval schedule for the timer control to be reset.

Timer callbacks are not called unless a call to RunUserInterface, GetUserEvent, or ProcessSystemEvents is in effect. Calling RunUserInterface, GetUserEvent, and ProcessSystemEvents does not alter interval schedules already in effect, but may trigger an overdue callback. If, upon calling one of these functions, the time since the last callback is greater than the ATTR\_INTERVAL value for a timer control, the callback is called. Only one such overdue callback is called no matter how many intervals have elapsed. Overdue callbacks do not cause the next interval to be rescheduled. Thus, the time between the overdue callback and the next regularly scheduled callback may be less than the ATTR\_INTERVAL value.

Calling ResumeTimerCallbacks or setting ATTR\_ENABLED to TRUE does not trigger overdue callbacks.

## **Programming with Graph and Strip Chart Controls**

This section describes how you can use the User Interface Library functions to control the elements of user interface graphs and strip charts.

#### **Functions for Graphs and Strip Charts**

As with any other control, you can create graphs and strip charts in the User Interface Editor or programmatically using NewCtrl. For details, see the *Programming with Controls* section of this chapter. You also use GetCtrlAttribute and SetCtrlAttribute to control the attributes of graphs and strip charts. The following functions are provided to programmatically change the axis ranges of graphs and strip charts and to change the scaling mode.

Use GetAxisRange to obtain the current x and y axis ranges of a graph or strip chart control.

Use SetAxisRange to set the current x and y axis ranges of a graph or strip chart control.

#### **Functions for Graphs Only**

Use one of the following functions to add a plot to a graph.

- Use PlotArc to plot an arc.
- Use PlotBitmap to plot a bitmap image.
- Use PlotIntensity or PlotScaledIntensity to plot a color-intensity graph.
- Use PlotLine to plot a single line segment.
- Use PlotOval to plot an oval.
- Use PlotPoint to plot a point.
- Use PlotPolygon to plot a polygon.
- Use PlotRectangle to plot a rectangle.
- Use PlotText to plot a text string.
- Use PlotWaveform to plot a waveform array.
- Use PlotX to plot X versus its indices.
- Use PlotXY to plot X versus Y.
- Use PlotY to plot Y versus its indices.

If the graph is visible, the program draws the plot immediately.

Use DeleteGraphPlot to remove one or all plots from a graph. DeleteGraphPlot frees the appropriate plots from memory.

Use GetPlotAttribute to obtain an attribute of a particular graph plot.

Use SetPlotAttribute to set an attribute of a particular graph plot.

Use one of the following functions to control the cursors in a graph.

- Use GetGraphCursor to obtain the current position of a specified cursor.
- Use SetGraphCursor to set the position of a specified cursor.
- Use GetGraphCursorIndex to obtain the plot handle and the array index of the plot that the specified cursor is attached to.
- Use SetGraphCursorIndex to attach a cursor to a particular data point.
- Use GetActiveGraphCursor to obtain the index of the active graph cursor.
- Use SetActiveGraphCursor to set the active graph cursor.
- Use GetCursorAttribute to obtain an attribute of a specified cursor.
- Use SetCursorAttribute to an attribute of a specified cursor.

## **Functions for Strip Charts Only**

- Use PlotStripChart to add one or more points to the strip chart traces. If the strip chart is visible, the points are drawn as you add them to each trace.
- Use PlotStripChartPoint to add one point to a strip chart that contains exactly one trace.
- Use ClearStripChart to clear all points from the strip chart. If the strip chart is visible, the points on the plot clear.
- Use GetTraceAttribute to obtain an attribute of a particular strip chart trace
- Use SetTraceAttribute to set an attribute of a particular strip chart trace.

## **Processing Graph and Strip Chart Events**

Graph events are processed like any other control. See the *Processing Control Events* section of this chapter for details of graph event processing. When the user moves a cursor on a graph a commit event is generated.

Because strip charts do not generate commit events, you can only process events from a strip chart through a callback function. See the *Processing Control Events* section of this chapter for details about processing events using callbacks.

## **Graph and Strip Chart Attributes**

Table 3-20 lists control attributes you can access through GetCtrlAttribute and SetCtrlAttribute.

Table 3-20. Graph and Strip Chart Attributes

#### For graphs and strip charts

Name	Туре	Description
ATTR_BORDER_VISIBLE	int	1 = border visible 0 = border invisible
ATTR_EDGE_STYLE	int	VAL_RAISED_EDGE or VAL_FLAT_EDGE or VAL_RECESSED_EDGE
ATTR_GRAPH_BGCOLOR	int	Graph border background color (RGB value—see discussion that follows this table).
ATTR_GRID_COLOR	int	Grid color (RGB value—see discussion that follows this table).
ATTR_INNER_LOG_MARKERS_ VISIBLE	int	Specifies whether labels and tick marks are shown next to the inner grid lines of log scale axes. (Default value: FALSE)
ATTR_PLOT_AREA_HEIGHT	int	The height of the plotting area in pixels (GetCtrlAttribute only).
ATTR_PLOT_AREA_WIDTH	int	The width of the plotting area in pixels (GetCtrlAttribute only).
ATTR_PLOT_BGCOLOR	int	Plot background color (RGB value—see discussion that follows this table).

Name	Туре	Description
ATTR_XAXIS_GAIN	double	The factor used to scale the value labels on the X axis. For example, if the X value is 10.0 and ATTR_XAXIS_GAIN is 2.0, then the label on the X axis shows as 20.0. (Default value: 1.0)
ATTR_XAXIS_OFFSET	double	The amount added to the value labels on the X axis. For example, if the X value is 10.0 and ATTR_XAXIS_OFFSET is 5.0, then the label on the X axis shows as 15.0. The X value is multiplied by ATTR_XAXIS_GAIN before ATTR_XAXIS_OFFSET is added. (Default value: 0.0)
ATTR_XDIVISIONS	int	(1 to 100, or VAL_AUTO)
ATTR_XENG_UNITS	int	(-308 to 308)
ATTR_XFORMAT	int	See Table 3-12.
ATTR_XGRID_VISIBLE	int	1 = x-grid visible 0 = x-grid invisible
ATTR_XLABEL_VISIBLE	int	1 = x-label visible 0 = x-label invisible
ATTR_XNAME	char *	x-axis name.
ATTR_XUSE_LABEL_STRINGS	int	Whether the X axis numerical value labels are replaced by strings associated with the X values. These strings can be specified either in the User Interface Editor or by calling the InsertAxisItem function.
ATTR_YAXIS_GAIN	double	The factor used to scale the value labels on the Y axis. For example, if the Y value is 10.0 and ATTR_YAXIS_GAIN is 2.0, then the label on the Y axis shows as 20.0. (Default value: 1.0)

Name	Туре	Description
ATTR_YAXIS_OFFSET	double	The amount added to the value labels on the Y axis. For example, if the Y value is 10.0 and ATTR_YAXIS_OFFSET is 5.0, then the label on the Y axis shows as 15.0. The Y value is multiplied by ATTR_YAXIS_GAIN before ATTR_YAXIS_OFFSET is added. (Default value: 0.0)
ATTR_YAXIS_REVERSE	int	Whether to reverse the orientation of the Y axis so that the lowest value is shown at the top. If the orientation of the Y axis is reversed, the vertical orientation of the plots is also reversed.
ATTR_YUSE_LABEL_STRINGS	int	Whether the Y axis numerical value labels are replaced by strings associated with the Y values. These strings can be specified either in the User Interface Editor or by calling the InsertAxisItem function.
ATTR_XNAME_LENGTH	int	Number of characters in x-axis name; GetCtrlAttribute only.
ATTR_XPRECISION	int	(0 to 15, or VAL_AUTO)
ATTR_XYLABEL_BOLD	int	1 = x & y axes labels bold 0 = x & y axes labels not bold
ATTR_XYLABEL_COLOR	int	x- and y-axis label color (RGB value—see discussion that follows this table).
ATTR_XYLABEL_FONT	char *	x- and y-axis label font (see Table 3-5).
ATTR_XYLABEL_FONT_NAME_LENGTH	int	Number of characters in font of x & y-axis labels; GetCtrlAttribute only.
ATTR_XYLABEL_ITALIC	int	1 = x & y axes labels in italics 0 = x & y axes labels not in italics

Name	Туре	Description
ATTR_XYLABEL_POINT_SIZE	int	Point size of x & y axis names; range = 0 to 32767.
ATTR_XYLABEL_STRIKEOUT	int	1 = x & y axes labels have strikeout 0 = x & y axes labels do not have strikeout
ATTR_XYLABEL_UNDERLINE	int	1 = x & y axes labels underlined 0 = x & y axes labels not underlined
ATTR_XYNAME_BOLD	int	1 = x & y axes names bold 0 = x & y axes names not bold
ATTR_XYNAME_COLOR	int	x- and y-axis name color (RGB value - see discussion that follows this table).
ATTR_XYNAME_FONT	char *	x- and y-axis name font (see Table 3-5).
ATTR_XYNAME_FONT_NAME_LENGTH	int	Number of characters in font of x & y-axis names; GetCtrlAttribute only.
ATTR_XYNAME_ITALIC	int	1 = x & y axes names in italics 0 = x & y axes names not in italics
ATTR_XYNAME_POINT_SIZE	int	Point size of x & y axes names range = 0 to 32767.
ATTR_XYNAME_STRIKEOUT	int	1 = x & y axes names have strikeout 0 = x & y axes names do not have strikeout
ATTR_XYNAME_UNDERLINE	int	1 = x & y axes names underlined 0 = x & y axes names not underlined
ATTR_YDIVISIONS	int	Range: 1 to 100, or VAL_AUTO
ATTR_YENG_UNITS	int	Range: -308 to 308
ATTR_YFORMAT	int	See Table 3-12.

Name	Type	Description
ATTR_YGRID_VISIBLE	int	1 = y-grid visible 0 = y-grid invisible
ATTR_YLABEL_VISIBLE	int	1 = y-label visible 0 = y-label invisible
ATTR_YMAP_MODE	int	VAL_LINEAR or VAL_LOG
ATTR_YNAME	char *	y-axis name
ATTR_YNAME_LENGTH	int	Number of characters in y-axis name GetCtrlAttribute only.
ATTR_YPRECISION	int	Range: 0 to 15, or VAL_AUTO

## For graphs only

Name	Туре	Description
ATTR_ACTIVE_YAXIS	int	Which of the two Y axes is used in plotting, setting a Y axis attribute, setting the Y axis range, or creating a graph cursor.  Values: VAL_LEFT_YAXIS,  VAL_RIGHT_YAXIS.
ATTR_COPY_ORIGINAL_DATA	int	See discussion below this table.
ATTR_DATA_MODE	int	VAL_RETAIN or VAL_DISCARD (see discussion that follows this table).
ATTR_ENABLE_ZOOMING	int	Whether the end-user can interactively zoom and pan the graph viewport.
		Default: FALSE
ATTR_NUM_CURSORS	int	Number of cursors (0 to 10).
ATTR_REFRESH_GRAPH	int	1 = plot to screen immediately 0 = do not plot to screen until graph is rescaled, overlapped, hidden, or ATTR_REFRESH_GRAPH = 1

## For graphs only (Continued)

Name	Туре	Description
ATTR_SHIFT_TEXT_PLOTS	int	1 = text is shifted so it will not be clipped 0 = text is shifted do it may be clipped
ATTR_SMOOTH_UPDATE	int	1 = use off-screen bitmap 0 = do not use off-screen bitmap (See discussion that follows this table.)
ATTR_XMAP_MODE	int	VAL_LINEAR or VAL_LOG.
ATTR_XMARK_ORIGIN	int	1 = tick marks along x-origin 0 = no tick marks along x-origin
ATTR_XREVERSE	int	Whether to reverse the orientation of the X axis so that the lowest value is shown at the right. If the orientation of the X axis is reversed, the horizontal orientation of the plots is also reversed.
ATTR_YMARK_ORIGIN	int	1 = tick marks along y-origin 0 = no tick marks along y-origin

## For strip charts only

Name	Type	Description
ATTR_NUM_TRACES	int	Number of traces (1-64).
ATTR_POINTS_PER_SCREEN	int	Range: 3 to 10000
ATTR_SCROLL_MODE	int	VAL_SWEEP or VAL_CONTINUOUS or VAL_BLOCK (See discussion that follows this table.)

## $For graph \ cursors \ (GetCursorAttribute \ and \ SetCursorAttribute)$

Name	Type	Description
ATTR_CROSS_HAIR_STYLE	int	See Table 3-21.
ATTR_CURSOR_COLOR	int	Cursor color (RGB value—see discussion that follows this table.)
ATTR_CURSOR_MODE	int	VAL_FREE_FORM or VAL_SNAP_TO_POINT (See discussion that follows this table.)
ATTR_CURSOR_POINT_STYLE	int	See Table 3-22.
ATTR_CURSOR_YAXIS	int	Used to change the Y axis to which a graph cursor is associated. When you create a graph cursor, its associated Y axis is determined by the value of ATTR_ACTIVE_YAXIS.  Afterwards, the association can be changed using ATTR_CURSOR_YAXIS. The associated axis serves as the reference for the cursor position coordinates used in calls to SetGraphCursor and GetGraphCursor.  Values: VAL_LEFT_YAXIS, VAL_RIGHT_YAXIS.

## For graph plots (GetPlotAttribute and SetPlotAttribute) and for strip chart traces (GetTraceAttribute and SetTraceAttribute)

Name	Type	Description
ATTR_LINE_STYLE	int	See Table 3-23.
ATTR_PLOT_STYLE	int	See Table 3-24.
ATTR_TRACE_COLOR	int	Trace color (RGB value—see discussion that follows this table).
ATTR_TRACE_POINT_STYLE	int	See Table 3-22.
ATTR_TRACE_VISIBLE	int	1 = trace is visible; 0 = trace is invisible

## For graph plots (GetPlotAttribute and SetPlotAttribute)

Name	Type	Description
ATTR_INTERPOLATE_PIXELS	int	Enable the calculation of the displayed color for each pixel by using interpolation.  n 0 = Interpolate pixels 1 = No Interpolation (Valid for Intensity plots only.)
ATTR_NUM_POINTS	int	Number of points in the plot data. For intensity plots, the number of points will be equal to the number of points in the 2 dimensional z-data array (valid for X, Y, XY, Waveform, Polygon and Intensity plots only). (GetPlotAttribute only.)
ATTR_PLOT_FONT	char *	The font name for the text plot (valid for PlotText plots only).
ATTR_PLOT_FONT_NAME_LENGTH	int	The length of the font name for the text plot (valid for PlotText plots only). (GetPlotAttribute only.)
ATTR_PLOT_ORIGIN	int	Determines the placement of a text string or bitmap with respect to the coordinates specified in a call to PlotText or PlotBitmap. See discussion following this table.
ATTR_PLOT_SNAPPABLE	int	By default, graph cursors for which ATTR_CURSOR_MODE is VAL_SNAP_TO_POINT snap to the closest plot. To prevent cursors from snapping to a particular plot, set ATTR_PLOT_SNAPPABLE for the plot to FALSE.
ATTR_PLOT_YAXIS	int	Used to change the Y axis with which a plot is associated. When a plot is first plotted, the Y axis to which it is associated is determined by the value of ATTR_ACTIVE_YAXIS.
		Afterwards, the association can be changed using ATTR_PLOT_YAXIS.  Values: VAL_LEFT_YAXIS,  VAL_RIGHT_YAXIS.

For graph plots (GetPlotAttribute and SetPlotAttribute) (Continued)

Name	Type	Description
ATTR_PLOT_ZPLANE_POSITION	int	The drawing order of the graph plot. The lowest ordered plot(0) is on top. Valid Range: 0 to (Number of Plots - 1)
ATTR_TRACE_BGCOLOR	int	The RGB color value for the background text of a text plot or the fill color for drawn object type plot (valid for Text, Rectangle, Polygon, Oval and Arc plots only).
ATTR_PLOT_XDATA	void *	A void pointer to a buffer for the X data to be copied to. (Valid for X, XY and Polygon plots only.) (GetPlotAttribute only.)
ATTR_PLOT_YDATA	void *	A void pointer to a buffer for the Y data to be copied to (valid for Y, XY, Waveform and Polygon plots only).  (GetPlotAttribute only.)
ATTR_PLOT_ZDATA	void *	A void pointer to a buffer for the Z data to be copied to. This buffer will be a two-dimensional array (valid for Intensity plots only). (GetPlotAttribute only.)
ATTR_PLOT_XDATA_TYPE	int	The type of data in the X data plot (valid for X, XY and Polygon plots only). (GetPlotAttribute only.)
ATTR_PLOT_YDATA_TYPE	int	The type of data in the Y data plot (valid for Y, XY, Waveform and Polygon plots only). (GetPlotAttribute only.)
ATTR_PLOT_ZDATA_TYPE	int	The type of data in the Z data plot (valid for Intensity plots only).  (GetPlotAttribute only.)

Name	Type	Description
ATTR_PLOT_XDATA_SIZE	int	The number of bytes in the X data plot data (valid for X, XY and Polygon plots only). (GetPlotAttribute only.)
ATTR_PLOT_YDATA_SIZE	int	The number of bytes in the Y data plot data (valid for Y, XY, Waveform and Polygon plots only). (GetPlotAttribute only.)
ATTR_PLOT_ZDATA_SIZE	int	The number in bytes in the Z data plot data (valid for Intensity plots only). (GetPlotAttribute only.)

For graph plots (GetPlotAttribute and SetPlotAttribute) (Continued)

#### **Graph Attribute Discussion**

An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. You can use the User Interface Library function MakeColor to create an RGB value from red, green, and blue color components. See Table 3-3 for a list of common color values.

The ATTR\_DATA\_MODE attribute controls whether LabWindows/CVI keeps or discards the scaled plot data for subsequent plots after drawing the data to the screen. If you set the attribute to VAL\_RETAIN, LabWindows/CVI retains scaled plot data in memory and accesses the data when the plot is overlapped or hidden. If you set the attribute to VAL\_DISCARD, the scaled plot data is freed from memory as soon as the plot is drawn. This conserves memory, but plots are lost if the graph is rescaled, overlapped, or hidden.

The ATTR\_COPY\_ORIGINAL\_DATA attribute specifies whether LabWindows/CVI makes a copy of the original plot data for each new plot added to the graph. The original plot data is needed whenever the graph is rescaled and the original plot data has been overwritten in your program.

The ATTR\_SMOOTH\_UPDATE attribute specifies whether LabWindows/CVI stores a copy of the graph in an off-screen bitmap. Using an off-screen bitmap results in less plot flicker and smoother cursor movement, but consumes more memory.

The ATTR\_SCROLL\_MODE attribute specifies the scrolling mode of the strip chart. If you set the attribute to VAL\_CONTINUOUS, old data scrolls off the left edge of the plot area as new data plots at the right edge. If you set the attribute to VAL\_SWEEP, new data overwrites old data from left to right. If you set the attribute to VAL\_BLOCK, the entire plot area is erased when data reaches the right edge of the area.

The ATTR\_CURSOR\_MODE specifies the behavior of a graph cursor. You can move VAL\_FREE\_FORM cursors to any location inside the plot area. VAL\_SNAP\_TO\_POINT cursors snap to the nearest data point when released.

Table 3-21 shows the cursor styles associated with ATTR\_CROSS\_HAIR\_STYLE. (Assume that ATTR\_CURSOR\_POINT\_STYLE is set to VAL\_SIMPLE\_DOT.)

Table 3-21. Cursor Styles for ATTR\_CROSS\_HAIR\_STYLE

Value	Cross hair Style
VAL_LONG_CROSS	- -
VAL_VERTICAL_LINE	ļ
VAL_HORIZONTAL_LINE	
VAL_NO_CROSS	
VAL_SHORT_CROSS	- -

Table 3-22 shows the styles associated with ATTR\_CURSOR\_POINT\_STYLE and ATTR\_TRACE\_POINT\_STYLE.

Table 3-22. Styles for ATTR\_CURSOR\_POINT\_STYLE and ATTR\_TRACE\_POINT\_STYLE

Value Style Name	Cursor/ Point Style
VAL_EMPTY_SQUARE	
VAL_SOLID_SQUARE	
VAL_ASTERISK	*
VAL_DOTTED_EMPTY_SQUARE	□
VAL_DOTTED_SOLID_SQUARE	•
VAL_SOLID_DIAMOND	+
VAL_EMPTY_SQUARE_WITH_X	•
VAL_EMPTY_SQUARE_WITH_CROSS	<b>H</b>
VAL_BOLD_X	×
VAL_SMALL_SOLID_SQUARE	-

Table 3-22. Styles for ATTR\_CURSOR\_POINT\_STYLE and ATTR\_TRACE\_POINT\_STYLE (Continued)

Value Style Name	Cursor/ Point Style
VAL_SIMPLE_DOT	
VAL_EMPTY_CIRCLE	0
VAL_SOLID_CIRCLE	•
VAL_DOTTED_SOLID_CIRCLE	•
VAL_DOTTED_EMPTY_CIRCLE	0
VAL_BOLD_CROSS	+
VAL_CROSS	+
VAL_SMALL_CROSS	+
VAL_X	×
VAL_SMALL_X	×
VAL_DOTTED_SOLID_DIAMOND	*
VAL_EMPTY_DIAMOND	0
VAL_DOTTED_EMPTY_DIAMOND	*
VAL_SMALL_EMPTY_SQUARE	
VAL_NO_POINT	

Table 3-23 shows the line styles associated with ATTR\_LINE\_STYLE. (Assume that ATTR\_PLOT\_STYLE is set to VAL\_THIN\_LINE.)

Table 3-23. Line Styles for ATTR\_LINE\_STYLE

Value	Line Style
VAL_SOLID	
VAL_DASH	/
VAL_DOT	
VAL_DASH_DOT	/
VAL_DASH_DOT_DOT	//

Table 3-24 shows the plot styles associated with ATTR\_PLOT\_STYLE. (Assume that the point style is set to VAL\_ASTERISK.)

Value **Plot Style** VAL THIN LINE VAL FAT LINE VAL CONNECTED POINTS VAL\_SCATTER VAL THIN STEP VAL FAT STEP VAL VERTICAL BAR (not valid for strip charts) VAL\_HORIZONTAL\_BAR (not valid for strip charts) VAL BASE ZERO VERTICAL BARS (not valid for strip charts) VAL\_BASE\_ZERO\_HORIZONTAL\_BARS (not valid for strip charts)

Table 3-24. Plot Styles for ATTR\_PLOT\_STYLE

Note: Under Windows, the plot style VAL FAT LINE forces the line style to be VAL SOLID.

#### **Plot Origin Discussion**

When PlotText or PlotBitmap is called, the text string or bitmap is placed on the graph with respect to a point specified by coordinates passed into the function. The orientation of the string or bitmap with respect to the point is determined by the ATTR\_PLOT\_ORIGIN attribute. The attribute specifies where the point (that is, the origin) is with respect to the rectangle that implicitly encloses the string or bitmap. For example, VAL\_LOWER\_LEFT (the default value) specifies that the string or bitmap be plotted so that the lower left corner of its enclosing rectangle is at the point specified.

The possible values are shown in the following table.

Table 3-25. Values for ATTR PLOT ORIGIN

Value	Description
VAL_LOWER_LEFT	The lower left corner of the enclosing rectangle.
VAL_CENTER_LEFT	The midpoint of the left edge of the enclosing rectangle.
VAL_UPPER_LEFT	The upper left corner of the enclosing rectangle.
VAL_LOWER_CENTER	The midpoint of the bottom edge of the enclosing rectangle.
VAL_CENTER_CENTER	The center of the enclosing rectangle.
VAL_UPPER_CENTER	The midpoint of the top edge of the enclosing rectangle.
VAL_LOWER_RIGHT	The lower right corner of the enclosing rectangle.
VAL_CENTER_RIGHT	The midpoint of the right edge of the enclosing rectangle.
VAL_UPPER_RIGHT	The upper right corner of the enclosing rectangle.

#### Two Y Axis (graphs only)

There are always two Y axes on a graph. By default, only the left Y axis is visible.

You can make the Y axis visible by using the following code.

```
SetCtrlAttribute (panel, ctrl, ATTR_ACTIVE_YAXIS, VAL_RIGHT_AXIS); SetCtrlAttribute (panel, ctrl, ATTR_YLABEL_VISIBLE, 1);
```

You can choose to make either one, both, or none of the Y axes visible.

The ATTR\_ACTIVE\_YAXIS attribute determines which of the two Y axes are used for the following actions.

- Adding a plot to the graph. (The active Y axis serves as the scaling reference.)
- Setting a Y axis attribute. (Each Y axis has its own attribute values.)
- Setting the Y axis range.
- Creating a graph cursor. (The cursor is associated with the active Y axis.)

Once a plot has been added to a graph, you can associate it with the other Y axis by using the ATTR\_PLOT\_YAXIS attribute.

Once a graph cursor has been created, you can associate it with the other Y axis by using the ATTR\_CURSOR\_YAXIS attribute. The associated Y axis serves as the reference for the cursor position coordinates in calls to SetGraphCursor and GetGraphCursor.

## **Optimizing Graph Controls**

This section presents attributes related to graphing and discusses how various settings affect performance.

#### **Optimizing Speed**

The following attributes affect the speed and appearance of your graph displays as they update.

#### Speed and ATTR\_SMOOTH\_UPDATE

When you enable ATTR\_SMOOTH\_UPDATE or select Smooth Update in the Graph control editor, your graph updates first to an off-screen buffer and then to the screen.

ATTR\_SMOOTH\_UPDATE improves performance as follows.

- Eliminates flashing associated with plotting large plots.
- Optimizes speed when you use graph cursors.
- Optimizes speed when a graph is updated after it has been overlapped or hidden.

ATTR\_SMOOTH\_UPDATE has the following disadvantages.

- Initial plotting speed is slower.
- Memory usage increases.

Smooth updating of the graph is automatically disabled when you make the color of the plot background transparent or when a visible item overlaps the plot area.

ATTR\_SMOOTH\_UPDATE slows the initial graphing of a plot because a graph updates to the offscreen buffer before plotting to the screen. However, when another window is covering a plot, and then you remove that window, ATTR\_SMOOTH\_UPDATE lets LabWindows/CVI refresh a graph quickly because the graph already exists in the offscreen buffer.

#### Speed and VAL\_AUTO\_SCALE

When you enable autoscaling both the recalculation of the axes limits and the remapping of graph plots are dynamically adjusted with every new plot. As the number of existing plots on a graph increase, you need to try to minimize scaling adjustments because the time needed to recalculate and remap all of the existing plots increases. You may want to minimize delays by disabling autoscaling, which prevents the recalculation and remapping of the graph plots. To disable autoscaling, call the SetAxisRange function with the **xAxisScaling** and the **yAxisScaling** parameters each set to VAL\_MANUAL or VAL\_LOCK.

#### **Controlling How Graphs Refresh**

You can use the **refresh** parameter of the DeleteGraphPlot function and the RefreshGraph function to determine when a graph is updated. A "draw event" signals LabWindows/CVI to refresh its graph. The last parameter of DeleteGraphPlot determines when a draw event is generated. To delete plots from a graph, your program can call DeleteGraphPlot with **refresh** set to VAL\_DELAYED\_DRAW, so that plots do not disappear until a draw event occurs.

The following conditions generate draw events.

- A GUI object covers the plot area.
- Almost any graph attribute changes.
- Adding a new plot while REFRESH\_GRAPH is enabled.
- DeleteGraphPlot is called with the **refresh** parameter set to VAL\_IMMEDIATE\_DRAW.
- The program enables REFRESH\_GRAPH through SetCtrlAttribute.
- The cursor moves over the graph.
- The program calls RefreshGraph.
- A call to ProcessDrawEvents or ProcessSystemEvents updates graph attribute changes. If a plot update is pending as well, the attribute change makes that plot update, too.

The preferable way to delete a plot and then plot a new one is to set refresh to VAL\_DELAYED\_DRAW when deleting, then plot the new plot. When you do this, and at the same time you enable smooth updating, you eliminate screen flashing and improve the speed of the update.

DeleteGraphPlot deletes all plots on a graph when the **plotHandle** parameter is set to -1.

ATTR\_REFRESH\_GRAPH determines whether your program plots on a graph control immediately or plots after the graph is rescaled, overlapped, hidden or the attribute is enabled.

When your program builds a multi-plot image, for which only the final appearance is of interest, the attribute should be turned off before plotting begins, and turned on when it ends. This causes only one draw event to occur, instead of one for each plot. Plotting occurs even more rapidly when you enable the smooth updates attribute. Plots that you add while REFRESH\_GRAPH is disabled are held in *pending* status: they are part of the graph, but are invisible until a draw event takes place. Pending plots only appear after a call to RefreshGraph or when the ATTR\_REFRESH\_GRAPH attribute is enabled.

#### **Optimizing Memory Usage**

You can optimize memory usage by disabling the ATTR\_COPY\_ORIGINAL\_DATA attribute and the ATTR\_DATA\_MODE setting, but the savings are not significant in comparison to the overall amount of memory that LabWindows/CVI uses.

The ATTR\_SMOOTH\_UPDATE graph attribute saves an off-screen bitmap of the graph. You can save memory by disabling this attribute.

The ATTR\_DATA\_MODE graph attribute lets you retain or discard scaled plot data for subsequent plots.

- When you disable ATTR\_SMOOTH\_UPDATE and set ATTR\_DATA\_MODE to discard, you get the following results.
  - No data prints with PrintPanel or PrintCtrl.
  - Plot data is lost when the graph is rescaled, hidden, overlapped or when a draw event occurs. (Reasons for rescaling are listed later in this subsection.)
- When you enable ATTR\_SMOOTH\_UPDATE and set ATTR\_DATA\_MODE to discard, you get the following result.
  - Plot data is lost when the graph is rescaled or when a draw event occurs.

Note: You cannot delete plots that you add to a graph while ATTR\_DATA\_MODE is set to discard because the plot functions do not return a plot ID. The graph behaves as if the plot does not exist.

Your graph can rescale for the following reasons.

- SetAxisRange is called.
- ATTR\_XMAP\_MODE or ATTR\_YMAP\_MODE changes.
- You draw a new plot when autoscaling is enabled and the minimum or maximum values change.
- You change graph attributes that affect the size of the plot area.

The ATTR\_COPY\_ORIGINAL\_DATA graph attribute determines whether the graph control will keep its own copy of the plot data. When disabled, the graph control maintains a pointer to the original array data used that was used when you originally made a call to that plotting function. If the data in the original array changes or is deallocated, either the graph displays incorrect data or an invalid pointer error occurs. ATTR\_COPY\_ORIGINAL\_DATA only affects graph plots that are associated with arrays, such as PlotWaveform and PlotXY. The graph control only needs to go back to the original data when the graph is rescaled.

Note: ATTR\_COPY\_ORIGINAL\_DATA is only valid if ATTR\_DATA\_MODE is set to retain data.

## **Programming with Pop-Up Panels**

Use InstallPopup to display and activate a panel as a dialog box. You must load a panel with the LoadPanel function or create the panel using the NewPanel function.

After a pop-up panel is installed, users can perform operations in LabWindows/CVI only on the pop-up panel.

Only the active pop-up panel can generate events (with the exception EVENT\_PANEL\_MOVE, EVENT\_PANEL\_SIZE, and EVENT\_CLOSE events from other panels). Use callback functions to process any kind of event or GetUserEvent to only process commit events. GetUserEvent returns the ID of the control that caused the event. GetUserEvent can operate in one of two ways.

- GetUserEvent waits for the user to generate an event before returning to the calling program.
- GetUserEvent returns immediately whether or not an event has occurred.

Use RemovePopup to remove either the active pop-up panel or all pop-up panels. RemovePopup does not unload the panel from memory.

Use SetSystemPopupAttributes and GetSystemPopupAttributes to set or obtain the values of attributes that affect all of the pop-up panel. The predefined pop-up panels are accessed through the following functions.

ConfirmPopup
DirSelectPopup
FileSelectPopup
FontSelectPopup
GenericMessagePopup
MessagePopup
MultifileSelectPopup
PromptPopup
SetFontPopupDefaults
WaveformGraphPopup
XGraphPopup
YGraphPopup
YGraphPopup

These functions handle the installation, user interaction with, and removal of the pop-up panels.

## **Using the System Attributes**

The system attributes are set and obtained using the SetSystemAttribute and GetSystemAttribute functions. They are attributes that apply to the User Interface Library in general, rather than to particular instances of user interface objects. The following table lists the system attributes.

Table 3-26. System Attributes

Attribute	Type	Notes
ATTR_ALLOW_UNSAFE_TIMER_EVENTS	int	1 - Allow unsafe timer events. 0 - Do not allow unsafe time events (the default) Windows 95 and NT only. See discussion below.
ATTR_ALLOW_MISSING_CALLBACKS	int	1 - LoadPanel and LoadMenuBar return a valid panel or menu bar handle even if not all callback functions referenced in the .uir file can be found.  0 - LoadPanel and LoadMenuBar return an error code if not all callback functions referenced in the .uir file can be found (the default).
ATTR_REPORT_LOAD_FAILURE	int	1 - Display a message when LoadPanel or LoadMenuBar fail (the default) 0 - Do not display a message when LoadPanel or LoadMenuBar fail See discussion below.
ATTR_SUPPRESS_EVENT_PROCESSING	int	1 - No events are processed 0 - Events are processed normally (the default) See discussion below.

#### **Unsafe Timer Events**

By default, timer control callbacks do not occur on Windows while you are moving or sizing a window, while the system menu is pulled down, or while the Alt-Tab key is pressed. (These conditions are called *event-blocking conditions*.) On Windows 95 and NT, you can use the ALLOW\_UNSAFE\_TIMER\_EVENTS attribute to enable timer events under some, but not all, of the event-blocking conditions. If you set the ALLOW\_UNSAFE\_TIMER\_EVENTS attribute to TRUE, timer events are blocked only under the following conditions.

- You have clicked on a window title bar, you are holding the mouse button down, but you are not moving the mouse.
- You are moving or resizing a window, and the Windows 95 "Show Window Contents While Dragging" option is disabled (or you are running on Windows NT.)

There are several limitations to this feature. One limitation is that while an event-blocking condition is in effect, timer callbacks are called no faster than once per 55 milliseconds.

Another limitation is that if a timer callback is called during an event-blocking condition and the callback causes events to be processed, mouse and keyboard input can behave erratically. Your program can cause this to happen in the following ways.

- The timer callback function calls ProcessSystemEvents in a loop.
- The timer callback function calls RunUserInterface, GetUserEvent, or a popup panel function such as MessagePopup or FileSelectPopup.
- Program execution is suspended in the timer callback function because of a breakpoint or run-time error.

In either case, the system functions normally once the timer callback returns.

This problem is inherent to Windows and occurs regardless of the development environment.

You should not enable this attribute until the code in your timer callbacks has been thoroughly debugged. The behavior of the system is undefined if you hit a breakpoint or run-time error when an event-blocking condition is in effect.

#### **Reporting Load Failures**

The LoadPanel, LoadPanelEx, LoadMenuBar, and LoadMenuBarEx functions can fail for many reasons. For instance, the library may not be able to find the .uir file. Or a callback function specified in the panel or menu bar may not be defined in the project, executable, or DLL.

It is not unusual for a load functions to fail in a standalone executable even though it succeeded in LabWindows/CVI. If you do not check for errors in your program, the behavior of the program can be very confusing. ATTR\_REPORT\_LOAD\_FAILURE, when enabled, causes an error message to be displayed when one of the load functions fails. The error message is displayed in all cases except when debugging and the Break on Library Errors feature are in effect. The attribute is enabled by default.

If a load function fails in a standalone executable or DLL created in an external compiler, the most common reasons are:

• The executable was created in a directory different than where the LabWindows/CVI project file was saved. This can cause the library to fail to find the .uir file.

- You did not create a .UIR Callbacks Object File, or you did not add it to your external compiler project. (See the External Compiler Support command in the **Build** menu of the Project Window.) This will cause the library to fail to find callback functions referenced in the .uir file.
- You did not call InitCVIRTE at the beginning of your program or in DLLMain. This will cause the library to fail to find callback functions referenced in the .uir file.
- Your callback functions are in a DLL but are not exported by the DLL, and you are not using LoadPanelEx or LoadMenuBarEx. This will cause the library to fail to find callback functions referenced in the .uir file.

## **Suppressing Event Processing**

If you call QuitUserInterface to terminate a RunUserInterface call and there are already events in the event queue, RunUserInterface processes these events before it terminates. To ensure that no events are processed and that no callbacks are called before RunUserInterface terminates, set the ATTR\_SUPPRESS\_EVENT\_PROCESSING attribute to 1. This attribute also suppresses event processing and callbacks if it is enabled while a call to GetUserEvent or ProcessSystemEvents is in effect. The attribute is automatically reset to zero when another call to RunUserInterface, GetUserEvent, or ProcessSystemEvents is made.

## **Generating Hard Copy Output**

You can generate hard copy output of panels or individual controls to a graphics printer or a file.

## **Functions for Hard Copy Output**

Use PrintPanel to output a panel and its child panels.

Use PrintCtrl to output an individual control.

Use SetPrintAttribute to set hard copy attributes.

Use GetPrintAttribute to obtain hard copy attributes.

## **Hard Copy Attributes**

Table 3-27 contains the list of control attributes accessible through GetPrintAttribute and SetPrintAttribute.

Table 3-27. Hard Copy Attributes

Attribute	Type	Notes
ATTR_COLOR_MODE	int	0 = VAL_BW 1 = VAL_GRAY_SCALE 2 = VAL_COLOR
ATTR_DUPLEX	int	1 = VAL_SIMPLEX 2 = VAL_VERTDUPLEX 3 = VAL_HORIZDUPLEX
ATTR_EJECT_AFTER	int	1 = eject page after print 0 = do not eject page after print
ATTR_NUMCOPIES	int	Number of copies; range = 1 to 100
ATTR_ORIENTATION	int	1 = VAL_PORTRAIT 2 = VAL_LANDSCAPE
ATTR_PAPER_HEIGHT	int	Millimeter/10 or -1 = VAL_USE_PRINTER_DEFAULT 0 = VAL_INTEGRAL_SCALE
ATTR_PAPER_WIDTH	int	Millimeter/10 or -1 = VAL_USE_PRINTER_DEFAULT 0 = VAL_INTEGRAL_SCALE
ATTR_TAB_INTERVAL	int	The number of spaces represented by a <tab> character.</tab>
ATTR_TEXT_WRAP	int	Determines whether to wrap text when text extends past the defined width.
ATTR_XOFFSET	int	Inches or VAL_USE_PRINTER_DEFAULT
ATTR_YOFFSET	int	Inches or VAL_USE_PRINTER_DEFAULT
ATTR_XRESOLUTION	int	Dots Per Inch or VAL_USE_PRINTER_DEFAULT
ATTR_YRESOLUTION	int	Dots Per Inch or VAL_USE_PRINTER_DEFAULT

## **Hard Copy Attribute Discussion**

The following list shows attribute names and their purpose.

ATTR_DUPLEX	_	Determines if the output is single or double sided.
ATTR_EJECT_AFTER	_	Determines if the next output is ejected from the printer. While ATTR_EJECT_AFTER is set to zero, outputs print on the same page until ATTR_EJECT_AFTER is set to one.
ATTR_ORIENTATION		Determines if the hard copy is in portrait or landscape mode.
ATTR_PAPER_HEIGHT		VAL_INTEGRAL_SCALE forces the hard copy height to be scaled integrally to the width preventing printer aliasing (distortion).
ATTR_PAPER_WIDTH	_	VAL_INTEGRAL_SCALE forces the hard copy width to be scaled integrally to the height preventing printer aliasing (distortion).
ATTR_XOFFSET		Sets the x offset of the hard copy image on the paper. The coordinates (0,0) define the upper-left corner of the paper. VAL_USE_PRINTER_DEFAULT centers the image in the x direction.
ATTR_YOFFSET		Sets the y offset of the hard copy image on the paper. The coordinates (0,0) define the upper-left corner of the paper. VAL_USE_PRINTER_DEFAULT centers the image in the y direction.
ATTR_XRESOLUTION	_	Sets the x resolution of the printer. It can be used if the printer supports different resolutions in the x and y dimensions.
ATTR_YRESOLUTION		Sets the y resolution of the printer. It can be used if the printer supports different resolutions in the x and y dimensions.

Note: Because of a limitation in the UNIX xpr printing utility, UNIX users cannot print multiple outputs on the same page when their printer is configured for Postscript.

Table 3-28. Values for ATTR\_COLOR\_MODE

Type of Printer	Values
default value	VAL_COLOR
PC with color printer:	VAL_COLOR: prints in color
	VAL_GRAYSCALE: prints in grayscale
	VAL_BW: undefined
PC with non-color printer	VAL_COLOR: prints in grayscale
	VAL_GRAYSCALE: prints in grayscale
	VAL_BW: prints in black and white
Sun with color printer	VAL_COLOR: prints in color
	VAL_GRAYSCALE: prints in grayscale
	VAL_BW: undefined
Sun with non-color printer	VAL_COLOR: undefined
	VAL_GRAYSCALE: prints in grayscale
	VAL_BW: prints in black and white

## **Special User Interface Functions**

#### RunUserInterface

RunUserInterface runs the GUI and issues all events to callback functions, until QuitUserInterface is called from a callback. The return value for RunUserInterface is passed back from QuitUserInterface.

#### **Precedence of Callback Functions**

Events trigger callback functions in the following order.

- For control operation events:
  - 1. Control callback
  - 2. Panel callback (keypress and mouse events only)
  - 3. Main callback

- For panel events:
  - 1. Panel callback
  - 2. Main callback
- For menu commit events:
  - 1. Menu item callback
  - 2. Main callback
- Timer control event:
  - 1. Control callback
- Main callback event:
  - 1. Main Callback

**Note:** The commit event is placed in the GetUserEvent queue after being sent to all callbacks.

#### **Swallowing Events**

User callbacks must always return 0 unless they intend to "swallow" the event to which they are responding. To swallow the event, the callback should return 1.

Only user input (mouse click and keypress events) and commit events can be swallowed. If swallowed, no further callbacks are called for that event. If a user input event is swallowed, the user's mouse click or keypress is ignored. If a commit event is swallowed, it is not placed into the GetUserEvent queue.

#### **Note:** The events that can be swallowed are:

EVENT\_COMMIT EVENT\_KEYPRESS
EVENT\_LEFT\_CLICK EVENT\_LEFT\_DOUBLE\_CLICK
EVENT\_RIGHT\_CLICK EVENT\_RIGHT\_DOUBLE\_CLICK
EVENT\_END\_TASK

#### **GetUserEvent**

GetUserEvent gets the next commit event from the GetUserEvent queue. Commit events occur when the user changes the state of a hot or validate control or selects a menu item. You can set GetUserEvent to wait until the next event or to return immediately even if no event occurs.

#### InstallMainCallback and SetIdleEventRate

An object-based callback approach is a common method of using callbacks to process user events. In an object-based callback approach, you use multiple callbacks to control user interface objects. You can assign unique callback functions to each panel, control, and menu item, or you can use separate callback functions for specific groups of controls or menu items.

You can use any scheme that makes sense to you. The object-based callback approach subdivides the program into small, manageable sections, each section having a specific task.

Alternatively, you can install a single callback function using InstallMainCallback to process all events. A main callback is like a GetUserEvent loop that is "turned upsidedown."

The main callback function is the only type of callback function that responds to EVENT\_END\_TASK. This event occurs only on MS Windows when the user is trying to exit Windows. Return a non-zero value to abort the exit of Windows.

The main callback function also responds to idle events. For example, your program will normally be suspended in the GetUserEvent or RunUserInterface function while a user holds the mouse button down on a control or pull-down menu. Other than timer control callbacks, any portion of your program that is supposed to run continuously temporarily ceases during that time. However, idle events occur continuously while your program is running, even while suspended in GetUserEvent or RunUserInterface. You can set the rate at which idle events occur using SetIdleEventRate.

Note: EVENT\_VAL\_CHANGED, EVENT\_IDLE and EVENT\_TIMER\_TICK are the only events that are generated while a user holds the mouse button down on a control or pull-down menu. The operating system blocks all events (including idle events) when a top-level panel is moved or sized.

Note: In general, it is recommended that you use timer controls instead of idle events.

For even greater flexibility, you can combine the object-based callback approach with the main callback approach. Object-based callbacks will be called before the main callback so that both have the opportunity to process events.

#### **ProcessDrawEvents**

While inside of a callback function or in code that does not call RunUserInterface or GetUserEvent, the program does not update the user interface. If a particular function is overly time-consuming, it essentially "locks out" user interface updates. To force these updates to be processed, place a call to ProcessDrawEvents in your source code.

Note: The user interface is updated automatically by the GetUserEvent function and when a callback returns.

## **ProcessSystemEvents**

While a callback function or other section of code that does not call RunUserInterface or GetUserEvent runs, user interface and system events are not processed. While such functions or code run, they temporarily stop user interface and system events. The ProcessSystemEvents function lets you force events to process while a time-consuming

function is running. You can make your program call ProcessSystemEvents occasionally, from within the function that is preventing system events. Because ProcessSystemEvents can allow other callback functions to be executed before it completes, you must use this function with care.

The ProcessSystemEvents function processes all pending system events, such as,

- System events that are delayed or suspended by a user application, for example keystrokes, mouse events, and screen updates.
- Events generated by other applications, for example, Windows messages intended to invoke a callback within the RegisterWinMsgCallback function.

Note: The ProcessSystemEvents function is called automatically by the LabWindows/CVI GetUserEvent function and after a callback returns.

#### **PostDeferredCall**

PostDeferredCall posts a function to LabWindows/CVI that is called at the next occurrence of GetUserEvent, RunUserInterface, or ProcessSystemEvents. PostDeferredCall would typically be used in a function installed as an asynchronous interrupt handler. The capabilities of the asynchronous interrupt handler are limited. It cannot perform time consuming tasks and it cannot call into the User Interface Library. The function that is posted by PostDeferredCall contains code that cannot be executed at interrupt time. This feature is useful when external devices generate events during source program execution.

#### QueueUserEvent

Use QueueUserEvent to place a programmer-defined event in the GetUserEvent queue. Event numbers 1000 to 10000 are reserved for programmer-defined events. GetUserEvent receives programmer-defined events.

## **FakeKeystroke**

Use FakeKeystroke to simulate a keystroke. This function has the same effect as actually pressing the key at the keyboard.

Note: The order in which the fake keystroke is received in relation to other events is not defined, so you must use this function with care.

## QuitUserInterface

QuitUserInterface terminates the RunUserInterface function.

# **Chapter 4 User Interface Library Reference**

This chapter describes the functions in the LabWindows User Interface Library. The *User Interface Library Overview* section contains general information about the User Interface Library functions and panels. The *User Interface Library Function Reference* section contains an alphabetical list of function descriptions.

## **User Interface Library Overview**

This section contains general information about the User Interface Library functions and panels.

#### **User Interface Function Panels**

The User Interface Library function panels are grouped in a tree structure according to the types of operations performed. The User Interface Library function tree is shown in Table 4-1.

The bold headings in the tree are the names of function classes and subclasses. Function classes and subclasses are groups of related function panels. The headings in plain text are the names of individual function panels. Each User Interface Library function panel generates one function call. The names of the corresponding function calls are in bold italics to the right of the function panel names.

The function classes in the tree are described here.

- **Panels** is a class of functions that load/create, modify, and unload/discard user-defined panels.
- **Menu Structures** is a class of functions that load/create, modify, and unload/discard user-defined menu structures.
- **Controls/Graphs/Strip Charts** is a class of functions that create, control, modify, and discard controls and graphs.
- **Pop-up Panels** is a class of functions that install and interact with user-defined and predefined dialog boxes.
- Callback Functions is a class of functions that install user-defined callback functions that respond to user interface events and Windows messages.

- **User Interface Management** is a class of functions that control user input and screen operations.
- **Printing** is a class of functions that configure and generate hard copy output.
- **Miscellaneous** is a class of functions that do not fit into the other classes.
- LW DOS Compatibility Functions is a class of functions that are maintained for backwards compatibility with existing LabWindows for DOS applications.

Table 4-1. The User Interface Library Function Tree

ser Interface Library	Function Name
Panels	
Load Panel	LoadPanel
Load Panel (Extended)	LoadPanelEx
New Panel NewPanel	
Discard Panel	DiscardPanel
Duplicate Panel	<i>DuplicatePanel</i>
Display Panel	DisplayPanel
Hide Panel	HidePanel
Get Active Panel	GetActivePanel
Set Active Panel	SetActivePanel
Validate Panel	ValidatePanel
Default Panel	DefaultPanel
Save Panel State	SavePanelState
Recall Panel State	RecallPanelState
Get Panel Attribute	GetPanelAttribute
Set Panel Attribute	SetPanelAttribute
Set Panel Position	SetPanelPos
Menu Structures	
Menu Bars	
Load Menu Bar	LoadMenuBar
Load Menu Bar (Extended)	LoadMenuBarEx
New Menu Bar	NewMenuBar
Discard Menu Bar	DiscardMenuBar
Set Panel Menu Bar	SetPanelMenuBar
Get Panel Menu Bar	GetPanelMenuBar
Get Menu Bar Attribute	GetMenuBarAttribute
Set Menu Bar Attribute	SetMenuBarAttribute
Empty Menu Bar	EmptyMenuBar
Get Shared Menu Bar Event Panel	GetSharedMenuBarEventPanel

Table 4-1. The User Interface Library Function Tree (Continued)

•	N /	Γ.		
	V	ler	ווו	S

New Menu
Discard Menu
Empty Menu
New SubMenu
Discard SubMenu
Run Popup Menu
New Menu
New SubMenu
Run Popup Menu
Run Popup Menu
New Mew Menu
Run Popup Menu
Run Popup Menu

**Menu Items** 

New Menu Item

Discard Menu Item
Insert Separator

NewMenuItem
DiscardMenuItem
InsertSeparator

**Controls/Graphs/Strip Charts** 

**General Functions** 

New Control NewCtrl **Duplicate Control DuplicateCtrl** DiscardCtrl **Discard Control** Get Active Control **GetActiveCtrl** Set Active Control SetActiveCtrl **Default Control Value DefaultCtrl** Get Control Value **GetCtrlVal** Set Control Value SetCtrlVal Get Control Attribute **GetCtrlAttribute** Set Control Attribute **SetCtrlAttribute** Get Control Bounding Rectangle **GetCtrlBoundingRect** 

List (Label/Value) Controls

Insert List Item
Replace List Item
Delete List Item
Delete List Item
DeleteListItem

Get Value From Index GetValueFromIndex

Get Value Length From Index GetValueLengthFromIndex

Get Index From Value GetIndexFromValue

Get Control Index
Set Control Index
Clear List Control
Get Number of List Items
Get List Item Image
Get List Item Image
Get Label From Index

Get Control
ClearListCtrl
GetNumListItems
GetNumListItems
GetListItemImage
SetListItemImage
GetLabelFromIndex

Get Label Length From Index GetLabelLengthFromIndex

Is List Item Checked
Check List Item

CheckListItem

CheckListItem

Get Number of Checked Items GetNumCheckedItems

Table 4-1. The User Interface Library Function Tree (Continued)

Text Boxes	
Insert Text Box Line	InsertTextBoxLine
Replace Text Box Line	ReplaceTextBoxLine
Delete Text Box Line	DeleteTextBoxLine
Get Number of Text Box Lines	GetNumTextBoxLines
Reset Text Box	ResetTextBox
Get Text Box Line	GetTextBoxLine
Get Text Box Line Length	GetTextBoxLineLength
Graphs and Strip Charts	o .
Graph Plotting and Deleting	
Plot X	PlotX
Plot Y	PlotY
Plot X-Y	PlotXY
Plot Waveform	PlotWaveform
Plot Point	PlotPoint
Plot Text	PlotText
Plot Line	PlotLine
Plot Rectangle	PlotRectangle
Plot Polygon	PlotPolygon
Plot Oval	PlotOval
Plot Arc	PlotArc
Plot Intensity	PlotIntensity
Plot Scaled Intensity	PlotScaledIntensity
Plot Bitmap	PlotBitmap
Delete Graph Plot	DeleteGraphPlot
Get Plot Attribute	GetPlotAttribute
Set Plot Attribute	SetPlotAttribute
Refresh Graph	RefreshGraph
Graph Cursors	
Get Graph Cursor	GetGraphCursor
Set Graph Cursor	SetGraphCursor
Get Active Graph Cursor	GetActiveGraphCursor
Set Active Graph Cursor	SetActiveGraphCursor
Get Graph Cursor Index	GetGraphCursorIndex
Set Graph Cursor Index	SetGraphCursorIndex
Get Cursor Attribute	GetCursorAttribute
Set Cursor Attribute	SetCursorAttribute
Strip Chart Traces	
Plot Strip Chart	PlotStripChart
Plot Strip Chart Point	PlotStripChartPoint

Table 4-1. The User Interface Library Function Tree (Continued)

Clear Strip Chart
Get Trace Attribute
Set Trace Attribute
Set Trace Attribute
SetTraceAttribute

**Axis Scaling** 

Get Axis Scaling Mode
Set Axis Scaling Mode
Set Axis Scaling Mode
SetAxis Scaling Mode
SetAxis Scaling Mode

Get Axis Range (Obsolete) GetAxisRange
Set Axis Range (Obsolete) SetAxisRange

**Axis Label Strings** 

Insert Axis Item
Replace Axis Item
Pelete Axis Item
Clear Axis Item
Clear Axis Items
Get Number of Axis Items
Get Axis Item Label and Value

InsertAxisItem
ReplaceAxisItem
ReplaceAxisItem
ReplaceAxisItem
ClearAxisItem
GetAxisItems
GetNumAxisItems
GetAxisItem

Get Axis Item Label Length GetAxisItemLabelLength

**Pictures** 

Display Image File

Delete Image
Get Image Info (Obsolete)
Get Image Bits (Obsolete)
Set Image Bits (Obsolete)
Alloc Image Bits (Obsolete)

Display Image File
Delete Image
Get Image
Get Image Info
Get Image Bits
Set Image Bits
Alloc Image Bits
Alloc Image Bits

Canvas

**Drawing** 

Draw Point

Draw Line

Draw Line To

Draw Rectangle

Dim Rectangle

CanvasDrawLine

CanvasDrawLineTo

CanvasDrawRect

CanvasDrawRect

CanvasDimRect

Draw Rounded Rectangle CanvasDrawRoundedRect

Draw Oval
Draw Arc
Draw Poly
Draw Text in Rectangle

CanvasDrawOval
CanvasDrawArc
CanvasDrawPoly
CanvasDrawText

Draw Text at Point CanvasDrawTextAtPoint
Draw Bitmap CanvasDrawBitmap

Scroll
Invert Rectangle
Clear
Clear
CanvasScroll
CanvasInvertRect
CanvasClear

Batch Drawing	
Start Batch Drawing	CanvasStartBatchDraw
End Batch Drawing	CanvasEndBatchDraw
Pens	
Set Pen Position	<b>CanvasSetPenPosition</b>
Get Pen Position	<b>CanvasGetPenPosition</b>
Set Pen Attributes To Defaults	CanvasDefaultPen
Clipping	
Set Clipping Rectangle	CanvasSetClipRect
Get Clipping Rectangle	CanvasGetClipRect
Accessing Pixel Values	<del>-</del>
Get a Single Pixel Value	CanvasGetPixel
Get Pixel Values	CanvasGetPixels
Miscellaneous	
Update Canvas	CanvasUpdate
Timers	
Reset Timer	ResetTimer
Suspend Timer Callbacks	SuspendTimerCallbacks
Resume Timer Callbacks	${\it Resume Timer Callbacks}$
op-up Panels	
Install Popup	InstallPopup
Remove Popup	RemovePopup
Message Popup	MessagePopup
Confirm Popup	ConfirmPopup
Prompt Popup	PromptPopup
Generic Message	Generic Message Popup
File Select Popup	FileSelectPopup
Multifile Select Popup	MultiFileSelectPopup
Directory Select Popup	<i>DirSelectPopup</i>
X Graph Popup	XGraphPopup
Y Graph Popup	YGraphPopup
X-Y Graph Popup	XYGraphPopup
Waveform Graph Popup	<i>WaveformGraphPopup</i>
Get System Popups Attribute	GetSystemPopupsAttribute
Set System Popups Attribute	Set System Popups Attribute
Font Select Popup	FontSelectPopup
Set Font Select Popup Defaults	Set Font Popup Defaults
Callback Functions	
Install Main Callback	InstallMainCallback

(continues)

Install Control Callback Install Panel Callback

Install Menu Callback

**InstallCtrlCallback** 

*InstallPanelCallback* 

InstallMenuCallback

Table 4-1. The User Interface Library Function Tree (Continued)

Install Menu Dimmer Callback InstallMenuDimmerCallback Post Deferred Call **PostDeferredCall Windows Interrupt Support** Register Windows Msg Callback RegisterWinMsgCallback Unregister Windows Msg Callback *UnRegisterWinMsgCallback* Get CVI Window Handle **GetCVIWindowHandle** Get CVI Task Handle **GetCVITaskHandle User Interface Management** Run User Interface **RunUserInterface** Ouit User Interface QuitUserInterface Get User Event **GetUserEvent** Set Input Mode SetInputMode **Process Draw Events ProcessDrawEvents Process System Events ProcessSystemEvents** Oueue User Event **OueueUserEvent** Set Idle Event Rate SetIdleEventRate Fake Keystroke **FakeKeystroke** Get Sleep Policy **GetSleepPolicy** Set Sleep Policy **SetSleepPolicy Printing** Get Print Attribute **GetPrintAttribute** Set Print Attribute SetPrintAttribute Print Control **PrintCtrl** Print Panel **PrintPanel PrintTextFile** Print Text File Print Text Buffer **PrintTextBuffer Mouse and Cursor GetWaitCursorState** Get Wait Cursor **SetWaitCursor** Set Wait Cursor Get Mouse Cursor **GetMouseCursor** Set Mouse Cursor **SetMouseCursor** Get Global Mouse State GetGlobalMouseState Get Relative Mouse State **GetRelativeMouseState Rectangles and Points Creating and Modifying** Make Rect MakeRect Set Rect Coordinates RectSet Set Rect Coords From Points **RectSetFromPoints** Set Bottom Edge of Rect **RectSetBottom** Set Right Edge of Rect RectSetRight

(continues)

Set Center Point of Rect

**RectSetCenter** 

Table 4-1. The User Interface Library Function Tree (Continued)

Offset Rect
Move Rect
Grow (or Shrink) Rect
Make Point
Set Point Coordinates

RectOffset
RectMove
RectGrow
MakePoint
MakePoint
PointSet

**Retrieving and Comparing Values** 

Get Rect Bottom
Get Rect Right
Get Rect Center
Are Rects Equal?
Is Rect Empty?

RectBottom
RectRight
RectCenter
RectCenter
RectEqual
RectEmpty

Does Rect Contain Point?

Does Rect Contain Rect?

Are Rects the Same Size?

Calculate Rect Union

Calculate Rect Intersection

Are Points Equal?

RectContainsPoint

RectContainsRect

RectSameSize

RectUnion

RectIntersection

PointEqual

Calculate Point Pinned to Rect *PointPinnedToRect* 

**Bitmaps** 

Create New Bitmap

NewBitmap

Get Bitmap From a File GetBitmapFromFile
Get Bitmap From a Control GetCtrlBitmap

Get Control Display Bitmap
Get Panel Display Bitmap
GetPanelDisplayBitmap
GetPanelDisplayBitmap

Get Bitmap Info
Get Bitmap Data
Alloc Bitmap Data
Set Control Bitmap
Discard Bitmap
Discard Bitmap

GetBitmapInfo
GetBitmapData
AllocBitmapData
SetCtrlBitmap
DiscardBitmap

Clipboard

Get Text From Clipboard
Put Text On Clipboard
Get Bitmap From Clipboard
Put Bitmap on Clipboard
ClipboardPutBitmap
ClipboardPutBitmap

Miscellaneous

Make Color Make Color

Get 3d Border Colors
Create Meta Font
Get Text Display Size
Get Screen Size
Get System Attribute
Set System Attribute

Get3dBorderColors
CreateMetaFont
GetTextDisplaySize
GetTextDisplaySize
GetScreenSize
GetSystemAttribute
SetSystemAttribute

(continues)

Table 4-1. The User Interface Library Function Tree (Continued)

## **LW DOS Compatibility Functions**

Configure Printer
Display PCX File
DOS Color to RGB
DOS Compatibility Window

Get Error String

Configure Printer
Display PCX File
Display PCXFile
DOSColor To RGB
DOSCompat Window
Get UILError String

## **Hard Copy Output**

### **Compatible Printers**

Under Windows, LabWindows/CVI can print to any graphics printer with a Windows compatible driver.

Under UNIX, LabWindows/CVI can print to any graphics printer compatible with the xpr printing utility under the X Window System.

In addition, output can be redirected to a disk file.

# **Obtaining Hard Copy Output**

You can use the following functions to obtain hard copy output.

PrintPanel
PrintCtrl
PrintTextFile
PrintTextBuffer

In addition, the following functions can also produce hard copy output if you select the hard copy option from the following pop-ups.

XGraphPopup XYGraphPopup YGraphPopup WaveformGraphPopup

## **Configuring Your System for Hard Copy Output**

Under Windows, the printer driver and output port are set using the Printers utility in the Windows Control Panel. Under UNIX, the default printer is set using the PRINTER environment variable or the printcap file and the printer filter is set in the .Xdefaults file. Hard copy attributes can be set interactively through a dialog box or programmatically through the SetPrinterAttribute function. These attributes are discussed in the section, Generating Hard Copy Output, in Chapter 3, Programming with the User Interface Library.

## **RGB Color Values**

The following functions can use RGB color values as input Parameters.

PlotArc PlotLine PlotOval PlotPoint PlotPolygon PlotRectangle PlotText PlotWaveform PlotX PlotXY PlotY PlotIntensity SetImageBits SetCtrlAttribute SetCursorAttribute SetMenuBarAttribute SetPanelAttribute SetTraceAttribute SetPlotAttribute

An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. Common colors are shown in Table 3-3 of Chapter 3, *Programming with the User Interface Library*.

You can also use the User Interface Library function, MakeColor, to create an RGB value from red, green, and blue color components.

#### **Fonts**

The following functions use font values as input parameters.

PlotText SetPanelAttribute SetCtrlAttribute FontSelectPopup SetFontSelectPopupDefaults

See the section *Using Fonts* in Chapter 1, *User Interface Concepts*, for more information on font values.

## **Shortcut Keys**

The following functions can use shortcut key values as input parameters.

SetMenuBarAttribute SetCtrlAttribute

In your code, shortcut keys are 4-byte integers consisting of three bit fields, 0x00MMVVAA, where:

MM =the modifier key

 $\nabla V =$ the virtual key

AA =the ASCII key

When constructing a shortcut key, modifier keys are bit-wise OR'ed with a virtual key or an ASCII key. Either the ASCII field or the virtual key field will be all zeros. For example:

```
VAL_SHIFT_MODIFIER | VAL_F1_VKEY
```

produces a shortcut key of SHIFT-F1, and

```
VAL_MENUKEY_MODIFIER | 'D'
```

produces a shortcut key of <Ctrl-D>. Virtual keys do not require modifiers but ASCII keys require at least one modifier.

Table 3-7 in Chapter 3, *Programming with the User Interface Library* shows the modifiers and virtual keys for shortcut keys.

# **Plot Array Data Types**

The following graphing functions have array parameters whose data values are interpreted based on other parameters called *data type specifiers*.

PlotPolygon
PlotStripChart
PlotWaveform
PlotX
PlotXY
PlotY
PlotIntensity
WaveformGraphPopup
XGraphPopup
XYGraphPopup
YGraphPopup

A data type specifier determines the data type of an array and must be one of the values shown in the following list.

VAL\_CHAR
VAL\_INTEGER
VAL\_SHORT\_INTEGER
VAL\_FLOAT
VAL\_DOUBLE
VAL\_UNSIGNED\_SHORT\_INTEGER
VAL\_UNSIGNED\_INTEGER
VAL\_UNSIGNED\_CHAR

## **Include Files**

The User Interface Library provides an include file that contains function declarations and defined constants for all of the library routines. The include file is named userint.h. You must include this file in all code modules that reference the User Interface Library.

# **Reporting Errors**

All the functions in the User Interface Library return an integer code containing the result of the call. If the return code is negative, an error occurred. Otherwise, the function completed successfully. Refer to Appendix A, *Error Conditions*, for a complete list of error codes. You can also use the GetUILErrorString function to convert the error number returned into a text error message.

# **User Interface Library Function Reference**

This section describes each function in the User Interface Library. The functions are in alphabetical order.

# AllocBitmapData

#### **Purpose**

Allocates the buffers necessary for calling GetBitmapData on a bitmap. If you use GetBitmapInfo, you must allocate the buffers yourself.

You must free the buffers when you are done with them.

Input	bitmapID	integer	The ID of the bitmap object containing the image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.
Output	colorTable	pointer to integer	A pointer variable into which the address of the allocated color table buffer is placed.
	bits	pointer to unsigned char	A pointer variable into which the address of the allocated bits data buffer is placed.
	mask	pointer to unsigned char	A pointer variable into which the address of the allocated mask buffer is placed.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **Parameter Discussion**

You may pass NULL for any of the **colorTable**, **bits**, or **mask** parameters if you do not want the corresponding buffer to be allocated.

If the image does not exist, the **colorTable**, **bits**, and **mask** parameters are set to NULL. The **colorTable** parameter is set to NULL if the pixel depth of the image is greater than 8. The **mask** parameter is set to NULL if the image does not have a mask.

Warning: You must free the colorTable, bitmap, and mask buffers when you are done with them. Use the ANSI C Library free function.

#### See Also

GetBitmapData, GetBitmapInfo

# **AllocImageBits**

## **Purpose**

Allocates the buffers necessary for calling GetImageBits on an existing image. This function provides an alternative to calling GetImageInfo and allocating the buffers yourself.

The following control types can contain images.

picture controls picture rings picture buttons graph controls

You must free the buffers allocated by this function when you are done with them.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
			The defined constant (located in the .uir header file) which was assigned to the control by the user Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	imageID	integer	For a picture ring, the zero-based index of an image in the ring. For a graph, the <b>plotHandle</b> returned from PlotBitmap. For picture controls and buttons, this is ignored.
Output	colorTable pointer to integer		A pointer variable into which the address of the allocated color table buffer is placed.
	bitmap pointer to unsigned char		A pointer variable into which the address of the allocated bitmap buffer is placed.
	mask	pointer to unsigned char	A pointer variable into which the address of the allocated mask buffer is placed.

#### Return Value

status integer Refer to Appendix A for error codes.
---

#### **Parameter Discussion**

You may pass NULL for any of the **colorTable**, **bitmap**, and **mask** parameters if you do not want the corresponding buffer to be allocated.

If the image does not exist, the **colorTable**, **bitmap**, and **mask** parameters are set to NULL. The **mask** parameter is set to NULL if the image does not have a mask.

Warning: You must free the colorTable, bitmap, and mask buffers when you are done with them. Use the ANSI C Library free function.

You can now use a 24-bit pixel depth in the four picture control image bits functions. When you do, the color table parameters to the functions are not used. The array of bits contains RGB values rather than indexes into the color table. Each RGB value in the array of bits represented by a 3-byte value of the form

0xRRGGBB

where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte should always be at the lowest memory address of the three bytes.

#### See Also

GetImageBits, SetImageBits

\_\_\_\_\_

## CanvasClear

int status = CanvasClear (int panelHandle, int controlID, Rect rect);

#### **Purpose**

Restores the specified rectangular area of a canvas control to the background color of the canvas control. The background color of the canvas control is determined by the ATTR PICT BGCOLOR attribute.

This operation is not restricted to the canvas clipping rectangle.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the rectangle to be cleared. Use VAL_ENTIRE_OBJECT to specify the entire canvas.

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## See also

MakeRect

# CanvasDefaultPen

int status = CanvasDefaultPen (int panelHandle, int controlID);

# **Purpose**

Sets all of the attributes of the canvas pen to the default values. The defaults are shown in the following table.

Canvas Pen Attribute	Default Value
ATTR_PEN_WIDTH	1
ATTR_PEN_STYLE	VAL_SOLID
ATTR_PEN_COLOR	VAL_BLACK
ATTR_PEN_FILL_COLOR	VAL_BLACK
ATTR_PEN_MODE	VAL_COPY_MODE
ATTR_PEN_PATTERN	A solid pattern, expressed as an array of 8 unsigned characters, each of which is 0xFF.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

## **Return Value**

## See Also

CanvasSetPenPosition, CanvasGetPenPosition, CanvasDrawLineTo

## **CanvasDimRect**

int status = CanvasDimRect (int panelHandle, int controlID, Rect rect);

## **Purpose**

Overlays a checkerboard pattern in the specified rectangular area of a canvas control. This has the visual effect of dimming objects within the area.

The checkerboard pattern is drawn using current values of the following attribute.

ATTR\_PEN\_FILL\_COLOR

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the area to be dimmed. Use VAL_ENTIRE_OBJECT to specify the entire canvas.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See also

MakeRect

## CanvasDrawArc

#### **Purpose**

Draws an arc on the canvas control. The arc is defined by specifying a rectangle that encloses the arc, along with a beginning angle (in tenths of degrees) and an arc angle (in tenths of degrees).

The arc is a section of an oval. A beginning angle of 0 indicates that the arc starts at the midpoint of the right edge of the rectangle. The arc angle indicates how far around the oval (counterclockwise, up to 3600) the arc is drawn.

The frame of the arc is drawn using the current value of the following attributes:

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

The interior of the arc is drawn using the current value of the following attributes.

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_PATTERN

The frame of the arc does not include the radius lines going from the center of the oval to the end points of the arc.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the rectangle within which to draw the arc.
	drawMode	integer	Specifies whether the arc's frame or interior (or both) are drawn. Valid values:  VAL_DRAW_FRAME  VAL_DRAW_INTERIOR  VAL_DRAW_FRAME_AND_INTERIOR
	beginningAngle	integer	The starting angle of the arc, in tenths of degrees.
			0 indicates the arc starts at the midpoint of the right edge of the rectangle. 900 indicates that the arc starts at the midpoint of the top edge of the rectangle. Negative values are valid.
	arcAngle	integer	How far around the oval (counter-clockwise, up to 3600) the arc is drawn. Specified in tenths of degrees. Negative values are valid.

## **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## See also

MakeRect, CanvasDrawOval

# CanvasDrawBitmap

# **Purpose**

Draws a bitmap image (or portion thereof) in the specified destination rectangle on the canvas control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	bitmapID	integer	The ID of the bitmap object containing the image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.
	sourceRect	Rect	A Rect structure specifying the portion of the bitmap to be drawn. The values are in terms of the pixel coordinates of the bitmap. The origin (0, 0) is at the upper left corner of the bitmap. Use VAL_ENTIRE_OBJECT to specify the entire image.
	destinationRect	Rect	A Rect structure specifying the size and location of the area in which the bitmap image is to be drawn on the canvas control. If <b>sourceRect</b> and <b>destinationRect</b> are not the same size, the bitmap is stretched or shrunk to fit.

## **Return Value**

#### **Parameter Discussion**

If you want the destination rectangle to be same size as the source rectangle, you can set the **height** and **width** in **destinationRect** to VAL\_KEEP\_SAME\_SIZE.

If you want the bitmap to stretch to fit the size of the canvas, pass VAL\_ENTIRE\_OBJECT as **destinationRect**.

## Example

The following code copies a bitmap image, without any stretching or shrinking, to the canvas control, starting 20 pixels below the top edge of the canvas, and 30 pixels to the right of left edge of the canvas.

```
CanvasDrawBitmap (panelHandle, controlID, bitmapID, VAL_ENTIRE_OBJECT, MakeRect(20,30, VAL_KEEP_SAME_SIZE, VAL_KEEP_SAME_SIZE));
```

#### See also

MakeRect

## **CanvasDrawLine**

#### **Purpose**

Draws a line between two specified points.

The line is drawn using the current value of the following attributes.

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	start	Point	A Point structure specifying the location at which the line begins.	
	end	Point	A Point structure specifying the location at which the line ends.	

## **Return Value**

status in	nteger	Refer to Appendix A for error codes.
-----------	--------	--------------------------------------

# See also

MakePoint, CanvasDrawLineTo

## CanvasDrawLineTo

int status = CanvasDrawLineTo (int panelHandle, int controlID, Point end);

## **Purpose**

Draws a line between the current pen position and a specified end point, and sets the pen position to the end point.

The line is drawn using the current value of the following attributes.

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function	
	end	Point	A Point structure specifying the location at which the line ends.	

#### **Return Value**

status	integer	Refer to Appendix A for error codes.

#### See also

MakePoint, CanvasGetPenPosition, CanvasSetPenPosition, CanvasDefaultPen, CanvasDrawLine

## **CanvasDrawOval**

#### **Purpose**

Draws an oval on the canvas control within the specified rectangle.

The frame of the oval is drawn using the current value of the following attributes.

ATTR\_PEN\_COLOR
ATTR\_PEN\_MODE
ATTR\_PEN\_WIDTH
ATTR\_PEN\_STYLE (ignored in Windows when pen width is greater than 1)

The interior of the oval is drawn using the current value of the following attributes:

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_PATTERN

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the rectangle within which to draw the oval.
	drawMode	integer	Specifies whether the oval's frame or interior (or both) are drawn. Valid values:  VAL_DRAW_FRAME  VAL_DRAW_INTERIOR  VAL_DRAW_FRAME_AND_INTERIOR

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See also

MakeRect, CanvasDrawArc

## **CanvasDrawPoint**

int status = CanvasDrawPoint (int panelHandle, int controlID, Point point);

# **Purpose**

Draws a point on the canvas control as the specified position.

The point is drawn using the current value of the following attributes:

ATTR\_PEN\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_WIDTH

At pen widths of greater than 1, the point may appear to be non-circular.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	point	Point	A Point structure specifying the location at which to draw the point.

## **Return Value**

status	integer	Refer to Appendix A for error codes.
butus	meger	refer to appendix at for error codes.

#### See also

MakeRect, CanvasDrawArc

# CanvasDrawPoly

## **Purpose**

Draws a polygon on the canvas control by connecting the specified points.

The frame of the polygon is drawn using the current value of the following attributes.

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

The interior of the polygon is drawn using the current value of the following attributes.

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_PATTERN

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	numberOfPoints	integer	The number of vertices in the polygon.
	points	Point array	An array of Point structures specifying the locations of the vertices of the polygon.
	wrap	integer	A nonzero value specifies that a line is drawn between last point and first point, thereby closing the polygon frame. This value is ignored when drawing only the interior.
	drawMode	integer	Specifies whether the polygon's frame or interior (or both) are drawn. Valid values:  VAL_DRAW_FRAME  VAL_DRAW_INTERIOR  VAL_DRAW_FRAME_AND_INTERIOR

## **Return Value**

status integer Refer to Appendix A for error codes.
---

## CanvasDrawRect

## **Purpose**

Draws a rectangle on the canvas control.

The frame of the rectangle is drawn using the current value of the following attributes.

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

The interior of the rectangle is drawn using the current value of the following attributes.

```
ATTR_PEN_FILL_COLOR
ATTR_PEN_MODE
ATTR_PEN_PATTERN
```

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the rectangle to be drawn.
	drawMode	integer	Specifies whether the rectangle's frame or interior (or both) are drawn. Valid values:  VAL_DRAW_FRAME  VAL_DRAW_INTERIOR  VAL_DRAW_FRAME_AND_INTERIOR

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### See also

MakeRect, CanvasDrawRoundedRect

## CanvasDrawRoundedRect

#### **Purpose**

Draws a rounded rectangle on the canvas control. Each corner of the rectangle is drawn as a quadrant of an oval.

The frame of the rectangle is drawn using the current value of the following attributes.

```
ATTR_PEN_COLOR
ATTR_PEN_MODE
ATTR_PEN_WIDTH
ATTR_PEN_STYLE (ignored in Windows when pen width is greater than 1)
```

The interior of the rectangle is drawn using the current value of the following attributes.

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_PATTERN

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure specifying the location and size of the rectangle to be drawn.
	ovalHeight	integer	The vertical diameter of the oval whose quadrants are drawn at the corners of the rounded rectangle.
	ovalWidth	integer	The horizontal diameter of the oval whose quadrants are drawn at the corners of the rounded rectangle.
	drawMode	integer	Specifies whether the rectangle's frame or interior (or both) are drawn. Valid values:  VAL_DRAW_FRAME  VAL_DRAW_INTERIOR  VAL_DRAW_FRAME_AND_INTERIOR

## **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# See also

MakeRect, CanvasDrawRect

## **CanvasDrawText**

## **Purpose**

Draws a text string within a specified rectangular area on the canvas control. You can set the alignment of the string within the rectangle. If the string exceeds the size of the rectangle, it is clipped.

The text is drawn using the current value of the following attribute.

ATTR\_PEN\_COLOR

The background rectangle is drawn using the current value of the following attributes:

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR PEN PATTERN

If you do not want the background rectangle to be drawn, set the ATTR\_PEN\_FILL\_COLOR attribute of the canvas control to VAL\_TRANSPARENT.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	text	string	The text string to be drawn within the rectangle.
	metaFont	string	Specifies the text font. Must be one of the predefined metafonts (see Table 3-5 in this manual) or a metafont created by a call to CreateMetaFont.
	bounds	Rect	A Rect structure specifying location and size of the background rectangle within which the text is drawn.
	alignment	integer	Determines the placement of the text string within the background rectangle. See discussion below.

#### Return Value

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

The values in the **bounds** parameter are in terms of pixel coordinates, with the origin (0,0) at the upper left corner of the canvas control.

If you want the size of the background rectangle to be adjusted automatically to the display size of the text string, set **height** and **width** in the **bounds** parameter to VAL\_KEEP\_SAME\_SIZE.

The valid values for the **alignment** parameters are listed in the following table.

Value	Description
VAL_LOWER_LEFT	Draw the string in the lower left corner of the background rectangle.
VAL_CENTER_LEFT	Start the string from the midpoint of the left edge of the background rectangle.
VAL_UPPER_LEFT	Draw the string in the upper left corner of the background rectangle.
VAL_LOWER_CENTER	Center the string just above the bottom edge of the background rectangle.
VAL_CENTER_CENTER	Center the string in the middle of the background rectangle.
VAL_UPPER_CENTER	Center the string just below the top edge of the background rectangle.
VAL_LOWER_RIGHT	Draw the string in the lower right corner of the background rectangle.
VAL_CENTER_RIGHT	Draw the string so that it ends just at the midpoint of the right edge of the background rectangle.
VAL_UPPER_RIGHT	Draw the string in the upper right corner of the background rectangle.

If the background rectangle specified by **bounds** is smaller than the text display size, the text is clipped to the rectangle and the specified **alignment** is ignored. If the rectangle width is smaller than the text display width, the text is displayed from the left. If the rectangle height is smaller than the text display height, the text is displayed from the top.

#### See also

MakeRect, CanvasDrawTextAtPoint

## CanvasDrawTextAtPoint

## **Purpose**

Draws a text string at the specified location in the canvas control. The location is in terms of an anchor point and an alignment around the point.

The text is drawn using the current value of the following attribute.

ATTR\_PEN\_COLOR

The background of the text is drawn using the current value of the following attributes:

ATTR\_PEN\_FILL\_COLOR ATTR\_PEN\_MODE ATTR\_PEN\_PATTERN

If you do not want the background rectangle to be drawn, set the ATTR\_PEN\_FILL\_COLOR attribute of the canvas control to VAL\_TRANSPARENT.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	text	string	The text string to be drawn at the anchor point.
	metaFont	string	Specifies the text font. Must be one of the predefined metafonts (see Table 3-5 in this manual) or a metafont created by a call to CreateMetaFont.
	anchorPoint	Point	A Point structure specifying location of the point at which the text is drawn.
	alignment	integer	Determines the placement of the text string in relation to the anchor point. See discussion below.

## **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

Each **alignment** value refers to a point on the rectangle that implicitly encloses the text string. The text string is placed so that the point indicated by the **alignment** parameter is at the location specified the **anchorPoint** parameter. The valid values for the **alignment** parameter are listed in the following table.

Value	Description
VAL_LOWER_LEFT	Draw the string so that lower left corner of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_CENTER_LEFT	Draw the string so that midpoint of the left edge of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_UPPER_LEFT	Draw the string so that upper left corner of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_LOWER_CENTER	Draw the string so that midpoint of the bottom edge of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_CENTER_CENTER	Draw the string so that center of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_UPPER_CENTER	Draw the string so that midpoint of the top edge of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_LOWER_RIGHT	Draw the string so that lower right corner of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_CENTER_RIGHT	Draw the string so that midpoint of the right edge of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .
VAL_UPPER_RIGHT	Draw the string so that upper right corner of its enclosing rectangle is at the location specified by <b>anchorPoint</b> .

## See also

MakeRect, CanvasDrawText

# CanvasEndBatchDraw

int nestingDepth = CanvasEndBatchDraw (int panelHandle, int controlID);

# **Purpose**

Ends the batch drawing started with CanvasStartBatchDraw.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

## **Return Value**

nestingDepth	integer	The number of calls to CanvasStartBatchDraw that have not been matched by calls to CanvasEndBatchDraw (including this call). A negative value indicates that an error occurred. Refer to Appendix A
		for error codes.

## See also

CanvasStartBatchDraw

# CanvasGetClipRect

int status = CanvasGetClipRect (int panelHandle, int controlID, Rect \*clipRect);

# **Purpose**

Obtains the current clipping rectangle for the canvas control. All drawing operations are restricted to the area in the clipping rectangle. Any drawing outside the clipping rectangle is not shown. Exception: CanvasClear is not restricted to the clipping rectangle.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	clipRect	Rect	The Rect structure into which the location and size of the clipping rectangle are stored. If clipping is disabled (the default state), the height and width values in the structure are set to zero.

#### **Return Value**

status	ınteger	Refer to Appendix A for error codes.

## See Also

CanvasSetClipRect

## **CanvasGetPenPosition**

int status = CanvasGetPenPosition (int panelHandle, int controlID, Point \*point);

## **Purpose**

Obtains the current position of the canvas pen.

**Note:** CanvasDrawLineTo is the only canvas drawing function that uses the pen position.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	point	Point	The Point structure into which the current position of the canvas pen is stored.

#### Return Value

status   Integer   Refer to Appendix A for error codes.	status	integer	Refer to Appendix A for error codes.
---	--------	---------	--------------------------------------

#### See Also

CanvasSetPenPosition, CanvasDefaultPen, CanvasDrawLineTo

## CanvasGetPixel

## **Purpose**

Obtains the color of a single pixel on a canvas control.

Note: The canvas control maintains an internal bitmap reflecting all of the drawing operations (except for drawing operations made while the ATTR\_DRAW\_POLICY attribute is set to VAL\_DIRECT\_TO\_SCREEN). There are times during which the internal bitmap contains the result of recent drawing operations that have not yet been reflected on the screen. This function obtains the pixel colors from the internal bitmap, not from the screen.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	pixelPoint	Point	A Point structure indicating the location of a pixel. The location is in terms of unscaled pixel coordinates. The origin (0,0) is the upper left corner of the canvas control.
Output	pixelColor	integer	The RGB color value of the pixel at the specified point.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### See also

MakePoint, CanvasGetPixels

## **CanvasGetPixels**

#### **Purpose**

Obtains the colors of the pixels in the specified rectangular area of a canvas control.

Note: The canvas control maintains an internal bitmap reflecting all of the drawing operations (except for drawing operations made while the ATTR\_DRAW\_POLICY attribute is set to VAL\_DIRECT\_TO\_SCREEN). There are times during which the internal bitmap contains the result of recent drawing operations that have not yet been reflected on the screen. This function obtains the pixel colors from the internal bitmap, not from the screen.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	The Rect structure specifying the location and size of the rectangular area from which to obtain the pixel colors.
			The location and size are expressed in terms of unscaled pixel coordinates. The origin (0,0) is the upper left corner of the canvas control. Use VAL_ENTIRE_OBJECT to specify the entire canvas.
Output	pixelColors	integer array	An array of RGB color values of the pixels in the specified rectangle. See discussion below.

#### **Parameter Discussion**

The total number of elements in the **pixelColors** array should be equal to **rect.height** \* **rect.width**. The pixel color values are stored in row-major order. For example, if **rect** has the following values,

rect.top	50
rect.left	60
rect.height	20
rect.width	15

then the color of pixel  $\{x = 65, y = 58\}$  is stored in pixel array at the following index.

When using a **rect.width** of VAL\_TO\_EDGE, substitute the following for **rect.width** in the above formula.

(total width of canvas) - rect.left

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See also

MakePoint, CanvasGetPixel

# CanvasInvertRect

int status = CanvasInvertRect (int panelHandle, int controlID, Rect rect);

# **Purpose**

Inverts the colors in the specified rectangular area of a canvas control. The colors that result from the inversion are dependent on the operating system. If you invert the same rectangle twice, you are guaranteed to get the original colors back.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	rect	Rect	A Rect structure which specifies the location and size of the rectangular area in which to invert the colors. Use VAL_ENTIRE_OBJECT to specify the entire canvas.

## **Return Value**

#### See also

MakeRect

#### CanvasScroll

## **Purpose**

Scrolls the contents of the specified rectangular area of a canvas control. The area that is exposed by the scrolling is filled using the current value of the ATTR\_PEN\_FILL\_COLOR attribute. The contents of the canvas outside the specified rectangular area is not affected by the scrolling.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	scrollRect	Rect	A Rect structure which specifies the location and size of the rectangular area to scroll. Use VAL_ENTIRE_OBJECT to specify the entire canvas.
	scrollAmountInXDirection	integer	The amount to scroll horizontally.
	scrollAmountInYDirection	integer	The amount to scroll vertically.

#### **Parameter Discussion**

A positive value for **scrollAmountInXDirection** moves the contents of the rectangle to the right. An area on the left side of the rectangle is thereby exposed. It is filled with the current value of the ATTR\_PEN\_FILL\_COLOR attribute.

A negative value for **scrollAmountInXDirection** moves the contents of the rectangle to the left. An area on the right side of the rectangle is thereby exposed. It is filled with the current value of the ATTR\_PEN\_FILL\_COLOR attribute.

A positive value for **scrollAmountInYDirection** moves the contents of the rectangle down. An area at the top of the rectangle is thereby exposed. It is filled with the current value of the ATTR\_PEN\_FILL\_COLOR attribute.

A negative value for **scrollAmountInYDirection** moves the contents of the rectangle the up. An area at the bottom of the rectangle is thereby exposed. It is filled with the current value of the ATTR\_PEN\_FILL\_COLOR attribute.

#### See Also

MakeRect

# CanvasSetClipRect

int status = CanvasSetClipRect (int panelHandle, int controlID, Rect clipRect);

## **Purpose**

Sets the clipping rectangle for the canvas control. All drawing operations are restricted to the area in the clipping rectangle. Any drawing outside the clipping rectangle is not shown. Exception: CanvasClear is not restricted to the clipping rectangle.

Changing the clipping rectangle does not affect current contents of the canvas.

In the initial state for a canvas control, clipping is disabled.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	clipRect	Rect	A Rect structure specifying into the location and size of the clipping rectangle. To disable clipping, set the height and width of <b>clipRect</b> to zero, or use VAL_EMPTY_RECT.	

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## See Also

CanvasGetClipRect

# **CanvasSetPenPosition**

int status = CanvasSetPenPosition (int panelHandle, int controlID, Point point);

# **Purpose**

Sets the position of the canvas pen.

Note: CanvasDrawLineTo is the only canvas drawing function that uses the pen position.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	point	Point	A Point structure specifying the new position of the canvas pen.

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## See Also

CanvasGetPenPosition, CanvasDefaultPen, CanvasDrawLineTo

#### CanvasStartBatchDraw

int nestingDepth = CanvasStartBatchDraw(int panelHandle, int controlID);

## **Purpose**

This function can be used to increase the drawing performance of the canvas control. In general, it should be used whenever you want to make two or more consecutive calls to canvas drawing functions. Each call to CanvasStartBatchDraw should be matched with a call to CanvasEndBatchDraw.

Before drawing operations can be performed, certain operating system functions must be invoked to prepare for drawing on the particular canvas. Without batch drawing, these system functions must be called for each canvas drawing operation. With batch drawing, the system functions are called only once for all of the drawing operations between CanvasStartBatchDraw and the matching CanvasEndBatchDraw.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

#### **Return Value**

nestingDepth	integer	The number of calls to CanvasStartBatchDraw
		(including this call) that have not been matched by calls to
		CanvasEndBatchDraw. A negative value indicates that
		an error occurred. Refer to Appendix A for error codes.

#### **Using This Function**

The following code shows an example of how you would incorporate a sequence of drawing operations on the same canvas control into one batch.

```
CanvasStartBatchDraw (panelHandle, controlID);
CanvasDrawLine (panelHandle, controlID, point1, point2);
CanvasDrawLine (panelHandle, controlID, point3, point4);
CanvasDrawRect (panelHandle, controlID, rect5);
CanvasEndBatchDraw (panelHandle, controlID);
```

During a batch draw, you may call drawing operations on other canvas controls or call other User Interface Library functions that perform drawing operations or process events. This has the effect of implicitly ending the batch. The next time you call a drawing function on the same canvas, the batch is implicitly restarted.

You may nest calls to CanvasStartBatchDraw.

Failure to properly match CanvasStartBatchDraw and CanvasEndBatchDraw calls can negate the potential performance improvements but does not cause any other ill effects.

Note: If the ATTR\_DRAW\_POLICY attribute for the canvas control is set to VAL\_UPDATE\_IMMEDIATELY, no update to the screen occurs until the batch is ended. Also, changing values of the ATTR\_DRAW\_POLICY and ATTR\_OVERLAP\_POLICY attributes during a batch draw has no effect until after the batch is ended.

#### See also

CanvasEndBatchDraw

## CanvasUpdate

int status = CanvasUpdate (int panelHandle, int controlID, Rect updateArea);

## **Purpose**

Immediately updates on the screen the contents of the canvas control within the specified rectangular area.

The canvas control maintains an internal bitmap reflecting all of the drawing operations (except for drawing operations made while the ATTR\_DRAW\_POLICY attribute is set to VAL\_DIRECT\_TO\_SCREEN). Maintaining the internal bitmap ensures that the canvas is redrawn correctly when it is exposed.

This function copies the content of the specified area in the internal bitmap to the canvas control.

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	updateArea	Rect	A Rect structure specifying the location and size of the rectangular to be updated from the internal bitmap. Use VAL_ENTIRE_OBJECT to specify the entire canvas control.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

### See also

MakeRect

## CheckListItem

## **Purpose**

This function places a check by, or removes a check from, the specified list item. It applies only to list boxes with the check mode attribute set.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function	
	itemIndex	integer	The zero-based index into the list where the item will be placed.	
	checked	integer	Specifies whether or not the specified list item is checked.	

### **Return Value**

status integer Refer to Appendix A for error codes.
---

## ClearAxisItems

int status = ClearAxisItems (int panelHandle, int controlID, int axis);

## **Purpose**

This function deletes all string/value pairs from the list of label strings for a graph or strip chart axis.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies the axis from which to delete all of the string/value pair(s). Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)

### **Return Value**

status integer Refer to Appendix A for error codes.	
---	--

### See Also

InsertAxisItem, ReplaceAxisItem, DeleteAxisItem, GetNumAxisItems

## ClearListCtrl

int status = ClearListCtrl (int panelHandle, int controlID);

## **Purpose**

This function clears all list items from the specified list control.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# ClearStripChart

int status = ClearStripChart (int panelHandle, int controlID);

## **Purpose**

Clears all traces from a strip chart control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

## **Return Value**

<b>status</b> intege	Refer to Appendix A for error codes.
----------------------	--------------------------------------

# ClipboardGetBitmap

int status = ClipboardGetBitmap (int \*bitmapID, int \*available);

## **Purpose**

Determines whether or not a bitmap image is available on the system clipboard and optionally retrieves a copy of the bitmap. The bitmap ID can then be passed to any function that accepts a bitmap, such as CanvasDrawBitmap.

You can discard the bitmap by passing its ID to DiscardBitmap.

### **Parameters**

Output	bitmapID	integer	An ID that serves as a handle to the bitmap copied from the clipboard. It is set to NULL if there is no bitmap on the clipboard. If you not want a copy of the bitmap, pass NULL.
	available	integer	Is set to 1 if a bitmap is available on the system clipboard, 0 otherwise. You may pass NULL for this parameter.

status	ınteger	Refer to Appendix A for error codes.

#### See Also

ClipboardPutBitmap, ClipboardGetText, GetBitmapData, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

## ClipboardGetText

int status = ClipboardGetText (char \*\*text, int \*available);

## **Purpose**

Determines whether or not a text string is available on the system clipboard and optionally retrieves a copy of the text.

When the copy of the text is no longer needed, you should free it by calling the free function.

#### **Parameters**

Output	text	string	A pointer to the nul-terminated string copied from the clipboard. It is set to NULL if there is no text on the clipboard. If you not want a copy of the text, pass NULL.
	available	integer	Is set to 1 if a text string is available on the system clipboard, 0 otherwise. You may pass NULL for this parameter.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

ClipboardPutText, ClipboardGetBitmap.

## ClipboardPutBitmap

int status = ClipboardPutBitmap (int bitmapID);

### **Purpose**

Copies a bitmap image onto the system clipboard.

Input	bitmapID	integer	The ID of the bitmap object containing the image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap,
			or GetPanelDisplayBitmap.

## **Return Value**

status int	teger	Refer to Appendix A for error codes.
------------	-------	--------------------------------------

#### See Also

ClipboardGetBitmap, ClipboardPutText, NewBitmap, GetBitmapFromFile, GetCtrlBitmap, GetCtrlDisplayBitmap, GetPanelDisplayBitmap, ClipboardGetBitmap.

# Clipboard Put Text

int status = ClipboardPutText (char text[]);

### **Purpose**

Copies a text string onto the system clipboard.

### **Parameter**

input text string A nur-terminated string.	Input text	string	A nul-terminated string.
--	------------	--------	--------------------------

### **Return Value**

etotue	integer	Refer to Appendix A for error codes.
Status	miegei	Refer to Appendix A for error codes.

#### See Also

ClipboardGetText, ClipboardPutBitmap

# **ConfigurePrinter**

## **Purpose**

Sets the orientation, height, width, and eject after print attributes. See Table 3-27, *Hard Copy Attributes*, in Chapter 3, *Programming with the User Interface Library*, for more information on printing attributes.

This function is retained for compatibility with LabWindows for DOS. It is superseded by SetPrintAttribute.

#### **Parameters**

Input	printFile	string	Is ignored in LabWindows/CVI because the print file is specified at the system level.
	orientation	integer	The orientation of the image on the page.  Valid Value: 1 = VAL_PORTRAIT  2 = VAL_LANDSCAPE
	imageWidth	integer	The width of the image in millimeter/10 or VAL_USE_PRINTER_DEFAULT or VAL_INTEGRAL_SCALE
	imageHeight	integer	The height of the image in millimeter/10 or VAL_USE_PRINTER_DEFAULT or VAL_INTEGRAL_SCALE
	ejectAfter	integer	Determines if the next output will be ejected from the printer. While <b>ejectAfter</b> is set to zero, outputs will print on the same page until <b>ejectAfter</b> is set to one.

#### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **ConfirmPopup**

int status = ConfirmPopup (char title[], char message[]);

### **Purpose**

Displays a prompt message in a dialog box and waits for the user to select the **Yes** or **No** button.

Input	title	string	The title of the dialog box.
	message	string	The message displayed on the dialog box.

### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### **Return Codes**

1	user selected Yes.
0	user selected No.

### CreateMetaFont

## **Purpose**

Creates a new meta font based on a pre-defined National Instruments font, an existing metafont, or a font supplied by the operating system. Metafonts contain typeface information, point size, and text style.

Input	newMetaFontName	string	The name to be associated with the new meta font.
	existingFontName	string	The name of the existing font on which the new meta font is based. The font may be one of the National Instrument fonts, a user-defined font saved by a previous CreateMetaFont function call, or a font supplied by the operating system.
	pointSize	integer	The point size of the new meta font. Any positive integer value is valid.
	bold	integer	Indicates whether or not the newly created meta font will have bold text. $0 = \text{not bold}$ $1 = \text{bold}$
	italics	integer	Indicates whether or not the newly created meta font will have italicized text.  0 = not italics  1 = italics
	underlined	integer	Indicates whether or not the newly created meta font will have underlined text.  0 = not underlined  1 = underlined
	strikeout	integer	Indicates whether or not the newly created meta font will have strikeout text.  0 = not strikeout  1 = strikeout

## **Return Value**

status	integer	Refer to Appendix A for error codes.

## **Parameter Discussion**

The following are examples of values that can be passed to **existingFontName**.

VAL\_7SEG\_META\_FONT VAL\_DIALOG\_FONT "Courier"

## **DefaultCtrl**

int status = DefaultCtrl (int panelHandle, int controlID);

### **Purpose**

This function restores a control to its default value.

If the control is visible, it is updated to reflect its default value. You assign default values to controls in the User Interface Editor or through the SetCtrlAttribute function.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

#### **Return Value**

status integer Refer to Appendix A for error codes.	
---	--

## **DefaultPanel**

int status = DefaultPanel (int panelHandle);

#### **Purpose**

Restores all panel controls to their default values.

If the panel is visible, it is updated to reflect the new control values. You assign default values to controls in the User Interface Editor or through the SetCtrlAttribute function using ATTR\_DFLT\_VALUE.

Input	panelHandle	integer	The specifier for a particular panel that is currently in
			memory. This handle will have been returned by the
			LoadPanel, NewPanel, or DuplicatePanel function.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **DeleteAxisItem**

## **Purpose**

Deletes one or more string/value pairs from the list of label strings for a graph or strip chart axis. These strings appear in place of the numerical labels. They appear at the location of their associated values on the graph or strip chart.

To see string labels on an X axis, you must set the ATTR\_XUSE\_LABEL\_STRINGS attribute to TRUE. To see string labels on a Y axis, you must set the ATTR\_YUSE\_LABEL\_STRINGS attribute to TRUE.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies the axis from which to delete the selected string/value pair(s). Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)
	itemIndex	integer	The zero-based index of the first item to be deleted.
	numberOfItems	string	The number of items to delete.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

 ${\tt InsertAxisItem, ReplaceAxisItem, ClearAxisItems, GetNumAxisItems}$ 

# Delete Graph Plot

## **Purpose**

Deletes one or all plots from a graph control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular pamemory. This handle will have LoadPanel, NewPanel, or I function.	been returned by the
	controlID	integer	The defined constant (located in which was assigned to the contraction, or the ID returned by the DuplicateCtrl function.	ol by the User Interface
	plotHandle	integer	The handle for the particular plotelete all plots in the graph contact.	
	refresh	integer	Selects when to refresh the grap following choices are valid:  VAL_DELAYED_DRAW  VAL_IMMEDIATE_DRAW  VAL_NO_DRAW	oh control. The  Delayed Draw.  Immediate Draw.  No Draw.

status	integer	Refer to Appendix A for error codes.
50000		Treated to 1 appending 12 for course

## **Parameter Discussion**

**plotHandle** will have been returned by one of the following functions.

PlotX PlotY PlotXY PlotWaveform PlotPoint PlotText PlotLine PlotRectangle PlotPolygon PlotOval PlotArc PlotIntensity PlotBitmap

If **refresh** is set to Delayed Draw, the deleted plot remains on the graph until one of the following actions takes place.

- Graph is rescaled.
- Size of the plot area is changed.
- Graph is overlapped.
- Graph is made visible after it was hidden.
- ATTR\_REFRESH\_GRAPH is set to 1 when it was previously 0.
- RefreshGraph function is called.
- Another plot is directed to the graph while ATTR\_REFRESH\_GRAPH is 1.

When one of the above events occurs, the entire plot area is redrawn.

If **refresh** is set to VAL\_IMMEDIATE\_DRAW, the plot area is redrawn immediately and the deleted plot is removed from the graph.

If **refresh** is set to VAL\_NO\_DRAW, the deleted plot remains on the graph until one of the following actions takes place.

- Graph is rescaled.
- Size of the plot area is changed.
- Graph is overlapped when ATTR\_SMOOTH\_UPDATE is 0.
- Graph is made visible when ATTR\_SMOOTH\_UPDATE is 0 after it was hidden.

# **DeleteImage**

int status = DeleteImage (int panelHandle, int controlID);

## **Purpose**

Removes an image from the specified picture control and from memory.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

### **Return Value**

<b>status</b> integ	Refer to Appendix A for error codes.
---------------------	--------------------------------------

## **DeleteListItem**

## **Purpose**

Deletes one or more items from a list control starting at Item Index.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index of the first item to be deleted.
	numberofItems	integer	The number of items to delete. To delete all items from <b>itemIndex</b> to the end, enter -1 for <b>numberofItems</b> .

## **Return Value**

<b>status</b> inte	ger Refer to Appendix A for error codes.	
--------------------	--	--

## **DeleteTextBoxLine**

int status = DeleteTextBoxLine (int panelHandle, int controlID, int lineIndex);

## **Purpose**

This function removes the line of text at the specified index.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	lineIndex	integer	The zero-based index of the text box line to be deleted.

status integer Refer to Appendix A for error codes.	
---	--

# DirSelectPopup

## **Purpose**

Displays a file-selection dialog box and waits for the user to select a directory or cancel.

### **Parameters**

Input	defaultDirectory	string	The initial directory. If "" is entered, then the current working directory is used.
	title	string	The title of the dialog box.
	allowCancel	integer	If non-zero, the user can cancel out of the dialog box. If zero, the user must make a selection.
	allowMakeDirectory	integer	If non-zero, the user is allowed to create a new directory.
Output	pathname	string	The buffer in which the user's selection is returned. The buffer must be at least MAX_PATHNAME_LEN bytes long.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

### **Return Codes**

0	VAL_NO_DIRECTORY_SELECTED
1	VAL_DIRECTORY_SELECTED

### **Parameter Discussion**

The maximum length of **defaultDirectory** is MAX\_PATHNAME\_LEN characters, including the ASCII NUL byte.

The maximum length of **title** is 255 excluding the ASCII NUL byte.

## DiscardBitmap

int status = DiscardBitmap (int bitmapID);

### **Purpose**

Discards a bitmap object.

#### **Parameter**

Input bitmapID	integer	The ID of the bitmap object. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.
----------------	---------	---

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

NewBitmap, GetBitmapFromFile, GetCtrlBitmap, GetCtrlDisplayBitmap, GetPanelDisplayBitmap, ClipboardGetBitmap.

### **DiscardCtrl**

int status = DiscardCtrl (int panelHandle, int controlID);

## **Purpose**

This function removes a control from the specified panel and from memory.

When discarding a control from its own callback function, you can call DiscardCtrl only when responding to the EVENT\_COMMIT event. Discarding the control from its own callback function in response to other events may cause unpredictable behavior.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

## **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## DiscardMenu

int status = DiscardMenu (int menuBarHandle, int menuID);

## **Purpose**

This function removes the specified menu and its sub-menus and items from the menu bar.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuID	integer	The ID for a particular menu within a menu bar.  The Menu ID should be a constant name (located in the .uir header file) generated by the User Interface  Editor or a value returned by the NewMenu function.

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## DiscardMenuBar

int status = DiscardMenuBar (int menuBarHandle);

## **Purpose**

Removes the specified menu bar from every panel on which it resides and from memory.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently
			in memory. This handle will have been returned by
			LoadMenuBar or NewMenuBar.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## DiscardMenuItem

int status = DiscardMenuItem (int menuBarHandle, int menuItemID);

## **Purpose**

This function removes a menu item from the specified menu and from memory.

### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuItemID	integer	The ID used to reference this menu item. The Menu Item ID will have been generated by the User Interface Editor or returned by the NewMenuItem function.

status	integer	Refer to Appendix A for error codes.
status	micgei	Refer to Appendix A for error codes.

## **DiscardPanel**

int status = DiscardPanel (int panelHandle);

## **Purpose**

Removes a panel from memory and clears it from the screen if visible.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in
			memory. This handle will have been returned by the
			LoadPanel, NewPanel, or DuplicatePanel
			function.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## DiscardSubMenu

int status = DiscardSubMenu (int menuBarHandle, int subMenuID);

## **Purpose**

This function removes a submenu from the specified menu bar and from memory.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar
	subMenuID	integer	The ID for a particular sub-menu within a menu bar. The <b>subMenuID</b> will have been a constant name generated by the User Interface Editor or a value returned by the NewSubMenu function.

status in	nteger	Refer to Appendix A for error codes.
-----------	--------	--------------------------------------

## DisplayImageFile

int status = DisplayImageFile (int panelHandle, int controlID, char filename[]);

## **Purpose**

Displays the contents of an image file on a specified picture control.

Supported image types:

PCX: Windows and UNIX

BMP, DIB, RLE, ICO: Windows only

WMF: Windows 95 and NT only

XWD: UNIX only

To display an image, first create a picture control in the User Interface Editor or with the NewCtrl function. Then call the DisplayImageFile function using the control ID.

To delete the image, call the DeleteImage function (which also removes it from memory.)

To replace the current image with another, simply call DisplayImageFile for the same picture control with a different image file.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	filename	string	The name of the image file which contains the image. If the name is a simple filename (in other words, contains no directory path), then the file is loaded from the project. If it is not found in the project, the file is loaded from the directory containing the project.

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **DisplayPCXFile**

int controlID = DisplayPCXFile (char filename[], int controlTop, int controlLeft);

#### **Purpose**

Displays the contents of an image file in a new picture control on the DOS Compatibility window at the given x and y coordinates. Window coordinates may be any value between 0 and 32767, with the origin in the upper left corner directly beneath the title bar before the panel is scrolled. These picture controls will be overlapped by child panels of this window. If the DOS Compatibility window has not yet been created, DisplayPCXFile will create it.

Supported image types:

PCX: Windows and UNIX

BMP, DIB, RLE, ICO: Windows only

WMF: Windows 95 and NT only

XWD: UNIX only

Note: This function has been replaced by DisplayImageFile, and should be translated by the user. Repeated use of this function will clutter the panel with redundant controls.

### **Parameters**

Input	filename	string	The name of the image file which contains the image. If the name is a simple filename (in other words, contains no directory path), then the file is loaded from the project. If it is not found in the project, the file is loaded from the directory containing the project.	
	controlTop controlLeft	integer integer	The coordinate of the top edge of the image.  The coordinate of the left edge of the image.	

#### **Return Value**

controlID	integer	er Returns the ID used to specify this control in	
	subsequent function calls. Negative values indica		
		an error occurred. Refer to Appendix A for error codes.	

## **DisplayPanel**

int status = DisplayPanel (int panelHandle);

#### **Purpose**

Displays a panel on the screen.

When a panel is visible and not dimmed, the user can operate it and events can be generated from it. Calling DisplayPanel when a panel is already displayed will cause the panel to be completely redrawn.

## **Parameters**

Input	panelHandle	integer	· · · · · · · · · · · · · · · · · · ·
			memory. This handle will have been returned by the
			LoadPanel, NewPanel, or DuplicatePanel function.

### **Return Value**

status i	integer	Refer to Appendix A for error codes.
----------	---------	--------------------------------------

## **DOSColorToRGB**

int status = DOSColorToRGB (int lwDOSColor);

## **Purpose**

Translates the 16 standard color values from LabWindows/DOS to RGB values as shown in the following table.

LW/DOS	LW/CVI
0 (black)	VAL_BLACK = 0x000000L
1 (dark blue)	VAL_DK_BLUE = 0x000080L
2 (dark green)	VAL_DK_GREEN = 0x008000L
3 (dark cyan)	VAL_DK_CYAN = 0x008080L
4 (dark red)	VAL_DK_RED = 0x800000L
5 (dark magenta)	VAL_DK_MAGENTA = 0x800080L
6 (brown)	VAL_DK_YELLOW = 0x808000L
7 (gray)	VAL_LT_GRAY = 0xCCCCCCL
8 (dark gray)	VAL_DK_GRAY = 0x808080L
9 (blue)	VAL_BLUE = 0x0000FFL

(continues)

#### (Continued)

LW/DOS	LW/CVI				
10 (green)	VAL_GREEN = 0x00FF00L				
11 (cyan)	VAL_CYAN = 0x00FFFFL				
12 (red)	VAL_RED = 0xff0000L				
13 (magenta)	VAL_MAGENTA = 0xff00ffL				
14 (yellow)	VAL_YELLOW = 0xffff00L				
15 (white)	VAL_WHITE = 0xFFFFFFL				

#### **Parameters**

Input	lwDOSColor	integer	One of the 16 standard colors from LabWindows/DOS.
-------	------------	---------	--

#### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# DOS Compat Window

int panelHandle = DOSCompatWindow (void);

### **Purpose**

Displays a window which serves as a parent panel for DOS LabWindows panels.

A panel handle is returned that is used by the **parentPanelHandle** parameter in the Load Panel function. This function can be used with DOS LabWindows .uir files to retain the appearance of the DOS User Interface screen.

This function exists as an aid for converting LabWindows for DOS applications. It should not be used when developing new applications in LabWindows/CVI.

panelHandle	integer	Returns an integer specifier (panel handle) for the DOS Compatibility Window. A negative number indicates that an error occurred. Refer to Appendix A for error codes.
		error occurred. Refer to Appendix A for error codes.

# **DuplicateCtrl**

## **Purpose**

This function copies an existing control from the source panel to the destination panel and returns a control ID which is used to reference the control in subsequent function calls.

#### **Parameters**

Input	sourcePanelHandle	integer	The handle of the source panel containing the control to be duplicated. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	destinationPanelHandle	integer	Specifies the parent panel handle into which the duplicate control is copied. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	duplicateLabel	string	The label for the duplicate control. Pass "" for no label. Pass 0 to use the label of the source control.
	controlTop	integer	The vertical coordinate at which the upper left corner of the control (not including labels) is placed.
	controlLeft	integer	The horizontal coordinate at which the upper left corner of the control (not including labels) is placed.

newID	Returns the ID used to specify the new (duplicate) control in subsequent function calls.
	Refer to Appendix A for error codes.

#### **Parameter Discussion**

The valid range for **controlTop** and **controlLeft** is -32,768 to 32,767 or VAL\_KEEP\_SAME\_POSITION. The origin (0,0) is at the upper-left corner of the panel (directly below the title bar) before the panel is scrolled.

## **DuplicatePanel**

## **Purpose**

This function duplicates a panel into the specified destination parent panel and returns the duplicate (new) panel handle.

#### **Parameters**

Input	destParentPanelHandle	integer	The handle for the parent panel into which the duplicate panel is copied. To make the panel a top-level panel, enter 0.
	originalPanelHandle	integer	The handle of the original panel to be duplicated. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	duplicatePanelTitle	string	The title of the duplicate (new) panel. Pass " " for no title. Pass 0 to use the same title as the original panel.
	panelTop	integer	The vertical coordinate at which the upper left corner of the panel (directly below the title bar) is placed. Pass VAL_KEEP_SAME_POSITION to keep the same top coordinate as the original panel.
	panelLeft	integer	The horizontal coordinate at which the upper left corner of the panel (directly below the title bar) is placed. Pass  VAL_KEEP_SAME_POSITION to keep the same left coordinate as the original panel.

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

For a top-level panel, (0,0) is the upper-left corner of the screen. For a child panel, (0,0) is the upper-left corner of the parent panel (directly below the title bar) before the parent panel is scrolled. The **panelTop** and **panelLeft** coordinates must be integer values from -32768 to 32767, or VAL\_AUTO\_CENTER to center the panel.

## **EmptyMenu**

int status = EmptyMenu (int menuBarHandle, int menuID);

### **Purpose**

This function removes all sub-menus and menu items from the specified menu.

#### **Parameters**

Input menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
menuID	integer	The ID for a particular menu within a menu bar. The Menu ID should be a constant name (located in the .uir header file) generated by the User Interface Editor or a value returned by the NewMenu function.

## **Return Value**

status integer Refer to Appendix A for error	codes.
--	--------

# ${\bf Empty Menu Bar}$

int status = EmptyMenuBar (int menuBarHandle);

#### **Purpose**

This function removes all menus and menu items from the specified menu bar but retains the menu bar handle in memory.

Input	menuBarHandle	integer	The specifier for a particular menu bar that is
			currently in memory. This handle will have been
			returned by LoadMenuBar or NewMenuBar.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **FakeKeystroke**

int status = FakeKeystroke (int keyCode);

### **Purpose**

Simulates a keystroke.

Note: The order in which the keystroke is received in relation to other events is not defined, so you must use this function with care.

#### **Parameters**

Input	keyCode	integer	Key codes are formed by a logical OR operation on
			values representing a modifier key and either an ASCII
			character or a virtual key. See Table 3-7 in Chapter 3
			for modifier and virtual keys.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **FileSelectPopup**

## **Purpose**

Displays a file-selection dialog box and waits for the user to select a file or cancel.

			·
Input	defaultDirectory	string	The initial directory. If " " is entered, then the current working directory will be used.
	defaultFileSpec	string	A string that specifies which files to display.  For example, "*.c" would cause all files with the extension .c to be displayed.
	fileTypeList	string	A list of file types, separated by semicolons, to be contained in the File Type List of the File Select Pop-up when <b>restrictExtension</b> is FALSE. For example, "*.c;*.h" allows the user to select "*.c" or "*.h" from the File Type List. ("*.*" is always available).
	title	string	The title of the dialog box.
	buttonLabel	integer	Selects the label for the file select button. The choices are:  "OK" = VAL_OK_BUTTON  "Save" = VAL_SAVE_BUTTON  "Select" = VAL_SELECT_BUTTON  (affects existing files only)  "Load" = VAL_LOAD_BUTTON (affects existing files only).
	restrictDirectory	integer	If non-zero, the user cannot change directories or drives. If zero, the user can change directories or drives.
	restrictExtension	integer	If non-zero, the user is limited to files with the default extension. If zero, the user can select files with any extension.
	allowCancel	integer	If non-zero, the user can cancel out of the File Select Popup. If zero, the user can leave the pop-up only by making a selection.
	allowMakeDirectory	integer	If non-zero, allows the user to make a new directory from the File Select Popup. This is useful when a user wants to save a file into a new directory.
Output	pathName	string	The buffer in which the user's selection is returned. The buffer must be at least MAX_PATHNAME_LEN bytes long.

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### **Return Codes**

0	VAL_NO_FILE_SELECTED
1	VAL_EXISTING_FILE_SELECTED
2	VAL_NEW_FILE_SELECTED

#### **Parameter Discussion**

The **defaultfilespec** is shown in the file name control when the pop-up is first displayed. If you specify an actual file name, such as test.c, that name appears in the file name box and also in the file list box. The default file specification (spec) cannot contain a directory path.

You need to declare the **pathName** string to be a least MAX\_PATHNAME\_LEN bytes long..

# **FontSelectPopup**

Brings up a dialog which allows the user to specify font settings.

		T	
Input	title	string	The title to be displayed on the dialog box. The maximum length is 255 characters.
	sampleText	string	The sample text to be displayed in the font select pop-up as demonstration of how the settings will affect the appearance of text.
	monospacedFontsOnly	integer	If nonzero, the user can select only monospaced (fixed width) fonts. If zero, the user may select any font.
	minimumFontSize	integer	The minimum value allowed in the 'Font Size' control.
	maximumFontSize	integer	The maximum value allowed in the 'Font Size' control.
	showDefaultButton	integer	If zero, the default button is hidden. If non-zero, the default button is shown. When the default button is pushed, the value of every control on the pop-up is set to the values specified in the last call to SetFontPopupDefaults.
	allowMetaFonts	integer	If zero, the National Instruments supplied metafonts are not listed in the typeface selection ring. If nonzero, the metafonts are listed.
Input/ Output	typefaceName	string	On input, this buffer contains the typeface name (for example, "Courier") to be initially displayed in the selection ring. On output, this buffer contains the typeface name the user has selected. The buffer must be at least 256 bytes long. Pass 0 to hide the typeface selection ring and prevent the user from changing the typeface.
	bold	integer	On input, the value to initially set in the 'Bold' checkbox. On output, the final value in the 'Bold' checkbox. Pass 0 to hide the 'Bold' checkbox.

(continues)

## **Parameters (Continued)**

underline	integer	On input, the value to initially set in the 'Underline' checkbox. On output, the final value in the 'Underline' checkbox. Pass 0 to hide the 'Underline' checkbox.
strikeOut	integer	On input, the value to initially set in the 'StrikeOut' checkbox. On output, the final value in the 'StrikeOut' checkbox. Pass 0 to hide the 'StrikeOut' checkbox.
italic	integer	On input, the value to initially set in the 'Italic' checkbox. On output, the final value in the 'Italic' checkbox. Pass 0 to hide the 'Italic' checkbox.
justification	integer	On input, the value to initially set in the 'Justification' ring control. On output, the final value in the 'Justification' ring control. Pass 0 to hide the 'Justification' ring control.
textColor	integer	On input, the value to initially set in the 'Text Color' control. On output, the final value in the 'Text Color' control. Pass 0 to hide the 'Text Color' control.
fontSize	integer	On input, the value to initially set in the 'Font Size' control. On output, the final value in the 'Font Size' control. Pass 0 to hide the 'Font Size' control.

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **Return Codes**

0	User canceled out of dialog box	
1	User modified the settings	

## **Parameter Discussion**

The valid values for justification are

VAL\_LEFT\_JUSTIFIED VAL\_RIGHT\_JUSTIFIED

VAL\_CENTER\_JUSTIFIED

**textColor** is an RGB value. An RGB value is an integer in the hexadecimal format 0x00RRGGBB, where RR, GG, and BB are the respective red, green, and blue components of the color value.

**fontSize** is specified in units of points.

If the user cancels out of the dialog box or the function returns an error code, none of the Input/Output parameters are modified.

#### See Also

SetFontPopupDefaults.

## GenericMessagePopup

### **Purpose**

This function displays a dialog box with a user-defined message and optionally accepts a response string.

Up to three buttons are provided for generic use. The function returns a value indicating which button was pressed.

Input	title	string	The title of the dialog box.
	message	string	The message displayed on the dialog box.
	buttonLabel1	string	The label on button 1.
	buttonLabel2	string	The label on button 2. To hide buttons 2 and 3, pass 0 to Button Label 2.
	buttonLabel3	string	The label on button 3. To hide button 3, pass 0 to Button Label 3.
	maxResponseLength	integer	The maximum number of bytes the user is allowed to enter. The <b>ResponseBuffer</b> must be large enough to contain all of the user's input plus one ASCII NULL byte.
	buttonAlignment	integer	Selects the location of the three buttons for the generic message pop-up. A non-zero value aligns the buttons along the side of the dialog box. A value of zero aligns the buttons along the bottom of the dialog box.
	activeControl	integer	Selects one of the three buttons or the input string as the active control. The active control is the control that accepts keystrokes when the dialog box is displayed. The following attribute names apply to activeControl.  VAL_GENERIC_POPUP_BTN1  VAL_GENERIC_POPUP_BTN2  VAL_GENERIC_POPUP_BTN3  VAL_GENERIC_POPUP_INPUT_STRING
	enterButton	integer	Selects which button has <enter> as its shortcut key. If no button is to have <enter> as its shortcut key, pass VAL_GENERIC_POPUP_NO_CTRL.</enter></enter>
	escapeButton	integer	Selects which button has <esc> as its shortcut key. If no button is to have <esc> as its shortcut key, pass VAL_GENERIC_POPUP_NO_CTRL.</esc></esc>
Output	responseBuffer	string	The buffer in which the user's response is stored. The buffer must be large enough to hold Max Response Length bytes plus one ASCII NULL byte. To hide the input string, pass 0 to Response Buffer.

### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### **Return Codes**

0	VAL_GENERIC_POPUP_NO_CTRL
1	VAL_GENERIC_POPUP_BTN1
2	VAL_GENERIC_POPUP_BTN2
3	VAL_GENERIC_POPUP_BTN3

## **Get3dBorderColors**

## **Purpose**

Takes an RGB value for the base color of an object and returns the RGB values for colors that can be used to make the object look 3-dimensional. The colors returned are similar to the colors used in Windows 95 for drawing 3-dimensional objects.

#### **Parameters**

Input	baseColor	integer	The RGB value for the color of an object.
Output	highlightColor	integer The RGB value for the color used to indicate the edges of the object that are in the most direct light	
	lightColor	integer	The RGB value for the color used to indicate the transition between the highlight color and the base color of the object.
	shadowColor	integer	The RGB value for the color used to indicate the edges of the object that are angled away from the light.
	darkShadowColor	integer	The RGB value for the color used to indicate the edges of the object that are angled farthest away from the light.

#### **Parameter Discussion**

You may pass NULL for any of the output parameters.

Currently, the **lightColor** is always the same as the **baseColor**, as is the case in Windows 95.

Currently, the **darkShadowColor** is always black, as is the case in Windows 95.

### **GetActiveCtrl**

int activeCtrl = GetActiveCtrl (int panelHandle);

### Purpose

This function obtains the ID of the active control on the specified panel.

The active control is the control that receives keyboard events when its panel is the active panel.

#### **Parameters**

Input	panelHandle	integer	
			memory. This handle will have been returned by the
			LoadPanel, NewPanel, or DuplicatePanel function.

#### **Return Value**

activeCtrl	J	Returns the control ID of the active control. The control ID was assigned to the control in the User Interface Editor, or returned by the NewCtrl or DuplicateCtrl function. Refer to Appendix A for error codes.
------------	---	---

# Get Active Graph Cursor

## Purpose

Obtains the active cursor on the specified graph control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	activeCursorNumber	integer	Returns the number of the active cursor. The value will range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.

## **Return Value**

status integer Refer to Appendix A for error codes.		
---	--	--

## **GetActivePanel**

int activePanel = GetActivePanel (void);

## **Purpose**

Obtains the handle of the active panel. The active panel is the panel that receives keyboard events.

activePanel	integer	Returns the handle of the active panel. this handle will have originally been assigned by
		LoadPanel, NewPanel, or Duplicate Panel. Refer to Appendix A for error codes.

## **GetAxisItem**

## **Purpose**

This function retrieves the string/value pair at the specified index in the list of label strings for a graph or strip chart axis.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	axis	integer	Specifies the axis from which to retrieve the selected string/value pair. Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)	
	itemIndex	integer	A zero-based index into the list of label strings.	
Output	itemLabel	string	Buffer in which the label string is returned.	
	itemValue	double- precision	The value associated with the label string.	

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

### **Parameter Discussion**

**itemLabel** must be large enough to hold the label string, including the terminating NUL byte. You can use GetAxisItemLabelLength to determine the length of the label string.

You may pass NULL for either of the output parameters.

#### See Also

InsertAxisItem, GetNumAxisItems, GetAxisItemLabelLength

# Get Axis Item Label Length

## **Purpose**

This function obtains the number of characters in a label string for a graph or strip chart axis. The label string is specified by its index in the list of string/value pairs for that axis.

The length returned does not include the terminating NUL byte.

#### **Parameters**

Input	panelHandle	integer The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	axis	integer	Specifies the axis for which to return the length of the selected label string. Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)
	itemIndex	integer	A zero-based index into the list of label strings.
Output	length	string	The length of the selected label string. Excludes the terminating NUL byte.

#### **Parameter Discussion**

**itemLabel** must be large enough to hold the label string, including the terminating NUL byte. You can use GetAxisItemLabelLength to determine the length of the label string.

You may pass NULL for either of the output parameters.

#### See Also

InsertAxisItem, GetNumAxisItems, GetAxisItem.

# GetAxisRange

## **Purpose**

Obtains the scaling mode and the range of the X and Y axes for a graph or strip chart control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

(continues)

## **Parameters (Continued)**

Output	xAxisScalingMode	integer	The current scaling mode of the X axis. $0L = VAL\_MANUAL$ $1L = VAL\_AUTOSCALE$
	xmin	double- precision	The current minimum range of the x-axis.
	xmax	double- precision	The current maximum range of the x-axis.
	yAxisScalingMode	integer	The current scaling mode of the Y axis. $0L = VAL\_MANUAL$ $1L = VAL\_AUTOSCALE$ .
	ymin	double- precision	The current minimum range of the Y axis.
	ymax	double- precision	The current maximum range of the Y axis.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

## **xAxisScalingMode**

VAL\_MANUAL The X axis is set to manual scaling, and its range is defined by Xmin and Xmax.

VAL\_AUTOSCALE The X axis is set to auto scaling. Xmin and Xmax are not returned. Auto scaling is not allowed for strip charts.

## yAxisScalingMode

VAL\_MANUAL The Y axis is set to manual scaling, and its range is defined by Ymin and Ymax.

VAL\_AUTOSCALE The Y axis is set to auto scaling. Ymin and Ymax are not returned. Auto scaling is not allowed for strip charts.

# **GetAxisScalingMode**

## **Purpose**

Obtains the scaling mode and the range of any graph axis or the Y axis of a strip chart.

This function is not valid for the X axis of a strip chart. To obtain the X offset and X increment for a strip chart, use the GetCtrlAttribute function with the ATTR\_XAXIS\_OFFSET and ATTR\_XAXIS\_GAIN attributes.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies for which axis to obtain the mode and range.  Valid values:  VAL_XAXIS (graphs only)  VAL_LEFT_YAXIS (graphs and strip charts)  VAL_RIGHT_YAXIS (graphs only)
Output	axisScaling	integer	The scaling mode used for the axis. See table below.
	min	double- precision	The current minimum value on the axis.
	max	double- precision	The current maximum value on the axis.

<b>status</b> integer
-----------------------

#### **Parameter Discussion**

**axisScaling** is one of the following values.

Valid Value	Description
VAL_MANUAL	The axis is set to manual scaling, and its range is defined by <b>min</b> and <b>max</b> .
VAL_AUTOSCALE	The axis is set to auto scaling. <b>min</b> and <b>max</b> are not used. Auto scaling is not valid for strip charts.
VAL_LOCK	The axis is set to manual scaling using the current (possibly auto scaled) minimum and maximum values on the axis. VAL_LOCK is not valid for strip charts.

If you call SetAxisScalingMode with **axisScaling** set to VAL\_AUTOSCALE, and you then call SetAxisScalingMode with **axisScaling** set to VAL\_LOCK, GetAxisScalingMode returns **axisScaling** as VAL\_MANUAL.

max always exceeds min.

You may pass NULL for any of the output parameters.

#### See Also

SetAxisScalingMode

# GetBitmapData

#### **Purpose**

Obtains the bit values that define the image associated with a bitmap. Before calling GetBitmapData, you must do one of the following.

- Call GetBitmapInfo to get the size of the buffers needed, and then allocate the buffers, or
- Call AllocBitmapData.

Input	bitmapID	integer	The ID of the bitmap object containing the image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.
Output	bytesPerRow integer		The number of bytes on each scan line of the image.
	pixelDepth integer		The number of bits per pixel.
	width integer		The width of the image, in pixels.
	height	integer	The height of the image, in pixels.
	colorTable integer array		An array of RGB color values, or NULL if <b>pixelDepth</b> is greater than 8.
	bits unsigned char array		An array of bits that determine the colors to be displayed on each pixel in the image.
	mask	unsigned char array	An array containing one bit per pixel in the image. Each bit specifies whether the pixel is actually drawn. May be NULL.

#### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

### **Parameter Discussion**

If there is no image, the **width** and **height** parameters are set to -1. If the bitmap originated from a Windows metafile (.WMF), the size of the bitmap obtained by this function is the size stored in the original Windows metafile.

The **pixelDepth** parameter is set to 1, 2, 8, 24, or 32.

The number of bits in the **bits** array for each pixel is equal to the **pixelDepth** value. If **pixelDepth** is 8 or less, the **bits** array is filled with indices into the **colorTable** array, and the number of entries in the **colorTable** array is 2 raised to the power of the **pixelDepth** parameter. If **pixelDepth** is greater than 8, the **colorTable** array is not used, and the **bits** array contains the actual RGB values.

For a **pixelDepth** of 24, each pixel is represented by a 3-byte RGB value of the form 0xRRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte is always at the lowest memory address of the three bytes.

If the **pixelDepth** is 32, each pixel in the **bits** array is represented by a 32-bit RGB value of the form  $0 \times 0 \, 0 \, \text{RRGGBB}$ , where RR, GG, and BB represent the red, green and blue intensity of the color. The 32-bit value is treated as a native 32-bit integer value for the platform. The most significant byte is always ignored. The BB byte should always be in the least significant byte. On a little-endian platform (for example, Intel processors), BB would be at the lowest memory address. On a big-endian platform (for example, Motorola processors), BB would be at the highest address. Note that this differs from the format of the bits array when the **pixelDepth** is 24.

The first pixel in the **bits** array is at the top, left corner of the image. The pixels in the array are in row-major order.

If GetBitmapInfo sets the **colorSize** parameter to zero, the **colorTable** array is not filled in.

In the **mask** array, a bit value of 1 indicates that the pixel is drawn. 0 indicates that the pixel is not drawn. Exception: If an image has a **pixelDepth** of 1, pixels with a **bits** value of 1 (foreground pixels) are always drawn and the **mask** affects only the pixels with a bitmap of 0 (background pixels). Each row of the mask is padded to the nearest even-byte boundary. For example, if the width of the image is 21 pixels, then there are 32 bits (in other words, 4 bytes) of data in each row of the mask.

A mask is useful for achieving transparency.

If GetBitmapInfo sets the **maskSize** parameter to zero, the **mask** array is not filled in.

You may pass NULL for any of the output parameters.

#### See Also

NewBitmap, GetBitmapFromFile, GetCtrlBitmap, GetCtrlDisplayBitmap, GetPanelDisplayBitmap, ClipboardGetBitmap, GetBitmapInfo, AllocBitmapData.

# **GetBitmapFromFile**

int status = GetBitmapFromFile(char fileName[], int \*bitmapID);

#### **Purpose**

Reads a bitmap image from a file and creates a bitmap object. The bitmap ID can then be passed to any function that accepts a bitmap, such as CanvasDrawBitmap or ClipboardPutBitmap.

You can discard the bitmap object by passing its ID to DiscardBitmap.

You can use the following image types:

PCX: Windows and SPARCstation

BMP, DIB, RLE, ICO: Windows only

WMF: Windows 95 and NT only

XWD: SPARCstation only

### **Parameters**

Input	fileName	string	The pathname of the file which contains the image. If the name is a simple filename, the file is loaded from the project. If it is not found in the project, the file is loaded from the directory containing the project.
Output	bitmapID	integer	An ID that serves as a handle to the bitmap object.

#### **Return Value**

status intege	Refer to Appendix A for error codes.
---------------	--------------------------------------

#### See Also

ClipboardPutBitmap, GetBitmapData, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

# GetBitmapInfo

### **Purpose**

Obtains size information about the image associated with a bitmap. This information can then be used in allocating the buffers to be passed to the GetBitmapData function.

As an alternative to this function, you can call AllocBitmapData, which allocates the buffers for you.

Input	bitmapID	integer	The ID of the bitmap object containing the image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.	
Output	colorSize	integer	The number of bytes in the image color table (0 if the pixel depth of the image is greater than 8).	
	bitsSize	integer	The number of bytes in the image bitmap.	
	maskSize	integer	The number of bytes in the image mask (0 if there is no mask).	

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### **Parameter Discussion**

You may pass NULL for any of the output parameters.

#### See Also

GetBitmapData, AllocBitmapData.

## **GetCtrlAttribute**

## **Purpose**

Obtains the value of a control attribute from the selected panel and control.

Since attributes may Return Values of different data types with different valid ranges, a list of attributes, their data types and valid values are provided in Table 3-9 in Chapter 3, *Programming with the User Interface Library*.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	controlAttribute	integer	Selects a control attribute. Many control attributes are specific to one kind of control, while others are used with all or many different controls. See Table 3-9 in Chapter 3 for a complete listing of control attributes.
Output	attributeValue	void *	Returns the value of the specified control attribute. See Table 3-9 in Chapter 3 for a complete listing of control attributes.

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# GetCtrlBitmap

 $\label{eq:controlID} \mbox{int } status = GetCtrlBitmap (\mbox{int } panelHandle, \mbox{int } controlID, \mbox{int } imageID, \\ \mbox{int } *bitmapID);$ 

## **Purpose**

Obtains a bitmap image from a control and stores it in a bitmap object. The bitmap ID can then be passed to any function that accepts a bitmap, such as CanvasDrawBitmap or ClipboardPutBitmap.

The following control types can contain images:

picture controls picture rings picture buttons graph controls canvas controls You can use this function on images set using DisplayImageFile, InsertListItem, ReplaceListItem, PlotBitmap, or SetImageBits, or SetCtrlAttribute with the ATTR\_IMAGE\_FILE attribute.

You can discard the bitmap object by passing its ID to DiscardBitmap.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	imageID	integer	For picture rings, the zero-based index of an image in the ring. For graphs, this argument is the <b>plotHandle</b> returned from PlotBitmap. For picture controls, picture buttons, and canvas controls, this argument is ignored.
Output	bitmapID	integer	An ID that serves as a handle to the bitmap object.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

ClipboardPutBitmap, GetBitmapData, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

# GetCtrlBoundingRect

### **Purpose**

This function returns the top, left, width, and height coordinates for the control's bounding rectangle.

The control's labels are included within the bounding rectangle.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	top	integer	Returns the top coordinate of the control's bounding rectangle.
	left	integer	Returns the left coordinate of the control's bounding rectangle.
	height	integer	Returns the vertical size of the control's bounding rectangle.
	width	integer	Returns the horizontal size of the control's bounding rectangle.

### **Return Value**

status in	nteger	Refer to Appendix A for error codes.
-----------	--------	--------------------------------------

#### **Parameter Discussion**

You can pass 0 (zero) to any parameter from which you are not interested in getting the value. The range of the **top** and **left** Parameters is -32768 to 32767. The range of the **height** and **width** Parameters is 1 to 32767. The origin (0,0) is at the upper left corner of the panel (before the panel is scrolled) directly below the title bar.

# GetCtrlDisplayBitmap

#### **Purpose**

This function creates a bitmap object containing a "snapshot" image of the current appearance of the specified control. The bitmap ID can then be passed to any function that accepts a bitmap, such as CanvasDrawBitmap or ClipboardPutBitmap.

For example, you can paste a picture of a control onto the system clipboard by calling GetCtrlDisplayBitmap and then passing the bitmap ID to ClipboardPutBitmap.

You can discard the bitmap object by passing the ID to the DiscardBitmap function.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	includeLabel	integer	If nonzero, the control label is included in the image.
Output	bitmapID	integer	An ID that serves as a handle to the bitmap object.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### See Also

ClipboardPutBitmap, GetBitmapData, GetPanelDisplayBitmap, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

## **GetCtrlIndex**

int status = GetCtrlIndex (int panelHandle, int controlID, int \*itemIndex);

### **Purpose**

This function returns the current index of the specified list control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	itemIndex	integer	Returns the current index of the specified list control.  Returns -1 if the list control has no items.

### **Return Value**

<b>status</b> in	nteger	Refer to Appendix A for error codes.
------------------	--------	--------------------------------------

## **GetCtrlVal**

int status = GetCtrlVal (int panelHandle, int controlID, void \*value);

## **Purpose**

Obtains the current value of a control.

When called on a list control (a list box or ring), GetCtrlVal returns the value of the current (selected) list item. To obtain the index of the selected list item, use the GetCtrlIndex function.

#### **Parameters**

Input	panelHandle integer		The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	value	void *	Returns the control's value. The data type of <b>value</b> must match the data type of the control.

### **Return Value**

status integer Refer to Append	dix A for error codes.
--------------------------------	------------------------

## **GetCursorAttribute**

## **Purpose**

Obtains one of the following graph cursor attributes: mode, point style, cross hair style, color, y-axis.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
	cursorAttribute	integer	Selects a particular graph cursor attribute.  Valid Attributes:  ATTR_CURSOR_MODE  ATTR_CURSOR_POINT_STYLE  ATTR_CROSS_HAIR_STYLE  ATTR_CURSOR_COLOR  ATTR_CURSOR_YAXIS
Output	attributeValue	integer	See Table 3-20 in Chapter 3 for a complete listing of cursor attributes.

<b>status</b> intege	Refer to Appendix A for error codes.
----------------------	--------------------------------------

### **GetCVITaskHandle**

int taskHandle = GetCVITaskHandle (void);

Note: This function is available only on the Windows 3.1 version of LabWindows/CVI.

## **Purpose**

This function returns the Windows 3.1 task handle associated with the LabWindows/CVI application. This number can be used by a DLL requiring LabWindows/CVI's Windows task handle.

For Windows 95 and NT, use the Windows API function GetCurrentProcessID.

#### **Return Value**

taskHandle	integer	The Windows task handle associated with the
		LabWindows/CVI application.

#### **GetCVIWindowHandle**

int windowHandle = GetCVIWindowHandle (void);

Note: This function is available only on the Windows version of LabWindows/CVI.

#### **Purpose**

This function returns the window handle associated with the LabWindows/CVI application. This number should be used in the DLL as the hwnd parameter for the Windows function, PostMessage, as indicated in the Windows SDK documentation.

To make this work, you call RegisterWinMsgCallback and GetCVIWindowHandle and then pass their Return Values (uMsg and hwnd) to the DLL. When the DLL wants to send a message, it calls PostMessage with these values. When LabWindows/CVI receives the message, it calls the callback function.

Note: LabWindows/CVI can receive the message only when it is processing events.

LabWindows/CVI processes events when it is waiting for user input. If the program running in LabWindows/CVI does not call RunUserInterface, GetUserEvent, or scanf, or if it does not return from a User Interface Library callback, events will not be processed. This can be remedied in the program by calling the User Interface Library function ProcessSystemEvents periodically.

### **Return Value**

windowHandle	integer	The Windows handle associated with the
		LabWindows/CVI application.

### GetGlobalMouseState

## **Purpose**

Obtains information about the state of the mouse cursor. **xCoordinate** and **yCoordinate** are set to the position of the mouse relative to the top, left corner of the screen.

#### **Parameters**

Output	panelHandle	integer	The handle of the panel that the mouse is over. 0 if the mouse is not over a panel.
	xCoordinate	integer	The x-coordinate of the mouse cursor relative to the left edge of the screen.
	yCoordinate	integer	The y-coordinate of the mouse cursor relative to the top of the screen.
	leftButtonDown	integer	0 if the left button is up. 1 if the left button is down.
	rightButtonDown	integer	0 if the right button is up. 1 if the right button is down.
	keyModifiers	integer	The state of the keyboard modifiers the (in other words, the <ctrl> and <shift> keys). If no keys are down, the value is 0. Otherwise, the value is the bitwise 'OR' of the appropriate key masks:  VAL_MENUKEY_MODIFIER and VAL_SHIFT_MODIFIER.</shift></ctrl>

status integer Refer to Appendix A for em	or codes.
---	-----------

### **Parameter Discussion**

You may pass NULL (0) in place of any of the output parameters.

#### See Also

GetRelativeMouseState.

# GetGraphCursor

# **Purpose**

Obtains the current position of the specified graph cursor.

The position is relative to the current range of the X and Y axes.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
Output	x	double- precision	Returns the X coordinate of the cursor position.
	y	double- precision	Returns the Y coordinate of the cursor position.

### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# ${\bf GetGraphCursorIndex}$

## **Purpose**

Obtains the plot handle and array index of the plot on which the cursor is attached.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
Output	plotHandle	integer	Contains the ID of the plot to which the cursor is attached. If the cursor is not attached to a plot, -1 is returned.
	arrayIndex	integer	Contains the array index of the data point to which the cursor is attached. If the cursor is attached to a point plot, or if the cursor is not attached to a data point, -1 is returned.

status integer Refer to Appendix A for error codes.
---

# **GetImageBits**

## **Purpose**

Obtains the bit values that define an image. You can modify the bit values and then apply them back to the image using SetImageBits.

Before calling GetImageBits,

- Call GetImageInfo to get the size of the buffers needed, and then allocate the buffers, or
- Call AllocImageBits.

The following control types can contain images.

picture controls picture rings picture buttons graph controls

This function can be used in images set via DisplayImageFile, InsertListItem, ReplaceListItem, PlotBitmap, or SetImageBits, or SetCtrlAttribute with the ATTR\_IMAGE\_FILE attribute.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the user Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	imageID	integer	For a picture ring, the zero-based index of an image in the ring. For a graph, the <b>plotHandle</b> returned from PlotBitmap. For picture controls and buttons, this is ignored.

(continues)

#### (Continued)

Output	rowBytes	integer	The number of bytes on each scan line of the image.
	depth	integer	The number of bits per pixel.
	width	integer	The width of the image, in pixels.
	height	integer	The height of the image, in pixels.
	colorTable	integer array	An array of RGB color values.
	bitmap	unsigned char array	An array of bits that determine the colors to be displayed on each pixel in the image.
	mask	unsigned char array	An array containing one bit per pixel in the image. Each bit specifies whether the pixel is actually drawn.

#### **Return Value**

status intege	Refer to Appendix A for error codes.
---------------	--------------------------------------

#### **Parameter Discussion**

If there is no image, the **width** and **height** parameters are set to -1. If the image was originally rendered from a Windows metafile (.WMF), the size of the bitmap obtained by this function is determined as follows.

- If the image was on a graph control or if the fit mode is VAL\_SIZE\_TO\_PICTURE, the size of the bitmap is the size of the image as it appears in the control.
- If the image is on a picture, picture ring, or picture button, and the fit mode is other than VAL\_SIZE\_TO\_PICTURE, the size of the bitmap is the size stored in the original Windows metafile.

The number of entries in the **colorTable** array must be equal to 2 raised to the power of the **depth** parameter.

The **pixelDepth** parameter is set to 1, 2, 8, 24, or 32.

The number of bits in the **bits** array for each pixel is equal to the **pixelDepth** value. If **pixelDepth** is 8 or less, the **bits** array is filled with indices into the **colorTable** array, and the number of entries in the **colorTable** array is 2 raised to the power of the **pixelDepth** parameter. If **pixelDepth** is greater than 8, the **colorTable** array is not used, and the **bits** array contains the actual RGB values.

For a **pixelDepth** of 24, each pixel is represented by a 3-byte RGB value of the form 0xRRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte is always at the lowest memory address of the three bytes.

If the **pixelDepth** is 32, each pixel in the **bits** array is represented by a 32-bit RGB value of the form  $0 \times 00$ RRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The 32-bit value is treated as a native 32-bit integer value for the platform. The most significant byte is always ignored. The BB byte should always be in the least significant byte. On a little-endian platform (for example, Intel processors), BB would be at the lowest memory address. On a big-endian platform (for example, Motorola processors), BB would be at the highest address. Note that this differs from the format of the bits array when the **pixelDepth** is 24.

The first pixel in the **bits** array is at the top, left corner of the image. The pixels in the array are in row-major order.

If GetBitmapInfo sets the **colorSize** parameter to zero, the **colorTable** array is not filled in.

In the **mask** array, a bit value of 1 indicates that the pixel is drawn. 0 indicates that the pixel is not drawn. Exception: If an image has a **pixelDepth** of 1, pixels with a **bits** value of 1 (foreground pixels) are always drawn and the **mask** affects only the pixels with a bitmap of 0 (background pixels). Each row of the mask is padded to the nearest even-byte boundary. For example, if the width of the image is 21 pixels, then there are 32 bits (in other words, 4 bytes) of data in each row of the mask.

A mask is useful for achieving transparency.

If GetImageInfo sets the **maskSize** parameter to zero, the **mask** array will not be filled in.

You may pass NULL for any of the output parameters.

You can now use a 24-bit pixel depth in the four picture control image bits functions. When you do, the color table parameters to the functions are not used. The array of bits contains RGB values rather than indexes into the color table. Each RGB value in the array of bits represented by a 3-byte value of the form

0xRRGGBB

where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte should always be at the lowest memory address of the three bytes.

#### See Also

GetImageInfo, AllocImageBits, SetImageBits.

# GetImageInfo

## **Purpose**

Obtains size information about an image associated with a control on a panel. This information can then be used in allocating the buffers to be passed to the GetImageBits function.

The following control types can contain images.

picture controls picture rings picture buttons graph controls

As an alternative to this function, you can call AllocImageBits, which allocates the buffers for you.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the user Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	imageID	integer	For a picture ring, the zero-based index of an image in the ring. For a graph, the <b>plotHandle</b> returned from PlotBitmap. For picture controls and buttons, this is ignored.	
Output	colorSize	integer	The number of bytes in the image color table (-1 if there is no image).	
	bitmapSize	integer	The number of bytes in the image bitmap (-1 if there is no image).	
	maskSize	integer	The of bytes in the image mask (0 if the image has no mask1 if there is no image.)	

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### **Parameter Discussion**

You may pass NULL for any of the output parameters.

You can now use a 24-bit pixel depth in the four picture control image bits functions. When you do, the color table parameters to the functions are not used. The array of bits contains RGB values rather than indexes into the color table. Each RGB value in the array of bits represented by a 3-byte value of the form

0xRRGGBB

where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte should always be at the lowest memory address of the three bytes.

#### See Also

GetImageBits.

## **GetIndexFromValue**

int status = GetIndexFromValue (int panelHandle, int controlID, int \*index, ...);

## **Purpose**

This function returns the index of the first list item with the specified value.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemValue	depends on the type of the control	Specifies the value whose index will be returned.
Output	index	integer	Returns the index of the first list item with the specified value.

### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **GetLabelFromIndex**

## **Purpose**

This function returns the label of the specified list item.

For picture ring controls, this function returns an empty string.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	itemIndex	integer	The zero-based index into the list.	
Output	itemLabel	string	Returns the label of the selected list item.	

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# Get Label Length From Index

## **Purpose**

This function returns the label length of the specified list item.

For picture ring controls, this function returns zero.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	itemIndex	integer	The zero-based index into the list.	
Output	length	integer	Returns the number of characters in the label of the selected list item.	

#### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# GetListItemImage

### **Purpose**

This function returns a value corresponding to the image state of the specified list item.

The image state of a list item indicates the presence of various folder icons next to the item.

This function is not valid for picture ring controls. For picture rings, see GetImageBits.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.  The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.  The zero-based index into the list.	
	controlID	integer		
	itemIndex	integer		
Output	image	integer	Returns the value corresponding to the image state of the specified list item. The possible image states are:  0 = VAL_NO_IMAGE  1 = VAL_FOLDER  2 = VAL_OPEN_FOLDER  3 = VAL_CURRENT_FOLDER	

### **Return Value**

status integer Refer to Appendix A for error codes.
---

## **GetMenuBarAttribute**

## **Purpose**

This function returns the value of the specified menu bar attribute.

Input menuBarHandle menuorMenuItemID	menuBarHandle	integer	The ID which was assigned to the menu or menu item by the User Interface Editor (located in the .uir header file), or returned by NewMenu, NewSubMenu, or NewMenuItem.
	integer	The ID which was assigned to the menu or menu item by the User Interface Editor (located in the .uir header file), or returned by NewMenu, NewSubMenu, or NewMenuItem. If the attribute corresponds to the entire menu bar, pass 0 (zero) as this parameter.	
	menuBarAttribute	integer	A particular menu bar attribute. See Table 3-6 in Chapter 3 for a complete listing of menu bar attributes.
Output	attributeValue	void *	The value of the selected menu bar attribute. See Table 3-6 in Chapter 3 for valid values associated with all menu bar attributes.

## **Return Value**

status integer Refer to Appendix A for error codes.
---

## GetMouseCursor

int status = GetMouseCursor (int \*mouseCursorStyle);

# Purpose

Returns the mouse cursor style set by SetMouseCursor.

### **Parameters**

Output	mouseCursorStyle	integer	Returns the mouse cursor style set by
			SetMouseCursor. The possible mouse
			cursor styles are shown in Table 3-4 of
			Chapter 3.

status	integer	Refer to Appendix A for error codes.

## **GetNumAxisItems**

## **Purpose**

Returns the number of items in the list of label strings for a graph or strip chart axis.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies the axis for which to return the count of string/value pairs. Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)
Output	count	integer	The number of string/value pairs for the axis.

## **Return Value**

## See Also

 ${\tt InsertAxisItem,\ GetAxisItem,\ GetAxisItemLabelLength}$ 

## **GetNumCheckedItems**

## **Purpose**

This function returns the number of checked list items from a specified list control.

This function only applies to list boxes with the check mode attribute set.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	numberofItems	integer	Returns the number of list items that are checked.

#### **Return Value**

status i	integer	Refer to Appendix A for error codes.
----------	---------	--------------------------------------

## **GetNumListItems**

int status = GetNumListItems (int panelHandle, int controlID, int \*count);

### **Purpose**

This function returns the number of list items in the specified list control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	count	integer	Returns the number of items in the specified list control. Because the indices are zero-based, this value will be 1 greater than the index of the last item.

## **Return Value**

<b>status</b> integ	Refer to Appendix A for error codes.
---------------------	--------------------------------------

## **GetNumTextBoxLines**

int status = GetNumTextBoxLines (int panelHandle, int controlID, int \*count);

## **Purpose**

This function returns the number of lines containing text in the specified text box.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
Output	count	integer	Returns the number of lines containing text in the specified text box.

#### **Return Value**

status integer Refer to Append	dix A for error codes.
--------------------------------	------------------------

## **GetPanelAttribute**

### **Purpose**

This function returns the value of a particular panel attribute.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	panelAttribute	integer	See Table 3-2 in Chapter 3 for a complete listing of panel attributes.
Output	attributeValue	void *	The value of the specified panel attribute. See Table 3-2 in Chapter 3 for valid values associated with all panel attributes.

#### **Return Value**

status i	integer	Refer to Appendix A for error codes.
----------	---------	--------------------------------------

# GetPanelDisplayBitmap

## **Purpose**

This function creates a bitmap object containing a "snapshot" image of the current appearance of the specified panel. The bitmap ID can then be passed any function that accepts a bitmap, such as CanvasDrawBitmap or ClipboardPutBitmap.

For example, you can paste a picture of a panel onto the system clipboard by calling GetPanelDisplayBitmap and then passing the bitmap ID to ClipboardPutBitmap.

You can discard the bitmap object by passing the ID to the DiscardBitmap function.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	scope	integer	Determines which portions of the specified panel are to be copied to the bitmap. See table of valid values below.
	area	Rect	Use this parameter to restrict the area of the panel copied into the bitmap. The rectangle coordinates are relative to the upper-left corner of the panel (directly below the title bar) before the panel is scrolled. Use VAL_ENTIRE_OBJECT if you do not want to restrict the area copied.
Output	bitmapID	integer	An ID that serves as a handle to the bitmap object.

# **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

The valid values for the **scope** parameter are:

Valid Values	Description
VAL_VISIBLE_AREA	The visible area of the panel is copied to the bitmap, including the frame, menu bar, and scroll bars.
VAL_FULL_PANEL	The entire contents of the panel are copied to the bitmap, excluding the frame, menu bar, and scroll bars. This includes contents that might currently be scrolled off the visible area.

### See Also

ClipboardPutBitmap, GetBitmapData, GetCtrlDisplayBitmap, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

# **GetPanelMenuBar**

int menuBarHandle = GetPanelMenuBar (int panelHandle);

# **Purpose**

This function returns the handle of the menu bar associated with the specified panel.

#### **Parameters**

Input	panelHandle	integer	1
			memory. This handle will have been returned by the
			LoadPanel, NewPanel, or DuplicatePanel
			function.

## **Return Value**

menuBarHandle	integer	The menu bar associated with the specified panel. The menu bar handle would have been returned by LoadMenuBar or NewMenuBar. If no menu bar is associated with the panel, zero is returned. Refer to Appendix A for error codes.
---------------	---------	--

# **GetPlotAttribute**

# **Purpose**

Obtains the value of a graph plot attribute.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the user Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	plotHandle	integer	The handle for a particular plot in the graph. It will have been returned by one of the graph plotting functions.
	plotAttribute	integer	Selects a particular graph plot attribute. See Table 3-20 in Chapter 3 for a complete listing of plot attributes.
Output	attributeValue	void *	Returns the value of the specified plot attribute. See Table 3-20 in Chapter 3 for a complete listing of plot attributes.

# **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **GetPrintAttribute**

int status = GetPrintAttribute (int printAttribute, int \*attributeValue);

# **Purpose**

Returns the value of the selected print attribute.

Input	printAttribute	integer	See Table 3-27 in Chapter 3 for a complete listing of print attributes.
Output	attributeValue	integer	The current value of the print attribute. See Table 3-27 in Chapter 3 for valid values associated with all print attributes.

status integer Refer to Appendix A for error codes.
---

# **GetRelativeMouseState**

## **Purpose**

Obtains information about the state of the mouse cursor. xCoordinate and yCoordinate are set to the position of the mouse relative to the top and left coordinates of the control specified. If controlID is 0, the coordinate information is relative to the top and left coordinates of the panel specified (excluding the panel frame and title bar). Note that the coordinates are returned even if the mouse is not over the control or the panel.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the user Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function. Pass 0 to indicate that the coordinates should be relative to the panel.
Output	xCoordinate	integer	The x-coordinate of the mouse cursor relative to the left edge of the control (or panel, if control ID is 0).
	yCoordinate	integer	The y-coordinate of the mouse cursor relative to the top of the control (or panel, if controlID is 0).
	leftButtonDown	integer	0 if the left button is up. 1 if the left button is down.
	rightButtonDown	integer	0 if the right button is up. 1 if the right button is down.
	keyModifiers	integer	The state of the keyboard modifiers the (in other words, the <ctrl> and <shift> keys). If no keys are down, the value is 0. Otherwise, the value is the bitwise 'OR' of the appropriate key masks:  VAL_MENUKEY_MODIFIER and VAL_SHIFT_MODIFIER.</shift></ctrl>

status i	integer	Refer to Appendix A for error codes.
----------	---------	--------------------------------------

# **Parameter Discussion**

You may pass NULL (0) in place of any of the output parameters.

### See Also

GetGlobalMouseState.

## **GetScreenSize**

int status = GetScreenSize (int \*height, int \*width);

# **Purpose**

Returns the height and width of the screen in pixels.

#### **Parameters**

Outp	put	height	integer	Height of the screen in pixels.
		width	integer	Width of the screen in pixels.

## **Return Value**

<b>status</b> integ	ger Refer to Appendix A for error codes.
---------------------	--

# **GetSharedMenuBarEventPanel**

int panelHandle = GetSharedMenuBarEventPanel (void);

# **Purpose**

This function returns the handle for the panel on which the last menu commit event occurred.

This function is especially useful when one menu bar is shared by multiple panels.

panelHandle	integer	Returns the handle for the panel on which the last
		commit event occurred. Refer to Appendix A for error
		codes.

# **GetSleepPolicy**

int sleepPolicy = GetSleepPolicy (void);

# **Purpose**

Obtains the current "sleep" policy. See SetSleepPolicy for more information on "sleeping".

## **Return Value**

sleepPolicy integer	The current sleep policy.
---------------------	---------------------------

## **Return Codes**

VAL_SLEEP_NONE	1	Never be put to sleep.
VAL_SLEEP_SOME	2	Be put to sleep a small period.
VAL_SLEEP_MORE	3	Be put to sleep for a longer period.

### See Also

SetSleepPolicy.

# **GetSystemAttribute**

int status = GetSystemAttribute (int systemAttribute, void \*attributeValue);

# **Purpose**

Returns the value of a particular system attribute.

### **Parameters**

Input	systemAttribute	integer	ATTR_ALLOW_UNSAFE_TIMER_EVENTS ATTR_REPORT_LOAD_FAILURE ATTR_ALLOW_MISSING_CALLBACKS
Output	attributeValue	void *	The value of the specified attribute. See Table 3-26 for values associated with this attribute.

### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **GetSystemPopupsAttribute**

int status = GetSystemPopupsAttribute (int popupAttribute, void \*attributeValue);

# **Purpose**

Returns the value of a particular system pop-up attribute.

#### **Parameters**

Input	popupAttribute	integer	ATTR_MOVABLE or ATTR_SYSTEM_MENU_VISIBLE
Output	attributeValue	void*	The value of the specified attribute. See Table 3-2 in Chapter 3 for valid values associated with these attributes.

## **Return Value**

	status	integer	Refer to Appendix A for error codes.
--	--------	---------	--------------------------------------

# **GetTextBoxLine**

# **Purpose**

This function returns a string from the specified text box line into Destination Buffer.

# **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	lineIndex	integer	The zero-based index into the text box.
Output	destinationBuffer	string	Returns the string at the specified text box line.

# **Return Value**

status integer Refer to Appendix A for error codes.
---

# Get Text Box Line Length

# **Purpose**

This function returns the number of characters in the selected text box line (including null characters.)

Input	panelHandle controlID	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.  The defined constant (located in the .uir header file)
	lineIndex	integer	which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.  The zero-based index into the text box.
Output	length	integer	Returns number of characters in the selected text box line.

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# GetTextDisplaySize

# **Purpose**

Returns the height and width of the specified text having the specified meta font.

### **Parameters**

Input	text metaFont	string string	The text string whose size is to be calculated.  The meta font to be used in calculating the size of the text.
Output	height width	integer integer	The height of the text in pixels.  The width of the text in pixels.

#### Return Value

status integr	Refer to Appendix A for error codes.
---------------	--------------------------------------

# **GetTraceAttribute**

## **Purpose**

Obtains one of the following strip chart trace attributes: color, trace style, point style, line style, visible.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	traceNumber	integer	The strip chart trace number may be from 1 to the number of defined strip chart traces. The number of defined strip chart traces is established through editing the strip chart in the User Interface Editor or calling SetCtrlAttribute
	traceAttribute	integer	Selects a particular strip chart trace attribute. See Table 3-20 in Chapter 3 for a complete listing of trace attributes.
Output	attributeValue	integer	The current value of the trace attribute.

# **Return Value**

status integer Refer to Appendix A for error codes.
---

# GetUILErrorString

char \*message = GetUILErrorString (int errorNum)

## **Purpose**

Converts the error number returned by a User Interface Library function into a meaningful error message.

### **Parameters**

Input <b>errorNum</b> integer	Status returned by User Interface function.
-------------------------------	---

# **Return Value**

message	string	Explanation of error.
---------	--------	-----------------------

# **GetUserEvent**

# Purpose

Obtains the next commit event or programmer-defined event from the GetUserEvent queue. A commit event occurs when the user changes the state of a hot or validate control or selects a menu item. Programmer-defined events are placed in the GetUserEvent queue by QueueUserEvent. The function description for QueueUserEvent describes valid programmer-defined events.

### **Parameters**

Input	waitMode	integer	If 1, GetUserEvent does not return until a commit event occurs. If 0, GetUserEvent returns immediately, whether or not a commit event has occurred.
Output	panelorMenuBarHandle	integer	Returns the handle of the panel or menu bar on which the commit event occurred. If <b>waitMode</b> is zero ("no wait") and no event has occurred, a -1 is returned.
	controlorMenuItemID	integer	Returns the ID of the control or menu item on which the commit event occurred. If <b>waitMode</b> is zero ("no wait") and no event has occurred, a -1 is returned.

## **Return Value**

|--|

## **Return Codes**

Contains the event retrieved from the GetUserEvent queue. The possible values are:

0	No event.
1	Commit event occurred.
1000-10000	Event queued by QueueUserEvent.

# **GetValueFromIndex**

# **Purpose**

This function returns the value for the specified list index.

### **Parameters**

Input	panelHandle controlID	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.  The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index into the list.
Output	itemValue	void *	Returns the value of the specified list item.

### **Return Value**

status into	eger	Refer to Appendix A for error codes.
-------------	------	--------------------------------------

# Get Value Length From Index

# **Purpose**

This function returns the length of the value for the specified list item.

This function is valid only for lists with string data type.

# **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID		The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index into the list.
Output	length	integer	Returns the length of the value at the Item Index.

### **Return Value**

integer Refer to Appendix A for error codes.	<b>status</b> in
--	------------------

# **GetWaitCursorState**

int cursorState = GetWaitCursorState (void);

# **Purpose**

Returns the state of the cursor, indicating whether the wait cursor is active or inactive.

# **Return Value**

<b>status</b> integ	ger Refer to Appendix A for error codes.
---------------------	--

# **Return Codes**

Returns the state of the wait cursor.

0	wait cursor inactive.
1	wait cursor active.

## **HidePanel**

int status = HidePanel (int panelHandle);

### **Purpose**

Clears a panel from the screen but leaves it in memory.

When a panel is hidden, it can still be updated programmatically. For example, you can add plots to a graph control on a hidden panel. When the panel displays again, it will show the new plots.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned
			by the LoadPanel, NewPanel, or DuplicatePanel function.

### **Return Value**

status	integer	Refer to Appendix A for error codes.	
--------	---------	--------------------------------------	--

## **InsertAxisItem**

# **Purpose**

This function inserts a string/value pair into the list of label strings associated with a graph or strip chart axis. These strings appear instead of the numerical labels. They appear at the location of their associated values on the graph or strip chart.

To see string labels on an X axis, you must set the ATTR\_XUSE\_LABEL\_STRINGS attribute to TRUE. To see string labels on a Y axis, you must set the ATTR\_YUSE\_LABEL\_STRINGS attribute to TRUE.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies the axis for which to insert the string/value pair. Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)
	itemIndex	integer	The zero-based index into the list at which the item is to be stored. Pass -1 to store the item at the end of the list. See discussion below.
	itemLabel	string	The label string being inserted. The label appears on the axis at the location of the associated value. A maximum of 31 characters are shown.
	itemValue	double- precision	The value to be associated with the label string being inserted. The label string appears on the axis at the location of the value.

## **Return Value**

status integer Refer to Appendix A for error codes.
---

## **Parameter Discussion**

**itemIndex** does not determine the order in which the labels appear on the axis. It merely represents the order in which LabWindows/CVI stores the string/value pairs. You can use the index as a handle for replacing or deleting label/value pairs.

If you pass -1 for **itemIndex**, the string/value pair is stored at the end of the list.

### See Also

ReplaceAxisItem, DeleteAxisItem, ClearAxisItems, GetNumAxisItems

## **InsertListItem**

# **Purpose**

This function inserts a label/value pair into a list or ring control at the specified zero-based index

The indices of existing label/value pairs at and beyond the specified index are increased by 1.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index into the list where the item will be placed. Pass -1 to insert the item at the end of the list.
	itemLabel	string	The label to be associated with the value being inserted.
	itemValue	depends on type of list control	The value to be associated with the label being inserted. The data type must be the same as the data type of the control.

#### **Return Value**

#### **Parameter Discussion**

For picture rings, the "label" is actually an image, and you pass the pathname of the image as the itemLabel parameter. The image pathname may be a complete pathname or a simple filename. If a simple filename, the image is located in the project. If not located in the project, it is located in the directory of the project. If you pass NULL or the empty string, a placeholder for the image is created, which can be filled using ReplaceListitem or SetImageBits.

You can create columns in a list box control by embedding escape codes in the **itemLabel** string. Use \033 to indicate an escape code, followed by p (for pixel), followed by a justification code

of 1 (left), c (center), or r (right). For example, the following code sets a left-justified column at the 100- and 200-pixel positions.

The preceding code segment creates the following tab format.

Chevrolet	Corvette	Red
Ford	Probe	Black

In the following example, the code segment sets a centered column at the 32-, 130-, and 230-pixel positions.

The preceding code segment creates the following tab format.

Chevrolet	Corvette	Red 🗖
Ford	Probe	Black

The code that inserts a vertical line is \033vline. The vertical line is added at the current position in the label.

You can also use escape codes to change the foreground and background colors of characters in a list box. The escape codes only affect the label that they are embedded into. Setting the color changes it until the color is changed again or the end of the line is reached.

To change the foreground color, the code is \033fgXXXXXX where XXXXXX is a 6 digit RGB value specified in hex.

To change the background color, the code is \033bgXXXXXX where XXXXXX is a 6 digit RGB value specified in hex.

To change either color back to the default color for the text, insert default instead of the 6 digit RGB value.

You can insert a separator bar into a ring control (Ring, Menu Ring, Recessed Menu Ring, or Pop-up Menu Ring) by embedding the escape code \033m- in the itemLabel string.

# **InsertSeparator**

# **Purpose**

This function inserts a new separator bar in the menu.

## **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuID	integer	The ID for a particular menu within a menu bar. The Menu ID should be a constant name (located in the .uir header file) generated by the User Interface Editor or a value returned by the NewMenu function.
	beforeMenuItemID	integer	The separator bar is inserted before (above) this menu item. To place the separator at the end (bottom) of the menu item list, enter -1 as the Before Menu Item ID.

# **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **InsertTextBoxLine**

# **Purpose**

This function inserts a string at the specified text box line.

Input	panelHandle	 The specifier for a particular panel that is currently in memory. This handle will have been returned by the
		LoadPanel, NewPanel, or DuplicatePanel
		function.

controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
lineIndex	integer	The zero-based index of a line in the specified text box. Pass -1 to insert the item at the end of the text box.
text	string	The text to be inserted at the specified Line Index.

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### **Parameter Discussion**

A text box in the User Interface Library can have only a limited number of lines. The number of lines multiplied by the pixel height of the font must be less than 32767, or else the text box will not scroll. In a text box that uses NIDialogMetaFont or NIEditorMetaFont, you can have a maximum of about 2500 lines.

# **InstallCtrlCallback**

# **Purpose**

This function installs a control callback. The InstallCtrlCallback function call takes a panel handle and control ID, the name of the event function that processes events for that control, and callback data of any type.

When an event is generated by the specified control (after the callback is installed), the event function is called.

This event function (type CtrlCallbackPtr) takes the form:

The event function is passed the panel handle and control ID of the control generating the event. Callback data defined by the user is also passed to the event function as well as the type of the event (such as a left mouse click), and any additional event data (such as the mouse position at

the time of a left mouse click). The possible control events and associated event data are shown in Table 3-1 of Chapter 3, *Programming with the User Interface Library*. Also refer to the online help for the Event Function control on the InstallCtrlCallback function panel.

A control callback can also be installed from the Edit Control panel in the User Interface Editor.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	eventFunction	CtrlCallbackPtr	The name of the user function that processes the control callback.
	callbackData	void *	A pointer to user defined data that is passed to the callback function.

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## InstallMainCallback

## **Purpose**

This function installs a main callback that is called for all panel, control, and menu events.

The InstallMainCallback function takes the name of an event function a pointer to callback data of any type, and a Boolean indicating whether or not to get idle events. (For a further discussion of the main callback, see the class help for Callback Functions.)

The **getIdleEvents** feature allows program execution to proceed when it would normally be suspended. For example, the program would normally be suspended in GetUserEvent or RunUserInterface when the user holds the mouse button down on a control or pull-down menu. Idle events occur continuously, even under these circumstances. Since the main callback

can receive idle events, the program can continue processing by responding to idle events. Call SetIdleEventRate to set the rate of idle events.

Note: EVENT\_VAL\_CHANGED and EVENT\_IDLE are the only events that are generated while a user holds the mouse button down on a control or pull-down menu.

The operating system blocks all events (including idle events) when a top-level panel is moved or sized.

When any event is generated (after the callback is installed), the event function is called.

This event function (type MainCallbackPtr) takes the form:

The event function is passed information on the source of the callback, either the panel handle and control ID, or the menu bar handle and menu item ID. Callback data defined by the user is also passed to the event function. Finally, the event function is also passed the type of the event (such as a left mouse click), and any additional event data (such as the mouse position at the time of a left mouse click). The possible events and associated event data that can be processed in the main callback are listed in Table 3-1 of Chapter 3, *Programming with the User Interface Library*. Also refer to the online help for the Event Function control on the InstallMainCallback function panel.

#### **Parameters**

Input	eventFunction	MainCallbackPt r	The name of the user function that processes the main callback.
	callbackData	void *	A pointer to user-defined data passed to the event function.
	getIdleEvents	integer	<ul><li>1 = respond to idle events.</li><li>0 = ignore idle events.</li></ul>

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## InstallMenuCallback

# **Purpose**

This function installs a menu callback. It takes a menu bar handle and menu/menu item ID, the name of the event function that processes commit events for the menu/menu item, and callback data of any type.

When an event is generated on the specified menu bar (after the callback is installed), the event function is called.

This event function (type MenuCallbackPtr) takes the form:

When a commit event is generated by a menu selection, the event function is passed the menu bar handle, menu item ID, and panel handle of the menu bar generating the event. Callback data defined by the user is also passed to the event function.

A menu callback can also be installed via the NewMenuItem function, or from the Edit Menu Bar dialog box in the User Interface Editor.

### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuorMenuItemID	integer	The menu or menu item ID assigned in the User Interface Editor or returned by the NewMenu or NewMenuItem.
	eventFunction	MenuCallbackPtr	The name of the user function that processes the menu callback.
	callbackData	void *	A pointer to user-defined data that is passed to the event function.

## **Return Value**

<b>status</b> in	eger Refer to Appendix A for error co	odes.
------------------	---------------------------------------	-------

# **InstallMenuDimmerCallback**

int status = InstallMenuDimmerCallback (int menuBarHandle,

MenuDimmerCallbackPtr dimmerFunction):

# **Purpose**

This function installs a menu dimmer callback. It takes the handle of a menu bar and the name of the callback function.

A menu dimmer callback is called just before a pull-down menu appears when a menu bar is clicked or a menu short-cut key is pressed. The menu bar handle and the handle of the panel on which the menu bar resides is passed to the specified dimmer function for processing. This callback function is useful for checking a program's state and then dimming invalid menu items before the menu is displayed.

This callback function (type MenuDimmerCallbackPtr) takes the form:

void CVICALLBACK DimmerFunctionName (int menuBarHandle, int panelHandle);

The dimmer function is passed the menu bar handle and panel handle of the menu bar that has been accessed.

### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by
			LoadMenuBar or NewMenuBar.
	dimmerFunction	MenuDimmerCallbackPtr	The name of the user function that processes the menu dimmer callback.

#### Return Value

status integer Refer to Appendix A for error codes.
---

## InstallPanelCallback

# **Purpose**

This function installs a panel callback. It takes a panel handle, the name of the event function that processes events for that panel, and callback data of any type.

When an event is generated on the specified panel (after the callback is installed), the event function is called.

This event function (type PanelCallbackPtr) takes the form:

The event function is passed the panel handle of the panel generating the event, callback data defined by the user, the type of the event (such as a left mouse click), and any additional event data (such as the mouse position at the time of a left mouse click).

See Table 3-1 in Chapter 3, *Programming with the User Interface Library*, for the events and event data that can be processed by a panel callback. Also refer to the online help for the Event Function control on the InstallPanelCallback function panel.

A panel callback can also be installed from the Edit Panel window in the User Interface Editor.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	eventFunction	PanelCallbackPtr	The name of the user function that processes the panel callback.
	callbackData	void *	A pointer to user defined data that is passed to the event function.

#### Return Value

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# **InstallPopup**

int status = InstallPopup (int panelHandle);

# **Purpose**

Displays and activates a panel as a dialog box.

The user cannot operate any other panels while a pop-up panel is active.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in	
			memory. This handle will have been returned by the	
			LoadPanel, NewPanel, or DuplicatePanel	
			function.	

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **IsListItemChecked**

# **Purpose**

This function returns a Boolean value indicating whether or not a list item is checked.

This function only applies to list boxes with the check mode attribute set.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	itemIndex	integer	The zero-based index into the list control.	

Output	checked	integer	Returns a Boolean value indicating whether a list item	
		is checked.		
		0 = not checked		
			1 = checked.	

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# LoadMenuBar

## **Purpose**

Loads a menu bar into memory from a User Interface Resource (.uir) file that was created in the User Interface Editor. The menu bar will reside on the panel specified by the destination panel handle.

The function returns a menu bar handle which is used in subsequent function calls to specify the menu bar.

Note: The ATTR\_REPORT\_LOAD\_FAILURE and ATTR\_ALLOW\_MISSING\_CALLBACKS system attribute affect the behavior of this function when an error is encountered. See the SetSystemAttribute function.

#### **Parameters**

Input	destinationPanelHandle	integer	The handle for the panel on which the menu bar is to reside.
	filename	string	The name of the User Interface Resource file which contains the menu bar.
	menuBarResourceID	integer	The defined constant which was assigned to the menu bar in the User Interface Editor.

### **Return Value**

menuBarHandle	integer	The value you can use in subsequent function
		calls to specify this menu bar. Refer to
		Appendix A for error codes.

### **Parameter Discussion**

destinationPanelHandle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function. If the destination panel is not currently in memory, pass a zero as the destination panel handle and this menu bar can later be assigned to a panel using SetPanelMenuBar.

You can use a complete pathname or a simple filename with the **filename** parameter. If the name is a simple filename (in other words, contains no directory path) and is listed in the project, then the file is loaded using the pathname from the project. Otherwise, the file is loaded from the directory containing the project.

The **menuBarResourceID** can be found in the .uir header file and is used only once to load the menu bar into memory. Subsequent function calls will refer to the menu bar with the menu bar handle returned by this function.

### See also

LoadMenuBarEx, SetSystemAttribute

### LoadMenuBarEx

## **Purpose**

LoadMenuBarEx loads a menu bar into memory from a User Interface Resource (.uir) that was file created in the User Interface Editor. LoadMenuBarEx is similar to LoadMenuBar, except that, when you use LoadMenuBarEx on Windows 95 and NT, the callback functions you reference in your .uir file can be defined in the DLL that contains the call to LoadMenuBarEx. On platforms other than Windows 95 and NT, LoadMenuBarEx works exactly like LoadMenuBar.

Note: The ATTR\_REPORT\_LOAD\_FAILURE and ATTR\_ALLOW\_MISSING\_CALLBACKS system attribute affect the behavior of this function when an error is encountered. See the SetSystemAttribute function.

Input	destinationPanelHandle	integer	The handle of the panel on which the menu bar is to reside.
	filename	string	The name of the User Interface Resource File that contains the menu bar.

panelResourceID	integer	The defined constant assigned to the menu bar in the User Interface Editor.
callingModuleHandle	void pointer	Usually, the module handle of the calling DLL. You can useCVIUserHInst. Zero indicates the project or executable.

menuBarHandle	integer	The value you can use in subsequent function
		calls to specify this menu bar. Negative values indicate that an error occurred. Refer to Appendix A for error codes.

### **Using this Function**

Refer to the function help for LoadMenuBar for detailed information on that function. When you call LoadMenuBar, the User Interface Library attempts to find the callback functions referenced in the .uir file. It searches the symbols defined in the project or in object, library, or DLL import library modules that have been loaded using LoadExternalModule. It does not search symbols that are defined in a DLL but not exported in the DLL import library.

You may want a DLL to load a menu bar and link to callback functions defined in (but not exported from) the DLL. You can do this by calling LoadMenuBarEx. You must specify the module handle of the DLL in the **callingModuleHandle** parameter. You can do this by using the pre-defined variable \_\_\_CVIUserHInst. (If you pass zero for the **callingModuleHandle**, the function behaves identically to LoadMenuBar.)

LoadMenuBarEx first searches the DLL symbols to find the callback functions referenced in the .uir. If there are any callback functions that it cannot find, it then searches for them in the same manner as LoadMenuBar.

LoadMenuBarEx expects the DLL to contain a table of the callback functions referenced by the .uir files loaded by the DLL. If you create the DLL in LabWindows/CVI, the table is included automatically. If you create the DLL using an external compiler, you must arrange for this table to be included in the DLL. You can do this by using the **External Compiler Support** command in the **Build** menu of the Project window. You must have a LabWindows/CVI project that lists all of the .uir files loaded by the DLL. In the External Compiler Support dialog box, specify the name of an object file to contain the table of callback function names. Then click on the **Create** button to create the object file. You must include the object file in the external compiler project you use to create the DLL.

The External Compiler Support information is contained in the LabWindows/CVI project file. If that project file is loaded and you modify and save any of the .uir files, LabWindows/CVI automatically regenerates the object file.

#### See also

LoadMenuBar, LoadPanelEx, SetSystemAttribute

# LoadPanel

## **Purpose**

Loads a panel into memory from a User Interface Resource (.uir) file created in the User Interface Editor.

The panel will be a child panel of the parent panel specified by **parentPanelHandle**. To make the panel a top-level panel, enter 0 for the **parentPanelHandle**. The loaded panel can then be displayed with the DisplayPanel function.

The function returns a panel handle which is used in subsequent function calls to specify the panel.

Note: The ATTR\_REPORT\_LOAD\_FAILURE and ATTR\_ALLOW\_MISSING\_CALLBACKS system attribute affect the behavior of this function when an error is encountered. See the SetSystemAttribute function.

#### **Parameters**

Input	parentPanelHandle	integer	The handle of the panel into which the panel is loaded as a child panel. Pass 0 to load the panel as a top-level window.
	filename	string	The name of the User Interface Resource file which contains the panel.
	panelResourceID	integer	The defined constant which was assigned to the panel in the User Interface Editor.

# **Return Value**

panelHandle	 The value you can use in subsequent function calls to specify this panel. Negative values
	indicate that an error occurred. Refer to Appendix A for error codes.

## **Parameter Discussion**

To make the panel a top-level panel, enter 0 for **parentPanelHandle**. If the panel is being loaded from a LabWindows for DOS .uir file, use the Return Value from the function DOSCompatWindow as the **parentPanelHandle**.

You can use a complete pathname or a simple filename for **filename**. If the name is a simple filename (in other words, contains no directory path) and is listed in the project, then the file is loaded using the pathname from the project. Otherwise, the file is loaded from the directory containing the project.

The **panelResourceID** can be found in the .uir header file and is used only once to load the panel into memory. Subsequent function calls refer to this panel with the **panelHandle** returned by this function.

#### See also

LoadPanelEx, SetSystemAttribute

## LoadPanelEx

# **Purpose**

LoadPanelEx loads a panel into memory from a User Interface Resource (.uir) file created in the User Interface Editor. LoadPanelEx is similar to LoadPanel, except that, when you use LoadPanelEx your program on Windows 95 and NT, the callback functions you reference in your .uir file can be defined in the DLL that contains the call to LoadPanelEx. On platforms other than Windows 95 and NT, LoadPanelEx works exactly like LoadPanel.

Note: The ATTR\_REPORT\_LOAD\_FAILURE and ATTR\_ALLOW\_MISSING\_CALLBACKS system attribute affect the behavior of this function when an error is encountered. See the SetSystemAttribute function.

Input	parentPanelHandle integ		The handle of the panel into which the panel is loaded as a child panel. Pass 0 to load the panel as a top-level window.
	filename	string	The name of the User Interface Resource File that contains the panel.
	panelResourceID	integer	The defined constant assigned to the panel in the User Interface Editor.

callingModuleHandle	void pointer	Usually, the module handle of the calling DLL. You can useCVIUserHInst. Zero
		indicates the project or executable.

panelHandle	integer	The value you can use in subsequent function
		calls to specify this panel. Negative values indicate that an error occurred. Refer to Appendix A for error codes.

### **Using this Function**

Refer to the function help for LoadPanel for detailed information on that function.

When you call LoadPanel, the User Interface Library attempts to find the callback functions referenced in the .uir file. It searches the symbols defined in the project or in object, library, or DLL import library modules that have been loaded using LoadExternalModule. It does not search symbols that are defined in a DLL but not exported in the DLL import library.

You may want a DLL to load a panel and link to callback functions defined in (but not exported from) the DLL. You can do this by calling LoadPanelEx. You must specify the module handle of the DLL in the **callingModuleHandle** parameter. You can do this by using the predefined variable \_\_CVIUserHInst. (If you pass zero for the **callingModuleHandle**, the function behaves identically to LoadPanel.)

LoadPanelEx first searches the DLL symbols to find the callback functions referenced in the .uir. If there are any callback functions that it cannot find, it then searches for them in the same manner as LoadPanel.

LoadPanelEx expects the DLL to contain a table of the callback functions referenced by the .uir files loaded by the DLL. If you create the DLL in LabWindows/CVI, the table is included automatically. If you create the DLL using an external compiler, you must arrange for this table to be included in the DLL. You can do this by using the **External Compiler Support** command in the **Build** menu of the Project window. You must have a LabWindows/CVI project that lists all of the .uir files loaded by the DLL. In the External Compiler Support dialog box, specify the name of an object file to contain the table of callback function names. Then click on the **Create** button to create the object file. You must include the object file in the external compiler project you use to create the DLL.

The External Compiler Support information is contained in the LabWindows/CVI project file. If that project file is loaded and you modify and save any of the .uir files, LabWindows/CVI automatically regenerates the object file.

#### See also

LoadPanel, LoadMenuBarEx, SetSystemAttribute

## MakeColor

int rgb = MakeColor (int red, int green, int blue);

# **Purpose**

Generates a color (RGB) value from the individual constituent red, green, and blue intensity levels.

An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. The first sixteen colors listed are the sixteen standard colors.

### Predefined RGB Values:

```
0xFF0000L = VAL_RED
0 \times 00 FF00L = VAL_GREEN
0 \times 0000 FFL = VAL BLUE
0 \times 00 FFFFL = VAL_CYAN
0xFF00FFL = VAL MAGENTA
0xffff00L = VAL_YELLOW
0x800000L = VAL_DK_RED
0 \times 000080L = VAL_DK_BLUE
0 \times 008000L = VAL DK GREEN
0 \times 008080L = VAL_DK_CYAN
0x800080L = VAL DK MAGENTA
0x808000L = VAL_DK_YELLOW
0xCCCCCCL = VAL_LT_GRAY
0x808080L = VAL DK GRAY
0 \times 000000L = VAL_BLACK
0xffffffL = VAL_WHITE
0 \times A 0 A 0 A 0 L = VAL_GRAY
0xE5E5E5L = VAL_OFFWHITE
VAL PANEL GRAY = VAL LT GRAY
```

Input	red	integer	The red level of the new color. Any integer value between 0 and 255 is valid.  0 = No red component.  255 = Maximum red component.
	green	integer	The green level of the new color. Any integer value between 0 and 255 is valid.  0 = No green component.  255 = Maximum green component.

blue	_	The blue level of the new color. Any integer value between 0 and 255 is valid.
		0 = No blue component. 255 = Maximum blue component.

rgb	_	Return Value indicating the RGB value. Refer to Appendix A for error codes.
-----	---	---

# **MakePoint**

Point point = MakePoint (int xCoordinate, int yCoordinate);

# **Purpose**

Returns a Point structure with the specified values. The Point structure defines the location of a point.

This function is useful when calling canvas control functions that require Point structures as input parameters. You can embed a call to MakePoint in calls to these functions, thereby eliminating the need to declare a Point variable.

### **Parameters**

Input	<b>xCoordinate</b> integer		The horizontal location of the point.
	yCoordinate	integer	The vertical location of the point.

## **Return Value**

point	Point	A Point structure containing the specified coordinate
		values.

## See Also

PointSet, MakeRect

# MakeRect

Rect rect = MakeRect (int top, int left, int height, int width);

# **Purpose**

Returns a Rect structure with the specified values. The Rect structure defines the location and size of a rectangle.

This function is useful when calling canvas control functions that require Rect structures as input parameters. You can embed a call to MakeRect in calls to these functions, thereby eliminating the need to declare a Rect variable.

### **Parameters**

Input	top	integer	The location of the top edge of the rectangle.
	left	integer	The location of the left edge of the rectangle.
	height	integer	The height of the rectangle.
	width	integer	The width of the rectangle.

### **Return Value**

rect	Rect	A Rect structure containing the specified coordinate values.
------	------	--

### See Also

RectSet, MakePoint

# MessagePopup

int status = MessagePopup (char title[], char message[]);

## **Purpose**

Displays a message in a dialog box and waits for the user to select the **OK** button.

Input	title	string	The title to be displayed on the dialog box.
-------	-------	--------	--

	message	string	The message to be displayed in the dialog box. To
			display a multi-line message, embed newline characters
			(\n) in the message string.

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# MultiFileSelectPopup

allowCancel,
int numberofSelectedFiles, char \*\*fileList);

# **Purpose**

Displays a file-selection dialog box and waits for the user to select a file or cancel.

	1	T	<u> </u>
Input	defaultDirectory	string	The initial directory. If " " is entered, then the current working directory will be used.
	defaultFileSpec	string	A string that specifies which files to display. For example, "*.c" would cause all files with the extension .c to be displayed.
	fileTypeList	string	A list of file types, separated by semicolons, to be contained in the File Type List of the File Select Pop-up when <b>restrictExtension</b> is FALSE. For example, "*.c;*.h" allows the user to select "*.c" or "*.h" from the File Type List. ("*.*" is always available).
	title	string	The title of the dialog box.
	restrictDirectory	integer	If non-zero, the user cannot change directories or drives. If zero, the user can change directories or drives.
	restrictExtension	integer	If non-zero, the user is limited to files with the default extension. If zero, the user can select files with any extension.
	allowCancel	integer	If non-zero, the user can cancel out of the File Select Popup. If zero, the user can leave the popup only by making a selection.
Output	numberofSelectedFiles	integer	The number of files selected by the user.
	fileList	array of strings	The buffer in which the user's selection is returned. The buffer is automatically allocated by MultiFileSelectPopup and is accessible as an array of strings.

status	integer	Refer to Appendix A for error codes.
	_	

#### **Return Codes**

0	VAL_NO_FILE_SELECTED
1	VAL_EXISTING_FILE_SELECTED

### **Parameter Discussion**

The **defaultFileSpec** is shown in the file name control when the pop-up is first displayed. If you specify an actual file name, such as test.c, that name appears in the file name box and also in the file list box. The **defaultFileSpec** cannot contain a directory path.

**fileList** is allocated dynamically, as is each string. When they are no longer needed, your program should free each string, and then free the array using the free function.

# NewBitmap

## **Purpose**

Creates a bitmap object. The bitmap ID can then be passed any function that accepts a bitmap, such as CanvasDrawBitmap or ClipboardPutBitmap.

You can discard the bitmap object by passing its ID to DiscardBitmap.

Input	bytesPerRow	integer	The number of bytes on each scan line of the image.	
	pixelDepth	integer	The number of bits per pixel.	
	width	integer	The width of the image, in pixels.	
	height	integer	The height of the image, in pixels.	
	colorTable	integer array	An array of RGB color values, or NULL if <b>pixelDepth</b> is greater than 8.	
	bits	unsigned char array	An array of bits that determine the colors to be displayed on each pixel in the image.	
	mask	unsigned char array	An array containing one bit per pixel in the image. Each bit specifies whether the pixel is actually drawn. May be NULL.	
Output	bitmapID	integer	An ID that serves as a handle to the bitmap object.	

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

Depending on the **pixelDepth** and **width**, the number of bits per line in the **bits** array might not be an even multiple of 8. If not, then the extra bits needed to get to the next byte boundary are considered "padding". If you set **bytesPerRow** to be a positive number, then the bits for each scan line must start on a byte boundary, and so padding may be required. In fact, you can set **bytesPerRow** to be larger than the minimum number of bytes actually needed. The extra bytes are also considered padding. If you pass -1, there is no padding at all. The bits for each scan line immediately follow the bits for the previous scan line.

The valid values for **pixelDepth** are 1, 4, 8, 24, and 32.

If the **pixelDepth** is 8 or less, the number of entries in the **colorTable** array must equal 2 raised to the power of the **pixelDepth** parameter. The **bits** array contain indices into the **colorTable** array. If the **pixelDepth** is greater than 8, the **colorTable** parameter is not used. Instead the **bits** array contains actual RGB color values, rather than indices into the **colorTable** array.

For a **pixelDepth** of 24, each pixel is represented by a 3-byte RGB value of the form 0xRRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte should always be at the lowest memory address of the three bytes.

If the **pixelDepth** is 32, each pixel in the **bits** array is represented by a 32-bit RGB value of the form 0x00RRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the

color. The 32-bit value is treated as a native 32-bit integer value for the platform. The most significant byte is always ignored. The BB byte should always be in the least significant byte. On a little-endian platform (for example, Intel processors), BB would be at the lowest memory address. On a big-endian platform (for example, Motorola processors), BB would be at the highest address. Note that this differs from the format of the bits array when the **pixelDepth** is 24.

In the **mask** array, a bit value of 1 indicates that the pixel is drawn. 0 indicates that the pixel is not drawn. Exception: If an image has a **pixelDepth** of 1, pixels with a **bits** value of 1 (foreground pixels) are always drawn and the **mask** affects only the pixels with a bitmap of 0 (background pixels). Each row of the mask must be padded to the nearest even-byte boundary. For example, if the width of the image is 21 pixels, then there must be 32 bits (in other words, 4 bytes) of data in each row of the mask.

A mask is useful for achieving transparency.

You may pass NULL if you do not need a mask.

#### See Also

GetBitmapFromFile, GetCtrlBitmap, GetCtrlDisplayBitmap, GetPanelDisplayBitmap, ClipboardGetBitmap, ClipboardPutBitmap, GetBitmapData, SetCtrlBitmap, PlotBitmap, CanvasDrawBitmap, DiscardBitmap.

### **NewCtrl**

### **Purpose**

This function creates a new control and returns a control ID used to specify the control in subsequent function calls.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlStyle	integer	See Table 3-10 in Chapter 3 for a complete listing of al control styles.	
	controlLabel	string	The label of the new control. Pass "" or 0 for no label.	
	controlTop	integer	The vertical coordinate at which the upper left corner of the control (not including labels) is placed.	
	controlLeft	integer	The horizontal coordinate at which the upper left corner of the control (not including labels) is placed.	

### **Return Value**

controlID	integer	Returns the ID used to specify this control in
	subsequent function calls. Negative values indicate	
		an error occurred. Refer to Appendix A for error codes.

### **Parameter Discussion**

**controlTop** and **controlLeft** coordinates must be integer values from -32768 to 32767. The origin (0,0) is at the upper-left corner of the panel (directly below the title bar) before the panel is scrolled.

# NewMenu

## **Purpose**

This function adds a new menu to the specified menu bar and returns a Menu ID to be used to specify the menu in subsequent function calls.

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuName	string	The new menu name that is added to the menu bar.
	beforeMenuID	integer	The new menu will be inserted before this menu. To place the new menu at the end of the menu bar, enter -1 for the <b>beforeMenuID</b> .

### **Return Value**

status	integer	The ID which will be used to reference this menu in
		subsequent function calls. Negative values indicate that
		an error occurred. Refer to Appendix A for error codes.

# NewMenuBar

int menuBarHandle = NewMenuBar (int destinationPanelHandle);

## Purpose

This function creates a new menu bar to reside on the specified destination panel and returns the new menu bar handle.

The new menu bar handle is used in subsequent function calls to specify this menu bar.

### **Parameters**

Input	destinationPanelHandle	integer	The handle for the panel on which the menu bar
			is to reside.

## **Return Value**

menuBarHandle	integer	Used in subsequent function calls to specify the
		menu bar. Refer to Appendix A for error codes.

## **Parameter Discussion**

If the destination panel is not currently in the memory, pass a zero as the **destinationPanelHandle** and this menu bar can later be assigned to a panel using SetPanelMenuBar.

## NewMenuItem

# **Purpose**

This function adds a new menu item to the specified menu and returns the **MenuItemID** to be used in subsequent calls to specify the menu item.

	1	ī	1
Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar
	menuID	integer	The ID for a particular menu within a menu bar. The Menu ID should be a constant name (located in the .uir header file) generated by the User Interface Editor or a value returned by the NewMenu function.
	itemName	string	The name of the new menu item.
	beforeMenuItemID	integer	The new menu item will be inserted before (above) this menu item. To place the new menu item at the end (bottom) of the menu item list, enter -1 for the <b>beforeMenuItemID.</b>
	shortCutKey	integer	Specifies the key used to automatically select the menu item.
	eventFunction	MenuCallbackPtr	The name of the user function that process the menu item callback.
	callbackData	void *	If you process the menu item event through a callback function, you can supply a pointer to user-defined data in this control. If you do not need to pass user-defined data to the callback function, or if you are not using a callback function to process the menu item event, supply a value of zero.

menuItemID	integer	Returns the ID which will be used to
		specify this menu item in subsequent
		function calls. Negative values indicate
		that an error occurred. Refer to
		Appendix A for error codes.

#### **Parameter Discussion**

Valid Shortcut Keys:

Shortcut keys are 4-byte integers consisting of three bit fields, 0x00MMVVAA, where:

MM =the modifier key

 $\nabla V =$ the virtual key

AA =the ASCII key

When a shortcut key is constructed, modifier keys are bit-wise OR'ed with a virtual key or an ASCII key. Code for either the ASCII field or the virtual key field will be all zeros.

#### For example:

```
VAL_SHIFT_MODIFIER | VAL_F1_VKEY produces a shortcut key of <Shift-F1>, and
```

VAL MENUKEY MODIFIER | 'D'

produces a shortcut key of <Ctrl-D> on the PC and <meta-D> on the SPARCstation. Virtual keys do not require modifiers but ASCII keys require at least one modifier.

## The modifier keys are:

```
VAL_SHIFT_MODIFIER

VAL_MENUKEY_MODIFIER (the <Ctrl> key)

VAL_SHIFT_AND_MENUKEY
```

## The virtual keys are:

```
VAL_FWD_DELETE_VKEY (not available on the SPARCstation)

VAL_BACKSPACE_VKEY (<Del> on the SPARCstation)

VAL_ESC_VKEY

VAL_TAB_VKEY

VAL_ENTER_VKEY

VAL_UP_ARROW_VKEY

VAL_DOWN_ARROW_VKEY

VAL_LEFT_ARROW_VKEY
```

```
VAL_RIGHT_ARROW_VKEY
VAL INSERT VKEY
VAL_HOME_VKEY
VAL_END_VKEY
VAL_PAGE_UP_VKEY
VAL_PAGE_DOWN_VKEY
VAL F1 VKEY
VAL_F2_VKEY
VAL_F3_VKEY
VAL F4 VKEY
VAL F5 VKEY
VAL_F6_VKEY
VAL_F7_VKEY
VAL_F8_VKEY
VAL_F9_VKEY
VAL_F10_VKEY
VAL_F11_VKEY
VAL_F12_VKEY
The possible ASCII keys are:
'A' or 'a'
'B' or 'b'
'C' or 'c'
```

### eventFunction

'Z' or 'z'

If you want to process the menu item event through a callback function, supply the name of that function as this parameter. This event function (type MenuCallbackPtr) should be prototyped as follows:

```
void CVICALLBACK EventFunctionName (int menuBarHandle, int menuItemID, void *callbackData, int panelHandle);
```

The event function is passed the menu bar handle, **menuItemID**, and panel handle of the menu bar generating the callback. Callback data defined by the user is also passed to the event function.

If you do not want to process the menu item event through a callback function, supply a value of zero (0) as this parameter.

## **NewPanel**

# **Purpose**

This function creates a new child panel inside the specified parent panel and returns the new panel handle.

To make the panel a top-level panel, enter 0 for the parent panel handle.

The new panel handle is used in subsequent function calls to specify this panel.

#### **Parameters**

Input	parentPanelHandle	integer	The handle of the panel into which the new child panel is loaded. To make the panel a top-level panel, enter 0.
	panelTitle	string	The title for the new panel.
	panelTop	integer	The vertical coordinate at which the upper left corner of the panel (directly below the title bar) is placed.
	panelLeft	integer	The horizontal coordinate at which the upper left corner of the panel (directly below the title bar) is placed.
	panelHeight	integer	The vertical size of the new panel. The height of the panel does not include the title bar or panel frame.
	panelWidth	integer	Size of the new panel in window coordinates. The width of the panel does not include the panel frame.

#### **Return Value**

panelHandle	Returns a panel handle to be used in subsequent function calls to reference the panel. Refer to
	Appendix A for error codes.

### **Parameter Discussion**

The **panelTop** and **panelLeft** coordinates must be integer values from -32768 to 32767, or VAL\_AUTO\_CENTER to center the panel. For a top-level panel, (0,0) is the upper-left corner of

the screen. For a child panel, (0,0) is the upper-left corner of the parent panel (directly below the title bar) before the parent panel is scrolled. **panelHeight** and **panelWidth** must be integer values from 0 to 32767.

## **NewSubMenu**

int subMenuID = NewSubMenu (int menuBarHandle, int menuItemID);

## **Purpose**

This function creates a submenu for a specified menu item and returns a **subMenuID** to specify the submenu in subsequent function calls.

A submenu appears as a triangle on the right side of the menu item.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar
	menuItemID	integer	This is the menu item on which the submenu is to be attached. The Menu Item ID will have been a constant name supplied in the User Interface Editor or a value returned by the NewMenuItem function.

#### Return Value

subMenuID	The ID which will be used to specify this submenu in
	subsequent function calls. Negative values indicate that
	an error occurred. Refer to Appendix A for error codes.

## **PlotArc**

## **Purpose**

Plots an arc into a graph control.

The arc is defined by specifying two opposing corners of a rectangle that enclose the arc, along with a beginning angle (in tenths of degrees) and an arc angle (in tenths of degrees).

For example, if X1=0.0, Y1=0.0, X2=200.0, Y2=200.0, Beg Angle=0, and Arc Angle=3600, then a circle centered on coordinates (100.0,100.0) would be plotted on the graph.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	x1	double- precision	The horizontal coordinate of one corner of the rectangle that encloses the arc.
	y1	double- precision	The vertical coordinate of one corner of the rectangle that encloses the arc.
	x2	double- precision	The horizontal coordinate of the opposing corner of the rectangle that encloses the arc.
	y2	double- precision	The vertical coordinate of the opposing corner of the rectangle that encloses the arc.
	beginAngle	integer	The starting angle of the arc, in tenths of degrees.  Positive angles proceed counter-clockwise and negative angles proceed clockwise, from 0 to 3600.
	arcAngle	integer	The sweep angle of the arc, in tenths of degrees. Positive angles proceed counter-clockwise and negative angles proceed clockwise, from 0 to 3600.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.
	fillColor	integer	Specifies the fill color of the figure.

plotHandle	integer	The handle for the plot. This handle can be passed to
		DeleteGraphPlot to delete the individual plot.
		Refer to Appendix A for error codes. It can also be
		passed to SetPlotAttribute and
		GetPlotAttribute

# **PlotBitmap**

## **Purpose**

Plots a bitmapped image into a graph control.

The origin of the image is expressed in terms of the X and Y coordinates of the graph. It pinpoints the lower left corner of the image.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	x	double- precision	The x-coordinate of the lower left corner of the bitmapped image.
	У	double- precision	The y-coordinate of the lower left corner of the bitmapped image.
	width	double- precision	The width, in graph units, of the area in which to fit the bitmapped image. If zero, then the width is the width of the image. If nonzero, the image is stretched or shrunk to fit.
	height	double- precision	The height, in graph units. of the area in which to fit the bitmapped image. If zero, then the height is the height of the image. If nonzero, the image is stretched or shrunk to fit.
	fileName	string	The name of the file which contains the image.

plotHandle	integer	The handle for the plot. This handle can be passed to
		SetImageBits, GetImageBits,
		SetPlotAttribute, GetPlotAttribute, or
		DeleteGraphPlot. Refer to Appendix A for error
		codes.

#### **Parameter Discussion**

**fileName** can be a complete pathname or a simple filename. If it is a simple filename (in other words, contains no directory path):

- If the file is listed in the project, then the file is loaded using the pathname from the project.
- Otherwise, the file is loaded from the directory containing the project.

The valid image types appear in the following list.

PCX: Windows and UNIX

BMP, DIB, RLE, ICO: Windows only

WMF: Windows 95 and NT only

XWD: UNIX only

**fileName** may be NULL or the empty string. This is useful when you want to define the image programmatically by calling SetCtrlBitmap using the **PlotHandle** returned by this function. The plot is not visible until a valid image is specified.

#### See Also

SetPlotAttribute, GetPlotAttribute

# **PlotIntensity**

### **Purpose**

This function draws a solid rectangular plot in a graph control. If you want to apply scaling factors and offsets to the data values, see the PlotScaledIntensity function.

The plot consists of pixels whose colors correspond to the magnitude of data values in a two-dimensional array and whose coordinates correspond to the locations of the data values in the array. For instance, the pixel associated with zArray[2][3] is located at  $\{x=3, y=2\}$ .

The size of the lower left corner of the plot area is at  $\{0, 0\}$ .

The upper right corner of the plot area is at {X-1, Y-1}, where,

X = Number of X Points

Y = Number of Y Points

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID		The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	zArray	numeric array	An array that contains the data values that are to be converted to colors.
	numberOfXPoints	integer	The number of points to be displayed along the x-axis in each row.
	numberOfYPoints	integer	The number of points to be displayed along the y-axis in each column.
	zDataType	integer	Specifies the data type of the elements in <b>zArray</b> , as well as the data type of the Color Map values.
	colorMapArray	ColorMap Entry	An array of ColorMapEntry structures which specifies how the data values in <b>zArray</b> are translated into colors. The maximum number of entries is 255.
	hiColor	integer	The RGB value to which all <b>zArray</b> values that are higher than the highest data value in <b>colorMapArray</b> are translated.
	numberOfColors	integer	The number of entries in <b>colorMapArray</b> . Must be less than or equal to 255.
	interpColors	integer	Indicates how to assign colors to <b>zArray</b> data values that do not exactly match the data values in the <b>colorMapArray</b> .
	interpPixels	integer	Indicates how pixels between the pixels assigned to the <b>zArray</b> values are colored.

plotHandle	integer	The handle for the plot. This handle can be passed to
		SetPlotAttribute, GetPlotAttribute, or
		DeleteGraphPlot. Refer to Appendix A for
		error codes.

### **Parameter Discussion**

**zArray** must be one of the following data types (specified in **zDataType**):

```
VAL_DOUBLE
VAL_FLOAT
VAL_INTEGER
VAL_SHORT_INTEGER
VAL_CHAR
VAL_UNSIGNED_INTEGER
VAL_UNSIGNED_SHORT_INTEGER
VAL_UNSIGNED_CHAR
```

The locations at which the colors are shown on the graph depend on the location of the data values in **zArray**.

• **zArray** should be a two dimensional array of the following form.

```
zArray[numberOfYPoints][numberOfXPoints]
```

• Each element of the array is associated with a pixel on the graph. The pixel associated with element zArray[y][x] is located at  $\{x, y\}$  on the graph.

colorMapArray contains up to 255 ColorMapEntry structures, which consist of:

```
union {
   char valChar;
   int valInt;
   short valShort;
   float valFloat;
   double valDouble;
   unsigned char valUChar;
   unsigned long valULong;
   unsigned short valUShort;
} dataValue;
int color; /* RGB value */
```

The Color Map array defines how data values in **zArray** are translated into color values. If a data value matches exactly to a data value in one of the ColorMapEntry structures, then it is converted to the corresponding color. Otherwise, the following conditions apply.

- If **interpColors** is zero, the color associated with the next higher data value is used.
- If **interpColors** is nonzero, the color is computed using a weighted mean of the colors associated with the Color Map data values immediately above and below the **zArray** value.

- Regardless of the value of **interpColors**, the following conditions apply.
  - Data values below the lowest Color Map data value are assigned the color of the lowest Color Map data value.
  - Data values above the highest Color Map data value are assigned the value of the hiColor parameter.

If **interpColors** is nonzero, the **numberOfColors** must be greater than or equal to 2.

The **colorMap** entries do not need to be in sorted order.

**interpPixels** indicates how pixels between the pixels assigned to the **zArray** values are colored. If **interpPixels** is zero, an unassigned pixel is given the same color as the closest assigned pixel. If **interpPixels** is nonzero, an unassigned pixel is first given a data value using a weighted mean of the data values associated with the four closest assigned pixels. Then the color is calculated using the **colorMap**.

#### **Performance Considerations**

If **interpPixels** is zero, the performance degrades as the number of data points in **zArray** increases.

If **interpPixels** is nonzero, the performance degrades as total number of pixels in the plot area increases.

#### See Also

PlotScaledIntensity

## **PlotLine**

#### **Purpose**

Plots a line into a graph control.

The starting and ending points of the line are specified in terms of X and Y coordinates of the graph.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	x1	double- precision	The horizontal coordinate of the starting point of the line.
	y1	double- precision	The vertical coordinate of the starting point of the line.
	x2	double- precision	The horizontal coordinate of the ending point of the line.
	y2	double- precision	The vertical coordinate of the ending point of the line.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

## **Return Value**

plotHandle integer		The handle for the plot. This handle can be passed to
		DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and GetPlotAttribute.

# **PlotOval**

## **Purpose**

Plots a oval into a graph control.

The oval is defined by specifying two opposing corners of a rectangle that enclose the oval in terms of X and Y coordinates of the graph.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	x1	double- precision	The horizontal coordinate of one corner of the rectangle that encloses the oval.
	y1	double- precision	The vertical coordinate of one corner of the rectangle that encloses the oval.
	x2	double- precision	The horizontal coordinate of the opposing corner of the rectangle that encloses the oval.
	y2	double- precision	The vertical coordinate of the opposing corner of the rectangle that encloses the oval.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.
	fillColor	integer	Specifies the fill color of the figure.

## **Return Value**

passed to SetPlotAttribute and GetPlotAttribute.
--

# **PlotPoint**

# **Purpose**

Plots a point into a graph control.

The position of the point is specified in terms of X and Y coordinates of the graph.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	xCoordinate	double- precision	The horizontal position at which to plot the point.
	yCoordinate	double- precision	The vertical coordinate at which to plot the point.
	pointStyle	integer	The point style to be used when plotting the array.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

## **Return Value**

plotHandle	integer	The handle for the plot. This handle can be passed to DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and GetPlotAttribute.
------------	---------	---

# **PlotPolygon**

# Purpose

Plots a polygon into a graph control.

The polygon is defined by a set of connected X-Y points. The last point is automatically connected to the first point to close the polygon.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	xArray	void *	The array that contains the values to be plotted along the X axis. The data type must be of the type specified by <b>xDataType.</b>
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	pointsInPolygon	integer	The number of connected points (corners) in the polygon. There must be at least three corners. <b>pointsInPolygon</b> controls the number of corners plotted, even if the number of elements in the X and Y Arrays are greater than the value of <b>pointsInPolygon</b> .
	xDataType	integer	Specifies the data type of the X array. See Table 3-11 in Chapter 3 for a list of data types.
	yDataType	integer	Specifies the data type of the Y array. See Table 3-11 in Chapter 3 for a list of data types.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.
	fillColor	integer	Specifies the fill color of the figure.

## **Return Value**

plotHandle	integer	The handle for the plot. This handle can be passed to
		DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and GetPlotAttribute

# **PlotRectangle**

# **Purpose**

Plots a rectangle into a graph control.

Two opposing corners of the rectangle are specified in terms of X and Y coordinates of the graph.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	x1	double- precision	The horizontal coordinate of one corner of the rectangle.
	y1	double- precision	The vertical coordinate of one corner of the rectangle
	x2	double- precision	The horizontal coordinate of the opposing corner of the rectangle.
	y2	double- precision	The vertical coordinate of the opposing corner of the rectangle.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.
	fillColor	integer	Specifies the fill color of the figure.

plotHandle	integer	The handle for the plot. This handle can be passed to DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and GetPlotAttribute.
------------	---------	---

# **PlotScaledIntensity**

## **Purpose**

This function draws a solid rectangular plot in a graph control. It is the same as PlotIntensity, except that you can apply scaling factors and offsets to the data values.

The plot consists of pixels whose colors correspond to the magnitude of data values in a two-dimensional array and whose coordinates correspond to the locations of the same data values in the array, scaled by **xGain** and **yGain** and offset by **xOffset** and **yOffset**. For instance the pixel associated with **zArray**[2][3] is located at the following coordinates.

```
{x = 3*xGain + xOffset, y = 2*yGain + yOffset}.
```

The lower left corner of the plot area is located at

```
{xOffset, yOffset}.
```

The upper right corner of the plot area is located at

```
\{(X-1)*xGain + xOffset, (Y-1)*yGain + yOffset\},\
```

where

X = Number of X Points

Y = Number of Y Points

_			
Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID inte		The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	zArray	numeric array	An array that contains the data values that are to be converted to colors.
	numberOfXPoints	integer	The number of points to be displayed along the x-axis in each row.
	numberOfYPoints	integer	The number of points to be displayed along the yaxis in each column.
	zDataType		Specifies the data type of the elements in <b>zArray</b> , as well as the data type of the Color Map values.
	yGain	double- precision	Specifies the scaling factor to be applied to the vertical locations implied by <b>zArray</b> vertical index values.
	yOffset	double- precision	Specifies the offset to be added to the vertical locations implied by <b>zArray</b> vertical index values.
	xGain	double- precision	Specifies the scaling factor to be applied to the horizontal locations implied by <b>zArray</b> horizontal index values.
	xOffset	double- precision	Specifies the offset to be added to the horizontal locations implied by <b>zArray</b> horizontal index values.
	colorMapArray	ColorMap Entry	An array of ColorMapEntry structures which specifies how the data values in <b>zArray</b> are translated. The maximum number of entries is 255.
	hiColor	integer	The RGB value to which all <b>zArray</b> values that are higher than the highest data value in <b>colorMapArray</b> are translated.
	numberOfColors	integer	The number of entries in <b>colorMapArray</b> . Must be less than or equal to 255.
	interpColors	integer	Indicates how to assign colors to <b>zArray</b> data values that do not exactly match the data values in the <b>colorMapArray</b> .
	interpPixels	integer	Indicates how pixels between the pixels assigned to the <b>zArray</b> values are colored.

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

**zArray** must be one of the following data types (specified in **zDataType**).

```
VAL_DOUBLE
VAL_FLOAT
VAL_INTEGER
VAL_SHORT_INTEGER
VAL_CHAR
VAL_UNSIGNED_INTEGER
VAL_UNSIGNED_SHORT_INTEGER
VAL_UNSIGNED_SHORT_INTEGER
VAL_UNSIGNED_CHAR
```

The locations at which the colors are shown on the graph depend on that location of the data values in **zArray**.

• **zArray** should be a two-dimensional array of the following form.

```
zArray[numberOfYPoints][numberOfXPoints]
```

• Each element of the array is associated with a pixel on the graph. The pixel associated with element **zArray**[y][x] is located at {x \* xGain + xOffset, y \* yGain + yOffset} on the graph.

colorMapArray contains up to 255 ColorMapEntry structures, which consist of:

```
union {
   char valChar;
   int valInt;
   short valShort;
   float valFloat;
   double valDouble;
   unsigned char valUChar;
   unsigned long valULong;
   unsigned short valUShort;
} data Value;
int color;  /* RGB value */
```

The Color Map array defines how data values in **zArray** are translated into color values. If a data value matches exactly to a data value in one of the ColorMapEntry structures, then it is converted to the corresponding color. Otherwise, the following conditions apply.

- If **interpColors** is zero, the color associated with the next higher data value is used.
- If **interpColors** is nonzero, the color is computed using a weighted mean of the colors associated with the Color Map data values immediately above and below the **zArray** value.
- Regardless of the value of **interpColors**, the following conditions apply.

- Data below the lowest Color Map data value are assigned the color of the lowest Color Map data value.
- Data values above the highest Color Map data value are assigned the value of the hiColor parameter.

If **interpColors** is nonzero, the **numberOfColors** must be greater than or equal to 2.

The **colorMapArray** entries do not need to be in sorted order.

**interpPixels** indicates how pixels between the pixels assigned to the **zArray** values are colored. If **interpPixels** is zero, an unassigned pixel is given the same color as the closest assigned pixel. If **interpPixels** is nonzero, an unassigned pixel is first given a data value using a weighted mean of the data values associated with the four closest assigned pixels. Then the color is calculated using the Color Map.

#### **Performance Considerations**

If **interpPixels** is zero, the performance depends on the number of data points in **zArray**.

If **interpPixels** is nonzero, the performance depends on the total number of pixels in the plot area.

# **PlotStripChart**

### **Purpose**

Adds one or more points to each trace in a strip chart control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	numberofPoints	integer	The number of <b>yArray</b> points to add to the strip chart.  This value must be an even multiple of the number traces in the strip chart. This value controls the number of points to plot even if the number of elements in <b>yArray</b> is greater than the <b>numberofPoints</b> .
	startingIndex	integer	The index of the element in the <b>yArray</b> where the first block of data begins. This value is zero-based and must be an even multiple of the number of traces in the strip chart. The default value is 0.
	skipCount	integer	The number of <b>yArray</b> elements to skip over (increment) after each set of points is plotted. The default is 0.
	yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## **Parameter Discussion**

### numberofPoints

The right edge of the strip chart is considered a grid line. The **Points per Screen** attribute of the strip chart encompasses this grid line at the right edge of the strip chart. To synchronize your data with the grid lines, you should set the strip chart **Points per Screen** attribute to one greater than the datapoints per screen, in other words,

strip chart Points per Screen = datapoints per screen + 1.

You can set the **Points per Screen** attribute of the strip chart in the User Interface Editor or you can use SetCtrlAttribute function with the ATTR\_POINTS\_PER\_SCREEN attribute.

The datapoints per screen is controlled by the **number of Points** parameter of PlotStripChart.

For Continuous mode strip charts, if you do not follow this algorithm, you will notice the grid lines drifting away from your datapoints.

For Sweep & Block mode, if you do not follow this algorithm, you will notice gaps on the right side of the strip chart, as described in the following example.

If you set Points per Screen to 100 points, the first call to PlotStripChart (with 100 points) plots from 0 to 99. The second call to PlotStripChart plots from 99 to 198 and then plots the last point (199) at the left edge of the strip chart. If the second PlotStripChart starts at 100—as you might expect—the information between 99 and 100 never appears on the screen.

To make all data appear on the screen, set your strip chart Points per Screen to 101 points.

### skipCount

Suppose you have an array that contains 4 data sets (A,B,C,D) and you want to plot each A-B pair into a strip chart control. If the elements are ordered in the following manner,

#### ABCDABCDABCD

then entering a **skipCount** of 2 will cause each C-D pair to be skipped before the next A-B pair is plotted.

# **PlotStripChartPoint**

int status = PlotStripChartPoint (int panelHandle, int controlID, double y);

# Purpose

This function provides a simple interface for adding one point to a strip chart that contains only one trace. The same operation can be performed using PlotStripChart.

Refer to the help text for the PlotStripChart function if you need more information about strip chart plots.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	y	double- precision	The data value to be plotted along the y-axis.

## **Return Value**

status intege	Refer to Appendix A for error codes.
---------------	--------------------------------------

## **PlotText**

## **Purpose**

Plots a text string into a graph control.

The origin of the text is the lower left corner of the string.

The origin of the text is specified in terms of the X and Y coordinates of the graph. If the graph attribute ATTR\_SHIFT\_TEXT\_PLOTS is non-zero and the text origin is within the graph area, the text shifts to the left and/or down until it is completely visible. If ATTR\_SHIFT\_TEXT\_PLOTS is zero, the text does not shift.

Input	t panelHandle integer controlID integer		The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
			The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
			The horizontal position at which to place the left edge of the text within the graph.
	yCoordinate double-precision		The vertical position at which to place the bottom edge of the text within the graph.
	text string integer  textColor integer		The string to be plotted.
			Selects the text font. See Table 3-5 in Chapter 3 for valid fonts.
			Specifies the color of the plotted text. Table 3-3 in Chapter 3 presents a list of the common colors.
	backgroundColor	integer	Specifies the background color of the plotted text. Table 3-3 in Chapter 3 presents a list of the common colors.

# **Return Value**

plotHandle	integer	The handle for the plot. This handle can be passed to DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and
		GetPlotAttribute.

## **PlotWaveform**

## **Purpose**

Plots a waveform into a graph control.

The values in Y Array are scaled according to Y Gain and Y Offset. The X axis timebase is scaled according to Initial X and X Increment. Each point in the plot is computed as follows:

$$X_i = (i * XInc) + InitX$$

$$y_i = (wfm_i * YGain) + YOff$$

where i is the index of the point in the waveform array.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	numberofPoints	integer	The number of points to be plotted.
	yDataType	integer	Specifies the data type of <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
	yGain	double- precision	Specifies the gain to be applied to the waveform (yArray) data.

(continues)

# **Parameters (Continued)**

yOffset	double- precision	Specifies a constant offset to be added to the waveform (yArray) data. The default value is 0.0
initialX	double- precision	Specifies the initial value for the X axis.
xIncrement	double- precision	Specifies the increment along the X axis for each new point.
plotStyle	integer	The curve style to be used when plotting the data points. See Table 3-24 in Chapter 3 for a list of plot styles.
pointStyle	integer	The point style to be used when plotting the array. The point style determines the type of marker drawn when the plot style is VAL_CONNECTED_POINTS or VAL_SCATTER. See Table 3-22 in Chapter 3 for a list of point styles.
lineStyle	integer	This control selects the line style. See Table 3-23 in Chapter 3 for a list of line styles.
pointFrequency	integer	Specifies the point interval at which marker symbols are drawn when the curve style is VAL_CONNECTED_POINTS or VAL_SCATTER.
color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

# **Return Value**

<b>plotHandle</b> in		The handle for the plot. This handle can be passed to DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be passed to SetPlotAttribute and GetPlotAttribute.
----------------------	--	---

# **PlotX**

## **Purpose**

Plots an array of X values against its indices along the Y axis. The plot is displayed in a graph control on the specified panel.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory.  This handle will have been returned by the LoadPanel,  NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	xArray	void *	The array that contains the values to be plotted along the X axis. The data type must be of the type specified by <b>xDataType</b> .
	numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>number of Points</b> .
	xDataType	integer	Specifies the data type of the <b>xArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
	plotStyle	integer	The curve style to be used when plotting the data points. See Table 3-24 in Chapter 3 for a list of plot styles.
	pointStyle	integer	The point style to be used when plotting the array. The point style determines the type of marker drawn when the plot style is VAL_CONNECTED_POINTS or VAL_SCATTER. See Table 3-22 in Chapter 3 for a list of point styles.
	lineStyle	integer	This control selects the line style. See Table 3-23 in Chapter 3 for a list of line styles.
	pointFrequency	integer	Specifies the point interval at which marker symbols are drawn when the curve style is VAL_CONNECTED_POINTS or VAL_SCATTER.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

plotHandle	integer	The handle for the plot. This handle can be passed to
		DeleteGraphPlot to delete the individual plot. Refer to
		Appendix A for error codes. It can also be passed to
		SetPlotAttribute and GetPlotAttribute.

## **PlotXY**

# **Purpose**

Plots an array of X values against an array of Y values.

The plot is displayed in a graph control on the specified panel.

## **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	xArray	void *	The array that contains the values to be plotted along the X axis. The data type must be of the type specified by <b>xDataType.</b>
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in X Array is greater than the <b>number of Points.</b>

(continues

## **Parameters (Continued)**

xDataType	integer	Specifies the data type of the <b>xArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
plotStyle	integer	The curve style to be used when plotting the data points. See Table 3-24 in Chapter 3 for a list of plot styles.
pointStyle	integer	The point style to be used when plotting the array. The point style determines the type of marker drawn when the plot style is VAL_CONNECTED_POINTS or VAL_SCATTER. See Table 3-22 in Chapter 3 for a list of point styles.
lineStyle	integer	This control selects the line style. See Table 3-23 in Chapter 3 for a list of line styles.
pointFrequ	ency integer	Specifies the point interval at which marker symbols are drawn when the curve style is VAL_CONNECTED_POINTS or VAL_SCATTER
color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

## **Return Value**

plotHandle	integer	The handle for the plot. This handle can be passed to DeleteGraphPlot to delete the individual plot. Refer to Appendix A for error codes. It can also be
		passed to SetPlotAttribute and GetPlotAttribute.

## **PlotY**

## **Purpose**

Plots an array of Y values against its indices along the X axis. The plot is displayed in a graph control on the specified panel.

	T	1	
Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>number of Points.</b>
	yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
	plotStyle	integer	The curve style to be used when plotting the data points. See Table 3-24 in Chapter 3 for a list of plot styles.
	pointStyle	integer	The point style to be used when plotting the array. The point style determines the type of marker drawn when the plot style is VAL_CONNECTED_POINTS or VAL_SCATTER. See Table 3-22 in Chapter 3 for a list of point styles.
	lineStyle	integer	This control selects the line style. See Table 3-23 in Chapter 3 for a list of line styles.
	pointFrequency	integer	Specifies the point interval at which marker symbols are drawn when the curve style is VAL_CONNECTED_POINTS or VAL_SCATTER.
	color	integer	Specifies the color of the curve to be plotted. An RGB value is a 4-byte integer with the hexadecimal format 0x00RRGGBB. RR, GG, and BB are the respective red, green, and blue components of the color value. See Table 3-3 in Chapter 3 for a list of the common colors.

plotHandle	integer	The handle for the plot. This handle can be passed to	
		DeleteGraphPlot to delete the individual plot.	
		Refer to Appendix A for error codes. It can also be	
		passed to SetPlotAttribute and	
		GetPlotAttribute.	

# **PointEqual**

int pointsAreEqual = PointEqual (Point point1, Point point2);

# Purpose

Indicates if two points are the same.

Returns 1 if the x and y values of two specified points are the same. Returns 0 otherwise.

# **Parameters**

Input	point1	Point	A point structure.
	point2	Point	A point structure.

# **Return Value**

pointsAreEqual	integer	An indication of the two points are the same.
----------------	---------	---

# **Return Codes**

1	The x and y coordinates in the two Point structures are the same.
0	The x and y coordinates in the two Point structures are not the same.

#### See Also

MakePoint

# **PointPinnedToRect**

void PointPinnedToRect (Point point, Rect rect, Point \*pinnedPoint);

# **Purpose**

This function ensures that a point is within a specified rectangular area. If the point is already enclosed by the rectangle, the location of the point remains unchanged. If the point is outside the rectangle, its location is set to the nearest point on the edge of the rectangle.

The Point structure containing the original location is not modified. The calculated location is stored in another Point structure.

#### **Parameters**

Input	point	Point A Point structure specifying the original location of the point.	
	rect	Rect	A Rect structure specifying the rectangle to which the point is to be pinned.
Output	pinnedPoint	Point	The Point structure in which the calculated location is stored.

### **Return Value**

None

#### See Also

MakePoint, MakeRect.

### **PointSet**

void PointSet (Point \*point, int xCoordinate, int yCoordinate);

### **Purpose**

Sets the values in an existing Point structure. The Point structure defines the location of a point.

Input	xCoordinate integer The new horizontal location of the point.		The new horizontal location of the point.
	yCoordinate	integer	The new vertical location of the point.
Output	point	Point	The Point structure in which the new values are set.

#### **Return Value**

None

### See Also

MakePoint

## **PostDeferredCall**

### **Purpose**

Posts a function to LabWindows/CVI that is to be called at the next occurrence of GetUserEvent, RunUserInterface, or ProcessSystemEvents.

PostDeferredCall would typically be used in a function installed as an asynchronous interrupt handler. The asynchronous interrupt handler is limited in what it can do. It cannot do anything time consuming and it cannot call into the User Interface Library. The function that is posted by PostDeferredCall contains the code that cannot be executed at interrupt time.

This is useful when external devices generate interrupts during source program execution.

#### **Parameters**

Input	deferredFunction	DeferredCallbackPtr	A pointer to the function whose execution
			will be deferred until the next
			GetUserEvent,
			RunUserInterface, or ProcessSystemEvents.
	callbackData	void *	A pointer to user-defined data passed to the deferred function.

status	integer	Refer to Appendix A for error codes.

### **Parameter Discussion**

The function pointed to by **deferredFunction** takes the following form:

void CVICALLBACK DeferredCallbackFunction (void \*callbackData);

# **PrintCtrl**

## **Purpose**

Prints the selected control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.	
	fileName	string	The name of the output file. If the name is non-empty, the output will be redirected to the file. If the name is not a complete pathname, the file will be created relative to the current working directory.	
	scaling	integer	Selects the scaling mode for printing. 1 expands the object to full size. 0 (zero) prints the object at the same relative location and size as displayed on the screen.	
	confirmDialogBox	integer	Displays a dialog box before printing to confirm print attributes. Requested and supported attribute values are shown for the current printer, allowing the user to change attribute values during run-time.	

printStatus	integer	Returns the status of the print operation. Refer to
		Appendix A for error codes.

# **Return Codes**

The value returned by the PrintCtrl function is a bit-field.

VAL_TOO_MANY_COPIES	(1<<0)
VAL_NO_MULTIPLE_COPIES	(1<<1)
VAL_NO_DUPLEX	(1<<2)
VAL_NO_LANDSCAPE	(1<<3)
VAL_CANT_FORCE_MONO	(1<<4)
VAL_NO_SUCH_XRESOLUTION	(1<<5)
VAL_NO_MULTIPLE_XRESOLUTIONS	(1<<6)
VAL_NO_SUCH_YRESOLUTION	(1<<7)
VAL_NO_MULTIPLE_YRESOLUTIONS	(1<<8)
VAL_NO_SEPARATE_YRESOLUTION	(1<<9)
VAL_USER_CANCEL	(1<<10)

# **PrintPanel**

# **Purpose**

Prints the selected panel.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.	
	fileName	string	The name of the output file. If the name is non-empty, the output will be redirected to the file. the name is not a complete pathname, the file will b created relative to the current working directory.	
	scaling	integer	Selects the scaling mode for printing. 1 expands the object to the size of an entire page. 0 (zero) prints the object at the same relative location and size as displayed on the screen.	
	scope	integer	Selects the portion of the specified panel to be printed. VAL_VISIBLE_AREA or VAL_FULL_PANEL.	
	confirmDialogBox	integer	Displays a dialog box before printing to confirm print attributes. Requested and supported attribute values are shown for the current printer, allowing the user to change attribute values during run-time.	

# **Return Value**

printStatus	integer	Returns the status of the print operation. Refer to
		Appendix A for error codes.

# **Return Codes**

The value returned by the PrintPanel function is a bit-field.

VAL_TOO_MANY_COPIES	(1<<0)
VAL_NO_MULTIPLE_COPIES	(1<<1)
VAL_NO_DUPLEX	(1<<2)
VAL_NO_LANDSCAPE	(1<<3)
VAL_CANT_FORCE_MONO	(1<<4)
VAL_NO_SUCH_XRESOLUTION	(1<<5)
VAL_NO_MULTIPLE_XRESOLUTIONS	(1<<6)
VAL_NO_SUCH_YRESOLUTION	(1<<7)
VAL_NO_MULTIPLE_YRESOLUTIONS	(1<<8)
VAL_NO_SEPARATE_YRESOLUTION	(1<<9)
VAL_USER_CANCEL	(1<<10)

#### **Parameter Discussion**

If VAL\_VISIBLE\_AREA is the **scope**, only that portion of the panel visible on the screen is printed. Menu bars, scroll bars, and a frame are printed along with the visible portion. If VAL\_FULL\_PANEL is the **scope**, the entire panel is printed. No menu bars, scroll bars, or frames are printed. Regardless of the **scope**, objects within child panels will be clipped to the frame of the child panel.

Note: By default PrintPanel uses the following settings:

- ATTR PAPER WIDTH is set to VAL USE PRINTER DEFAULT
- ATTR PAPER HEIGHT is set to VAL INTEGRAL SCALE.

If the printout does not fit on the page, call SetPrintAttribute before PrintPanel which changes the settings as follows:

- ATTR\_PAPER\_WIDTH is set to VAL\_INTEGRAL\_SCALE
- ATTR\_PAPER\_HEIGHT is set to VAL\_USE\_PRINTER\_DEFAULT.

### **PrintTextBuffer**

int status = PrintTextBuffer (char buffer[], char outputFile[]);

### **Purpose**

Prints the contents of a text buffer. You may direct the output to the printer or to a file.

Newline/carriage-return characters are honored.

Tabs are expanded according to the current state of the ATTR\_TAB\_INTERVAL attribute. This attribute can be modified using the SetPrintAttribute function. The default tab interval is 4.

Text that extends beyond the end of the paper can be truncated or wrapped, depending on the state of the ATTR\_TEXT\_WRAP attribute. This attribute can be modified using the SetPrintAttribute function. The default is 'wrap'.

#### **Parameters**

Input	buffer	string	The text to be printed. Must be terminated by an ASCII NUL byte.
	outputFile	string	The name of a file to which to direct the output. If " ", the output is directed to the printer.

status integer Refer to Appendix A for error codes.
---

#### **Parameter Discussion**

If **outputFile** is a not a complete pathname, it is created relative to the current working directory

#### See Also

PrintTextFile.

#### **PrintTextFile**

int status = PrintTextFile (char fileName[], char outputFile[]);

## **Purpose**

Prints a text file. You can direct the output to the printer or to a file.

Newline/carriage-return characters are honored.

Tabs are expanded according to the current state of the ATTR\_TAB\_INTERVAL attribute. This attribute can be modified using the SetPrintAttribute function. The default tab interval is 4.

Text that extends beyond the end of the paper can be truncated or wrapped, depending on the state of the ATTR\_TEXT\_WRAP attribute. This attribute can be modified using the SetPrintAttribute function. The default setting is 'wrap'.

#### **Parameters**

Input	fileName	string	The name of the file to print.
	outputFile	string	The name of a file to which to direct the output. If "", the output is directed to the printer.

## **Return Value**

#### **Parameter Discussion**

**fileName** may be a complete pathname or a simple filename. If the name is a simple filename (in other words, contains no directory path), then the following conditions apply.

- If the file is listed in the project, the file is located using the pathname from the project.
- Otherwise, the file is located in the directory containing the project.

If outputFile is a not a complete pathname, it is created relative to the current working directory

#### See Also

PrintTextBuffer.

### **ProcessDrawEvents**

int status = ProcessDrawEvents(void);

### **Purpose**

While inside of a callback function or in code that does not call RunUserInterface or GetUserEvent, the user interface is not updated. If a particular function is overly time-consuming, it essentially "locks out" user interface updates. To force these updates to be processed, call ProcessDrawEvents when you want the user interface to be updated.

Note: The user interface is updated automatically by the GetUserEvent function and when a callback returns.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.

# **ProcessSystemEvents**

int status = ProcessSystemEvents (void);

### **Purpose**

While inside of a callback function or in code that does not call RunUserInterface or GetUserEvent, user interface and system events are not processed. If a particular function is overly time-consuming, it will essentially "lock out" user interface and system events. To force these events to be processed, call ProcessSystemEvents occasionally in the code that is locking out system events. Care must be taken when using this function, because it can allow other callback functions to be executed before ProcessSystemEvents completes.

This function processes all pending system events. These include:

- System events that have been delayed or suspended by a user application. For example: keystrokes, mouse events, and screen updates.
- Events generated by other applications. For example: Windows messages intended to invoke a callback installed with RegisterWinMsqCallback.

Note: This function is called automatically by the GetUserEvent function and after a callback returns.

# **PromptPopup**

## Purpose

Displays a prompt message in a dialog box and waits for the user to type a reply.

#### **Parameters**

Input	title message	string string	The title to be displayed on the dialog box.  The message to be displayed on the dialog box.  The \n character can be used to create multi-line messages.
	maxResponseLength	integer	The maximum number of bytes the user is allowed to enter. The <b>responseBuffer</b> must be large enough to contain all of the user's input plus one ASCII NULL byte.
Output	responseBuffer	string	The buffer in which the user's response is stored. The buffer must be large enough to hold maxResponseLength bytes plus one ASCII NULL byte.

### **Return Value**

status integer Refer to Appendix A for error codes.
---

# QueueUserEvent

int status = QueueUserEvent (int eventNumber, int panelHandle, int controlID);

## **Purpose**

QueueUserEvent is used to place a programmer-defined event in the GetUserEvent queue.

Event numbers 1000 to 10000 are reserved for programmer-defined events. Programmer-defined events are returned by GetUserEvent.

#### **Parameters**

Input	eventNumber	integer	Is an integer value between 1000 and 10000 placed in the event queue which can later be processed by GetUserEvent
	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function. Pass 0 (zero) when the event doesn't apply to a particular panel.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function. Pass 0 (zero) when the event doesn't apply to a particular control.

### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# QuitUserInterface

int status = QuitUserInterface (int returnCode);

# **Purpose**

QuitUserInterface should be called only from within a callback function invoked during execution of RunUserInterface. It causes RunUserInterface to return.

The value returned by RunUserInterface is the value that was passed to QuitUserInterface.

#### **Parameters**

Input	returnCode	integer	The value that will be returned from the call to
			RunUserInterface that is being terminated. This parameter can be used as a flag to pass information
			back through the RunUserInterface function. The value should be greater than or equal to zero.

### **Return Value**

status inte	ger Refer to Appendix A for error codes.	
-------------	--	--

### RecallPanelState

int status = RecallPanelState (int panelHandle, char filename[], int stateIndex);

## Purpose

Reads a panel state from a file created with the SavePanelState function. If the panel is currently visible, all controls are updated to reflect their new states.

Note: If the panel has been modified in the User Interface Editor or programmatically since the panel state was saved, recalling the panel state may fail or may result in a modified panel state.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	filename	string	The name of the file in which the panel state was saved. If the name is a simple filename (in other words, contains no directory path), then the file is loaded from the directory containing the project.
	stateIndex	integer	The same state index assigned to the panel state when it was saved using SavePanelState.

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **RectBottom**

int bottom = RectBottom (Rect rect);

# **Purpose**

Returns the y coordinate of the bottom edge a rectangle. The bottom edge is **not** enclosed by the rectangle. It is computed as follows.

**bottom** = **rect.top** + **rect.height** 

#### **Parameter**

Input	rect	Rect	Specifies the location and size of a rectangle.
-------	------	------	---

### **Return Value**

bottom	integer	The y coordinate of the bottom of the rectangle. The bottom is not enclosed by the rectangle, and is equal to <b>rect.top</b> +
		rect.height.

#### See Also

RectRight

# **RectCenter**

void RectCenter (Rect rect, Point \*center);

# **Purpose**

Calculates the location of the center point of the specified rectangle. For even heights (or widths), the center point is rounded towards the top (or left).

Input	rect	Rect	Specifies the location and size of a rectangle.
Output	center	Point	Specifies the location of the center of the rectangle.

### **Return Value**

None

# **RectContainsPoint**

int containsPoint = RectContainsPoint (Rect rect, Point point);

# **Purpose**

Returns 1 if the specified rectangle encloses the specified point. Returns 0 otherwise. The rectangle is considered to enclose the point if the point is in the interior of the rectangle or on its frame.

### **Parameters**

Input	rect	Rect	Specifies the location and size of a rectangle.
Output	point	Point	Specifies the location of the center of the rectangle.

### **Return Value**

containsPoint	integer	Indicates if <b>rect</b> contains <b>point</b> .
---------------	---------	--

# **Return Codes**

1	<b>point</b> is in the interior or on the frame of the rectangle specified by <b>rect</b> .
0	<b>point</b> is outside the frame of the rectangle specified by <b>rect.</b>

# **RectContainsRect**

int containsRect = RectContainsRect (Rect rect1, Rect rect2);

# **Purpose**

Returns 1 if the first rectangle encloses the second rectangle. Returns 0 otherwise. A rectangle is considered to enclose another rectangle if every point of the second rectangle is in the interior or on the frame of the first rectangle. (A rectangle encloses itself.)

#### **Parameters**

Input	rect1	Rect	Specifies the location and size of a rectangle.
	rect2	Rect	Specifies the location and size of a rectangle.

### **Return Value**

containsRect integ	r Indicates if <b>rect</b>	1 encloses rect2.
--------------------	----------------------------	-------------------

#### **Return Codes**

1	rect1 encloses rect2.
0	rect1 does not enclose rect2.

# **RectEmpty**

int isEmpty = RectEmpty (Rect rect);

## **Purpose**

Returns 1 if the specified rectangle is empty. Returns 0 otherwise. A rectangle is considered to be empty if either its height or width is less than or equal to zero.

## **Parameter**

Input	rect	Rect	Specifies the location and size of a rectangle. A Rect
			structure.

# **Return Value**

<b>isEmpty</b> integer	Indicates if the rectangle specified by <b>rect</b> is empty.
------------------------	---

#### **Return Codes**

1	Either rect.height or rect.width of is less than or equal to zero.
0	Both rect.height and rect.width are greater than zero.

# **RectEqual**

int areEqual = RectEqual (Rect rect1, Rect rect2);

## **Purpose**

Returns 1 if the location and size of the two specified rectangles are identical. Returns 0 otherwise.

### **Parameters**

Input	rect1	Rect	Specifies the location and size of a rectangle.
	rect2	Rect	Specifies the location and size of a rectangle.

#### **Return Value**

areEqual	integer	Indicates if the top, left, height, and width values in <b>rect1</b> are
		identical to those of <b>rect2</b> .

## **Return Codes**

rect1 and rect2 have the identical top, left, height, and width values.

rect1 and rect2 do not have the identical top, left, height, and width values.

# **RectGrow**

void RectGrow (Rect \*rect, int dx, int dy);

# **Purpose**

Modifies the values in a Rect structure so that the rectangle it defines grows or shrinks around its current center point.

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies a rectangle of a different size but the same center point.
Input	dx	integer	The amount to grow the rectangle horizontally. Use a negative value to shrink the rectangle horizontally.
	dy	integer	The amount to grow the rectangle vertically. Use a negative value to shrink the rectangle vertically.

### **Return Value**

None

# **RectIntersection**

int rectsIntersect = RectIntersection (Rect rect1, Rect rect2, Rect \*intersectionRect);

# **Purpose**

Returns an indication of whether two rectangles are intersecting. If they are, the function fills in a Rect structure describing the intersection area.

## **Parameters**

Input	rect1	Rect	Specifies the location and size of a rectangle.
	rect2	Rect	Specifies the location and size of a rectangle.
Output	intersectionRect	Rect	The Rect structure set to the largest rectangle enclosed by both <b>rect1</b> and <b>rect2</b> . If <b>rect1</b> and <b>rect2</b> do not intersect, this parameter is set to an empty rectangle (height and width of zero). You may pass 0 for this parameter.

### **Return Value**

rectsIntersect	integer	Indicates if <b>rect1</b> and <b>rect2</b> intersect (have any points
		in common).

# **Return Codes**

1	rect1 and rect2 intersect.		
0	rect1 and rect2 do not intersect.		

# **RectMove**

void RectMove (Rect \*rect, Point point);

# **Purpose**

Modifies a Rect structure so that the top, left corner of the rectangle it defines is at the specified point.

### **Parameters**

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies a rectangle of the same size but a different location.
Input	point	Point	A Point structure specifying the new location of the top, left corner of the rectangle.

### **Return Value**

None

# **RectOffset**

void RectOffset (Rect \*rect, int dx, int dy);

# **Purpose**

Modifies the values in a Rect structure to shift the location of the rectangle it defines.

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies a rectangle of the same size but a different location.
Input	dx	integer	The amount to shift the rectangle horizontally. Use a positive value to shift the rectangle to the right. Use a negative value to shift the rectangle to the left.
	dy	integer	The amount to shift the rectangle vertically. Use a positive value to shift the rectangle down. Use a negative value to shift the rectangle up.

### **Return Value**

None

# RectRight

int rightEdge = RectRight (Rect rect);

# **Purpose**

Returns the x coordinate of the right edge a rectangle. The right edge is **not** enclosed by the rectangle. It is computed as follows.

rightEdge = rect.left + rect.width

### **Parameter**

Input	rect	Rect	Specifies a rectangle.
111111111111111111111111111111111111111		11000	~pooritos a rootaingro.

### **Return Value**

rightEdge	integer	The x coordinate of the right edge of the rectangle. The
		right edge is not enclosed by the rectangle, and is equal
		to rect.left + rect.width.

# See Also

RectBottom

# **RectSameSize**

int areSameSize = RectSameSize (Rect rect1, Rect rect2);

## **Purpose**

Returns 1 if the two specified rectangle have the same height and width. Returns 0 otherwise.

#### **Parameters**

Input	rect1	Rect	Specifies the location and size of a rectangle.
	rect2	Rect	Specifies the location and size of a rectangle.

#### **Return Value**

areSameSize integer Indicates if the height, and width values in rect1 to those of rect2.	are identical
---	---------------

### **Return Codes**

1	rect1 and rect2 have the identical height, and width.
0	rect1 and rect2 do not have the identical height and width.

# RectSet

void RectSet (Rect \*rect, int top, int left, int height, int width);

# **Purpose**

Sets the values in an existing Rect structure. The Rect structure defines the location and size of a rectangle.

#### **Parameters**

Input	top	integer	The new location of the top edge of the rectangle.
	left	integer	The new location of the left edge of the rectangle.
	height	integer	The new height of the rectangle.
	width	integer	The new width of the rectangle.
Output	rect	Rect	The Rect structure in which the new values are set.

None

### See Also

MakeRect

# **RectSetBottom**

void RectSetBottom (Rect \*rect, int bottom);

### **Purpose**

Sets the height of a Rect structure so that the bottom edge of the rectangle it defines is at the specified location. The bottom edge of the rectangle is **not** enclosed by the rectangle and is equal to the top plus the height.

### **Parameters**

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies the same rectangle except with a different bottom edge.
Input	bottom	integer	The y coordinate of the new bottom edge.

#### **Return Value**

None

### **RectSetCenter**

void RectSetCenter (Rect \*rect, Point center);

# **Purpose**

Modifies the values of a Rect structure so that it retains its current size but is centered around the specified point.

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies a rectangle of the same size but with a different center point.
Input	center	Point	A Point structure specifying the location of the new center point of the rectangle.

Return	Value
--------	-------

None

# **RectSetFromPoints**

void RectSetFromPoints (Rect \*rect, Point point1, Point point2);

# **Purpose**

Sets the values in a Rect structure so that it defines the smallest rectangle that encloses two specified points. Each point is located on a corner of the frame of the rectangle.

### **Parameters**

Input	point1	Point	Specifies the location of a point.
	point1	Point	Specifies the location of a point.
Output	rect	Rect	The Rect structure that is set to enclose the specified points.

## **Return Value**

None

# RectSetRight

void RectSetRight (Rect \*rect, int right);

# **Purpose**

Sets the width of a Rect structure so that the right edge of the rectangle it defines is at the specified location. The right edge of the rectangle is **not** enclosed by the rectangle and is equal to the left edge plus the width.

#### **Parameters**

Input/Output	rect	Rect	On input, specifies the size and location of a rectangle. On output, specifies the same rectangle except with a different right edge.
Input	right	integer	The x coordinate of the new right edge.

# **Return Value**

None

# **RectUnion**

void RectUnion (Rect rect1, Rect rect2, Rect \*unionRect);

## **Purpose**

Calculates the smallest rectangle which encloses two specified rectangles.

### **Parameters**

Input	rect1	Rect	Specifies the size and location of a rectangle.
	rect1	Rect	Specifies the size and location of a rectangle.
Output	unionRect	Rect	The Rect structure that is set to the smallest rectangle that encloses both <b>rect1</b> and <b>rect2</b> .

#### **Return Value**

None

# RefreshGraph

int status = RefreshGraph (int panelHandle, int controlID);

# **Purpose**

Immediately redraws the plot area.

This action removes any plots that were deleted using DeleteGraphPlot in Delayed Draw mode. It also displays any plots that are plotted while ATTR\_REFRESH\_GRAPH is set to FALSE.

#### **Parameters**

input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.

# Register Win Msg Callback

int messageNumber = RegisterWinMsgCallback (WinMsgCallbackPtr callbackFunction,

char messageIdentifier[],
void \*callbackData, int dataSize,
int \*callbackID,
int deleteWhenProgramStops);

Note: This function is available only in the Windows version of LabWindows/CVI.

## **Purpose**

This function registers a callback function that is called when the LabWindows/CVI application receives the specified Windows message.

Input	callbackFunction	WinMsgCallbackPtr	The name of the user function that is called whenever LabWindows/CVI receives the Windows message returned by RegisterWinMsgCallback. To send this message to LabWindows/CVI, call the Windows API function PostMessage from a DLL.
	messageIdentifier	string	A user-defined string that allows two processes to use the same Windows message number. (See discussion below.)
	callbackData	void *	A pointer to user-defined data passed to the event function.
	dataSize	integer	If dataSize = zero, then the callbackData pointer is the same pointer that will be passed to callbackFunction when it is called. If dataSize is greater than zero, then the data pointed to by the callbackData pointer will be copied and the callbackFunction will be called with the callbackData pointer pointing to the copy of the data.
	deleteWhenProgramStops	integer	If true, UnRegisterWinMsgCallback is implicitly called when the user program terminates. If false, the callback function remains installed when the user program terminates.
Output	callbackID	integer	The ID that is passed to UnRegisterWinMsgCallback to disable the callback function.

# **Return Value**

	messageNumber	integer	The message number assigned by Windows. If 0 (zero), the function fail
--	---------------	---------	--

### **Parameter Discussion**

**callbackFunction** is a pointer to an event function that takes the form:

void CVICALLBACK EventFunctionName (unsigned short wParam, unsigned lParam, void \*callbackData); The event function is passed the **wParam** and **lParam** Parameters that were passed to PostMessage. The **callbackData** that was passed to RegisterWinMsgCallback is also passed to the event function.

If you pass zero (0) for the **messageIdentifier**, a unique Windows message number is returned by RegisterWinMsgCallback. Subsequent calls to RegisterWinMsgCallback (or the Windows API function RegisterWindowMessage) does not return the same **messageNumber** until you call UnRegisterWinMsgCallback with the **callbackId** returned by RegisterWinMsgCallback.

If you pass a string for the **messageIdentifier**, any subsequent call to RegisterWinMsgCallback (or the Windows API function RegisterWindowMessage) using the same **messageIdentifier** string returns the same **messageNumber**.

To send the message registered through RegisterWinMsgCallback to LabWindows/CVI, pass this message number to the Windows API function PostMessage.

If RegisterWinMsgCallback fails, this value will be 0.

# RemovePopup

int status = RemovePopup (int removePopup);

## **Purpose**

Removes either the active pop-up panel or all pop-up panels.

#### **Parameters**

Input	removePopup	integer	Selects whether to remove all pop-up panels or only the
			active pop-up panel. $1 = All$ 0 = Active Only.

#### **Return Value**

<b>status</b> integ	ger Refer to Appendix A for error codes.	
---------------------	--	--

# ReplaceAxisItem

# **Purpose**

This function replaces the string/value pair at the specified index in the list of label strings for a graph or strip chart axis. These strings appear in place of the numerical labels. They appear at the location of their associated values on the graph or strip chart.

To see string labels on an X axis, you must set the ATTR\_XUSE\_LABEL\_STRINGS attribute to TRUE. To see string labels on a Y axis, you must set the ATTR\_YUSE\_LABEL\_STRINGS attribute to TRUE.

The original list of label strings can be created in the User Interface Editor or by calling InsertAxisItem.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies the axis for which to replace the string/value pair at the specified index. Valid values:  VAL_XAXIS  VAL_LEFT_YAXIS  VAL_RIGHT_YAXIS (graphs only)
	itemIndex	integer	The zero-based index of the item to be replaced.
	itemLabel	string	The string to replace the existing string in the item at the specified index. If you pass 0, then the existing string is not replaced. A maximum of 31 characters from the string are shown in an axis label.
	itemValue	double- precision	The value to replace the existing value in the string/value pair at the specified index. The string appears as an axis label at the location of the value.

status integer Refer to Appendix A for error codes.	
---	--

#### See Also

InsertAxisItem, DeleteAxisItem, ClearAxisItems, GetNumAxisItems

# ReplaceListItem

# **Purpose**

This function replaces the label/value pair at the specified index in a list control with a new label/value pair.

### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index into the list where the item will be replaced.
	itemLabel	string	The label to be associated with the value being replaced. Pass 0 to use the existing label.
	itemValue	depends on the data type of the list control	The value to be associated with the label being replaced. The data type must be the same as the data type of the control.

### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

#### **Parameter Discussion**

The Parameter Discussion in InsertListItem tells you how to create columns and colored text in List Box controls and separator bars in Ring controls.

For picture rings, the "label" is actually an image, and you pass the pathname of the image as the itemLabel parameter. The image pathname may be a complete pathname or a simple filename. If a simple filename, the image is located in the project. If not located in the project, it is located in the directory of the project. If you pass NULL or the empty string, a placeholder for the image is created, which can be filled using ReplaceListitem or SetImageBits.

# ReplaceTextBoxLine

## **Purpose**

This function replaces the string at the specified text box line.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	lineIndex	integer	The zero-based index into the text box.
	text	string	The string to replace the line of text at the specified <b>lineIndex.</b>

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# ResetTextBox

int status = ResetTextBox (int panelHandle, int controlID, char text[]);

# **Purpose**

This function replaces all text from the specified text box with the specified string.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	text	string	The string to replace all text in the specified text box.

#### **Return Value**

status integer Refer to Appendix A for error codes.
---

# ResetTimer

int status = ResetTimer (int panelHandle, int controlID);

## Purpose

This function resets the interval start times for timer controls. ResetTimer resets a timer whether or not it is disabled or suspended. When a timer with an ATTR\_INTERVAL of x seconds is reset, the interval is rescheduled to end x seconds from the time of the call.

You may specify an individual timer control on a panel, all timer controls on a panel, or all timer controls on all panels.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. The handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function. Pass 0 to indicate all timer controls on all panels.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function. Pass 0 to indicate all timer controls on the specified panel.

### **Return Value**

status integ	er Refer to Appendix A for error codes.
--------------	---

#### See Also

SuspendTimerCallbacks, ResumeTimerCallbacks.

# ResumeTimerCallbacks

int status = ResumeTimerCallbacks (void);

# **Purpose**

Cancels the effect of a call to SuspendTimerCallbacks.

Callbacks resume using the ongoing interval schedules, which are not affected by SuspendTimerCallbacks.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### See Also

SuspendTimerCallbacks, ResetTimer.

# RunPopupMenu

### **Purpose**

Displays a menu and tracks mouse and keyboard events on the menu.

In most cases, you should call this function from a User Interface panel or control callback function that has received a LEFT\_CLICK, RIGHT\_CLICK, or KEYPRESS event.

If the user selects an item from the menu, the following actions occur.

- If a callback function is associated with the menu item, the function is called.
- The ID of the menu item is returned.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuID	integer	The ID for a particular menu within a menu bar. The Menu ID should be a constant name (located in the .uir header file) generated in the User Interface Editor, or a value returned by the NewMenu function.
	panelHandle	integer	The handle for the panel over which you want the menu to appear. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	top	integer	The vertical coordinate at which the upper left corner of the menu is to be placed. Must be a value from -32768 to 32767. It represents the pixel offset from the top of the panel specified by <b>panelHandle</b> .
	left	integer	The horizontal coordinate at which the upper left corner of the menu is to be placed. Must be a value from -32768 to 32767. It represents the pixel offset from the left edge of the panel specified by <b>panelHandle</b> .

(continues)

### **Parameters (Continued)**

pinTop	integer	The vertical coordinate of the upper left corner of the "pin" area relative to the upper left corner of the panel specified by the <b>panelHandle</b> parameter.
pinLeft	integer	The horizontal coordinate of the upper left corner of the "pin" area relative to the upper left corner of the panel specified by the <b>panelHandle</b> parameter.
pinHeight	integer	The height of the "pin" area.
pinWidth	integer	The width of the "pin" area.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### **Return Codes**

>0	ID of menu item selected.
0	User did not select a menu item.

#### **Parameter Discussion**

**pinTop**, **pinLeft**, **pinHeight**, and **pinWidth** define the "pin" area. Usually the "pin" area is the area on which the user pressed the mouse button in order to bring up the menu. When the user releases the mouse button over the "pin" area, the menu remains visible (is "pinned"). When the user releases the mouse button over any other area, the menu disappears.

If you do not want there to be a "pin" area, pass zeros for **pinTop**, **pinLeft**, **pinHeight**, **pinWidth**.

### RunUserInterface

int status = RunUserInterface (void);

### **Purpose**

RunUserInterface runs the User Interface and issues events to callback functions.

RunUserInterface does not return until QuitUserInterface is called from within a callback function. The value returned by RunUserInterface is the value that was passed to QuitUserInterface.

status	integer	The value that was passed to the
		QuitUserInterface function.

### **SavePanelState**

int status = SavePanelState (int panelHandle, char filename[], int stateIndex);

## **Purpose**

Saves the state of a panel to a file. The current value of all controls on the panel are also saved. The following attributes associated with the control's values are saved: label/value pairs; label/value pairs index; minimum, maximum, and increment values; and listbox checkmark state values.

If you want to retain plotted array data in a graph control, your original array must still be in memory when you call RecallPanelState. Alternatively, the graph could be configured to Copy Original Plot Data in the User Interface Editor or via the SetGraphAttribute function using ATTR\_COPY\_ORIGINAL\_DATA.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	filename	string	The name of the file in which to save the panel state. If the file already exists, its contents will be overwritten. If the name is a simple filename (in other words, contains no directory path), then the file is saved in the directory containing the project.
	stateIndex	integer	Assigns a unique state index to each panel state so that you can save multiple panel states to the same file.

## **Return Value**

status integer Refer to Appendix A for error codes.
---

# **SetActiveCtrl**

int status = SetActiveCtrl (int panelHandle, int controlID);

# **Purpose**

This function sets the active control on the specified panel.

The active control is the control that receives keyboard events when its panel is the active panel.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.

# **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# ${\bf Set Active Graph Cursor}$

# **Purpose**

Sets the active cursor on the specified graph control.

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	activeCursorNumber	integer	Specifies the new active cursor number. The value may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.

# **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **SetActivePanel**

int status = SetActivePanel (int panelHandle);

# **Purpose**

Makes the selected panel the active panel. The active panel is the panel which receives keyboard events.

#### **Parameters**

Input	panelHandle	 The specifier for a particular panel that is currently in	
		memory. This handle will have been returned by the	
		LoadPanel, NewPanel, or DuplicatePanel	
		function.	

# **Return Value**

<b>status</b> inte	eger	Refer to Appendix A for error codes.
--------------------	------	--------------------------------------

# SetAxisScalingMode

## **Purpose**

Sets the scaling mode and the range of any graph axis or the Y axis of a strip chart.

This function is not valid for the X axis of a strip chart. To set the X offset and X increment for a strip chart, use the SetCtrlAttribute function with the ATTR\_XAXIS\_OFFSET and ATTR\_XAXIS\_GAIN attributes.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	axis	integer	Specifies for which axis to set the mode and range.  Valid values:  VAL_XAXIS (graphs only)  VAL_LEFT_YAXIS (graphs and strip charts)  VAL_RIGHT_YAXIS (graphs only)
	axisScaling	integer	The scaling mode to be used for the axis. See table below.
	min	double- precision	The minimum axis value when the axis is configured for manual scaling.
	max	double- precision	The maximum axis value when the axis is configured for manual scaling.

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### **Parameter Discussion**

**axisScaling** must be one of the following values.

Valid Value	Description
VAL_MANUAL	The axis is set to manual scaling, and its range is defined by <b>min</b> and <b>max</b> .
VAL_AUTOSCALE	The axis is set to auto scaling. <b>min</b> and <b>max</b> are not used. You cannot use auto scaling in strip charts.
VAL_LOCK	The axis is set to manual scaling using the current (usually auto-scaled) minimum and maximum values on the axis. You cannot use VAL_LOCK in strip charts.

If axisScaling is VAL\_MANUAL, max must exceed min.

#### See Also

GetAxisScalingMode

# **SetAxisRange**

## **Purpose**

Sets the scaling mode and the range of the X and Y axes for a graph or strip chart control.

# **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID integer		The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	xAxisScaling	integer	The scaling mode used by the X axis.
	xminXinit	double- precision	For a graph, <b>xmin</b> specifies the minimum axis range when the X axis is configured for manual scaling. In this case, <b>xmax</b> must exceed <b>xmin</b> . For a strip chart, <b>Xinit</b> specifies the initial X axis value.
	xmaxXinc double-precision		For a graph, <b>xmax</b> specifies the maximum axis range when the X axis is configured for manual scaling. In this case, <b>xmax</b> must exceed <b>xmin</b> . For a strip chart, <b>Xinc</b> specifies the X axis increment for each new point.
	yAxisScaling	integer	The scaling mode used by the Y axis.
	ymin	double- precision	Specifies the minimum axis range when the Y axis is configured for manual scaling. In this case, <b>ymax</b> must exceed <b>ymin</b> .
	ymax	double- precision	Specifies the maximum axis range when the Y axis is configured for manual scaling. In this case, <b>ymax</b> must exceed <b>ymin</b> .

integer integer	Refer to Appendix A for error codes.	
-----------------	--------------------------------------	--

#### **xAxisScaling**

Valid Values	Description
VAL_NO_CHANGE	The current X axis scaling mode remains unchanged. <b>xmin</b> and <b>xmax</b> are not used.
VAL_MANUAL	The X axis is set to manual scaling, and its range is defined by <b>xmin</b> and <b>xmax</b> .
VAL_AUTOSCALE	The X axis is set to auto scaling. <b>xmin</b> and <b>xmax</b> are not used. Auto scaling is not allowed for strip charts.
VAL_LOCK	The X axis is set to manual scaling using the current axis range. Lock scaling is not allowed for strip charts.

# yAxisScaling

Valid Values	Description	
VAL_NO_CHANGE	The current Y axis scaling mode remains unchanged. <b>ymin</b> and <b>ymax</b> are not used.	
VAL_MANUAL	The Y axis is set to manual scaling, and its range is defined by <b>ymin</b> and <b>ymax</b> .	
VAL_AUTOSCALE	The Y axis is set to auto scaling. <b>ymin</b> and <b>ymax</b> are not used. Auto scaling is not allowed for strip charts.	
VAL_LOCK	The Y axis is set to manual scaling using the current axis range. Lock scaling is not allowed for strip charts.	

#### **SetCtrlAttribute**

int status = SetCtrlAttribute (int panelHandle, int controlID, int controlAttribute,
...);

## **Purpose**

Sets a control attribute for the selected panel and control.

Not all attributes are valid for each type of control, attributes may Return Values of different data types with different valid ranges. A list of attributes, their data types and valid values are provided in Table 3-9 in Chapter 3, *Programming with the User Interface Library*.

The attributes that users cannot set are denoted as such in Chapter 3, *Programming with the User Interface Library*, Table 3-9. These attributes may be examined with the GetCtrlAttribute function.

Note: When you set control attributes that affect the font of a control, you should modify the ATTR\_TEXT\_FONT attribute first.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	controlAttribute	integer	A particular control attribute.
	attributeValue	depends on the attribute	The value of the specified control attribute.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# SetCtrlBitmap

#### **Purpose**

Sets the image of a control from a bitmap object. Can be used to replace an existing image on a control or to create a new image on a control.

The following control types can contain images:

picture controls picture rings picture buttons graph controls

For picture controls, this function can be used as an alternative to DisplayImageFile.

For picture buttons, this function can be used as an alternative to SetCtrlAttribute with the attribute set to ATTR\_IMAGE\_FILE.

For picture rings, this function can be used as an alternative to ReplaceListItem. (To add a new entry, first call InsertListItem with a NULL value, and then call SetCtrlBitmap.)

For graphs, you must first call PlotBitmap with a NULL filename. Then call SetCtrlBitmap.

If you want to delete an image, call SetCtrlBitmap with 0 as the value for the bitmap ID.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is contained in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control in the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	imageID	integer	For picture rings, the zero-based index of an image in the ring. For graphs, this argument is the <b>plotHandle</b> returned from PlotBitmap. For picture controls and picture buttons, this argument is ignored.
	bitmapID	integer	The ID of the bitmap object containing the new image. The ID must have been obtained from NewBitmap, GetBitmapFromFile, GetCtrlBitmap, ClipboardGetBitmap, GetCtrlDisplayBitmap, or GetPanelDisplayBitmap.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
		Troit to Tippelloni Tiple of the Court

#### See Also

NewBitmap, GetBitmapFromFile, GetCtrlBitmap, GetCtrlDisplayBitmap, GetPanelDisplayBitmap, ClipboardGetBitmap.

#### SetCtrlIndex

int status = SetCtrlIndex (int panelHandle, int controlID, int itemIndex);

#### **Purpose**

This function sets the current index of the specified list control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	itemIndex	integer	The zero-based index into the list control.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## **SetCtrlVal**

int status = SetCtrlVal (int panelHandle, int controlID, ...);

#### **Purpose**

Sets the value of a control to the specified value.

When called on a list control (a list box or ring), SetCtrlVal sets the current list item to the first item whose associated value is **value**. To set the current list item via zero-based index, use the SetCtrlIndex function.

When called on a text box, SetCtrlVal appends **value** to the contents of the text box. Use ResetTextBox to replace the contents of the text box with **value**.

# **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is
			currently in memory. This handle will have been
			returned by the LoadPanel, NewPanel, or
			DuplicatePanel function.

controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
value	depends on the data type of the control	The new value of the control. The data type of <b>value</b> must match the data type of the control.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

# SetCursorAttribute

# **Purpose**

Sets one of the following graph cursor attributes: mode, point style, cross hair style, color, or y-axis.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
	cursorAttribute	integer	Selects a particular graph cursor attribute.  Valid Attributes:  ATTR_CURSOR_MODE  ATTR_CURSOR_POINT_STYLE  ATTR_CROSS_HAIR_STYLE  ATTR_CURSOR_COLOR  ATTR_CURSOR_YAXIS
	attributeValue	integer	The new value of the attribute. See Table 3-20 for a complete listing of cursor attribute values.

#### **Return Value**

status in	nteger	Refer to Appendix A for error codes.
-----------	--------	--------------------------------------

# **SetFontPopupDefaults**

## **Purpose**

This function specifies the settings to apply to the FontSelectPopup when the user presses the **Default** button.

This function applies to all attributes that affect the sample text display, even attributes for which the controls have been hidden.

The default values specified by this function apply only to the next call to FontSelectPopup. Thus, this function should always be called before each call to FontSelectPopup. If you do not call it before FontSelectPopup, the parameters have the following default values:

Parameter Name	Default Value
typefaceName	VAL_DIALOG_FONT
bold	0
underline	0
strikeOut	0
italic	0
justification	VAL_LEFT_JUSTIFIED
textColor	VAL_BLACK
fontSize	12

#### **Parameters**

Input	typefaceName	string	The default typeface name (for example, "Courier") for use by FontSelectPopup.
	bold	integer	The default bold setting for use by FontSelectPopup.
	underline	integer	The default underline setting for use by FontSelectPopup.
	strikeOut	integer	The default strike out setting for use by FontSelectPopup.
	italic	integer	The default italic setting for use by FontSelectPopup.
	justification	integer	The default justification setting for use by FontSelectPopup.
	textColor	integer	The default text color setting for use by FontSelectPopup.
	fontSize	integer	The default font size for use by FontSelectPopup.

etatus	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

FontSelectPopup.

# SetGraphCursor

## **Purpose**

Sets the position of the specified graph cursor.

The position is relative to the current range of the X and Y axes.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
	x	double- precision	Specifies the X coordinate of the new cursor position.
	y	double- precision	Specifies the Y coordinate of the new cursor position.

status integer Refer to Appendix A for error codes.	
---	--

# ${\bf Set Graph Cursor Index}$

# **Purpose**

Attaches a cursor to particular data point defined by a plot handle and array index.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	cursorNumber	integer	The cursor number may range from 1 to the number of defined cursors for the specified graph. The number of defined cursors is established when you edit the graph in the User Interface Editor or through SetCtrlAttribute.
	plotHandle	integer	Specifies the handle of the plot on which to attach the cursor. Cursors cannot be attached to plots generated by, PlotText PlotOval PlotRectangle PlotArc PlotLine PlotBitmap PlotIntensity
	arrayIndex	integer	Specifies the array index of the data point on which to attach the cursor.

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## **SetIdleEventRate**

int status = SetIdleEventRate (int interval);

# **Purpose**

This function sets the interval between idle events.

Idle events can be processed by the main callback function if enabled through InstallMainCallback.

The InstallMainCallback function takes the name of an event function (type MainCallbackPtr), a pointer to callback data of any type, and a Boolean indicating whether or not to get idle events.

The **getIdleEvents** feature allows program execution to proceed when it would normally be suspended. For example, the program would normally be suspended in GetUserEvent or RunUserInterface when the user holds the mouse button down on a control or pull-down menu.

Note: Idle events are not generated while a top level panel is being moved or sized.

#### **Parameters**

Input	interval	integer	Specifies the wait interval between generated idle events (in milliseconds) A value of zero will cause idle events to occur at the fastest possible rate. For non-zero values, the resolution of idle events is the resolution of the system timer (1 milliseconds on Windows) and an
			operating system dependent latency.

status in	integer	Refer to Appendix A for error codes.
-----------	---------	--------------------------------------

# **SetImageBits**

## **Purpose**

Sets the bit values that define an image. Can be used to replace an existing image on a control or to create a new image on a control.

The following control types can contain images: picture controls, picture rings, picture buttons, graph controls.

For a picture control, this function can be used as an alternative to DisplayImageFile.

For a picture buttons, this function can be used as an alternative to SetCtrlAttribute with the attribute ATTR\_IMAGE\_FILE.

For picture rings, this function can be used as an alternative to ReplaceListItem. (To add a new entry, first call InsertListItem with a NULL value, and then call SetImageBits.)

For graphs, you must first call PlotBitmap with a NULL filename. Then call SetImageBits.

If you want to delete an image, call SetImageBits with -1 as the value for the **width** or the **height** parameter.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.		
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.		
	imageID	integer	For a picture ring, the zero-based index of an image in the ring. For a graph, the <b>plotHandle</b> , returned from <b>PlotBitmap</b> . For picture controls and buttons, this is ignored.		
	rowBytes	integer	The number of bytes on each scan line of the image.		
	depth	integer	The number of bits per pixel.		
	width	integer	The width of the image, in pixels.		
	height	integer	The height of the image, in pixels.		
	colorTable	integer array	An array of RGB color values.		
	bitmap	unsigned char array	An array of bits that determine the colors to be displayed on each pixel in the image.		
	mask	unsigned char array	An array containing one bit per pixel in the image. Each bit specifies whether the pixel is actually drawn.		

#### **Return Value**

status integr	r Refer to Appendix A for error codes.
---------------	--

#### **Parameter Discussion**

If either the width or height parameter is -1 and there is an existing image, it is deleted.

Depending on the depth and width, the number of bits per scan line in the bitmap array may not be an even multiple of 8. If not, then the extra bits needed to get to the next byte boundary is considered "padding". If you specify **rowBytes** as a positive number, then the bits for each scan line must start on a byte boundary, and so padding may be required. In fact, you can specify a value for **rowBytes** that is larger than the minimum number of bytes actually needed. The extra

bytes are also considered padding. If you pass -1, there is no padding at all. The bits for each scan line immediately follow the bits for the previous scan line.

The valid values for **pixelDepth** are 1, 4, 8, 24, and 32.

If the **pixelDepth** is 8 or less, the number of entries in the **colorTable** array must equal 2 raised to the power of the **pixelDepth** parameter. The **bits** array contain indices into the **colorTable** array. If the **pixelDepth** is greater than 8, the **colorTable** parameter is not used. Instead the **bits** array contains actual RGB color values, rather than indices into the **colorTable** array.

For a **pixelDepth** of 24, each pixel is represented by a 3-byte RGB value of the form 0xRRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The RR byte should always be at the lowest memory address of the three bytes.

If the **pixelDepth** is 32, each pixel in the **bits** array is represented by a 32-bit RGB value of the form  $0 \times 00$ RRGGBB, where RR, GG, and BB represent the red, green and blue intensity of the color. The 32-bit value is treated as a native 32-bit integer value for the platform. The most significant byte is always ignored. The BB byte should always be in the least significant byte. On a little-endian platform (for example, Intel processors), BB would be at the lowest memory address. On a big-endian platform (for example, Motorola processors), BB would be at the highest address. Note that this differs from the format of the bits array when the **pixelDepth** is 24..

In the **mask** array, a bit value of 1 indicates that the pixel is drawn. 0 indicates that the pixel is not drawn. Exception: If an image has a **pixelDepth** of 1, pixels with a **bits** value of 1 (foreground pixels) are always drawn and the **mask** affects only the pixels with a bitmap of 0 (background pixels). Each row of the mask must be padded to the nearest even-byte boundary. For example, if the width of the image is 21 pixels, then there must be 32 bits (in other words, 4 bytes) of data in each row of the mask.

A mask is useful for achieving transparency.

You may pass NULL if you do not need a mask.

#### See Also

GetImageInfo, AllocImageBits, GetImageBits.

# **SetInputMode**

## **Purpose**

Controls whether user input is recognized.

When an object's input mode is disabled, it appears dimmed on the screen. Recognition of user input can be controlled at the panel, control, menu bar, menu, or menu item level.

#### **Parameters**

Input	panelorMenuBarHandle	integer	The handle of the panel or menu bar on which you wish to set the recognition of user input. If -1 is entered, all panels and all menu bars are affected.
	controlorMenuItemID	integer	The ID of the control or menu item on which you wish to set the recognition of user input. The ID is the defined constant that was assigned to the control or menu item in the User Interface Editor or the ID returned by NewCtrl or NewMenuItem. If -1, all controls on the panel and/or all items in the menu bar are affected.
	inputMode	integer	Specifies whether user input is enabled or disabled.  0 = disabled.  1 = enabled.

status integer Refer to Appendix A for error codes.
---

# **SetListItemImage**

# **Purpose**

This function puts a predefined image in a list control on the same line as the specified item index.

This function is not valid for picture ring controls. For picture rings, see SetImageBits.

# **Valid Images:**

no folder	VAL_NO_IMAGE
folder	VAL_FOLDER
open folder	VAL_OPEN_FOLDER
current folder	VAL_CURRENT_FOLDER

#### **Parameters**

Input	panelHandle controlID	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.  The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or	
			DuplicateCtrl function.	
	itemIndex	integer	The zero-based index into the list.	
	image	integer	Selects an image for display in the specified list item.	

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## **SetMenuBarAttribute**

## **Purpose**

This function sets the value of the specified menu bar attribute.

#### **Parameters**

Input	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.
	menuorMenuItemID	integer	The menu or menu item ID assigned in the User Interface Editor or returned by the NewMenu or NewMenuItem. If the attribute corresponds to the entire menu bar, pass 0 as this parameter.
	menuBarAttribute	integer	See Table 3-6 in Chapter 3 for a complete listing of menu bar attributes.
	attributeValue	depends on the attribute	The value of the selected menu bar attribute. See Table 3-6 in Chapter 3 for a complete listing of menu bar attribute values.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

## **SetMouseCursor**

int status = SetMouseCursor (int mouseCursorStyle);

#### **Purpose**

Sets the mouse cursor to the specified style.

This function sets the mouse cursor for all existing panels and any panels created by NewPanel or DuplicatePanel or loaded by LoadPanel.

#### **Parameters**

Input	mouseCursorStyle	_	Specifies the mouse cursor style. See Table 3-4 in Chapter 3 for a list of valid mouse cursor
			styles.

## **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **SetPanelAttribute**

int status = SetPanelAttribute (int panelHandle, int panelAttribute, ...);

# Purpose

This function sets a particular panel attribute.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	panelAttribute	integer	A particular panel attribute. See Table 3-2 in Chapter 3 for a complete listing of panel attributes.
	attributeValue	depends on the attribute	The value of the specified panel attribute. See Table 3-2 in Chapter 3 for a complete listing of panel attribute values.

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

## **SetPanelMenuBar**

int status = SetPanelMenuBar (int panelHandle, int menuBarHandle);

## **Purpose**

This function assigns a menu bar to the specified panel.

A panel can have only one menu bar at a time, but multiple panels can share the same menu bar.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	menuBarHandle	integer	The specifier for a particular menu bar that is currently in memory. This handle will have been returned by LoadMenuBar or NewMenuBar.

#### **Return Value**

status integer Refer to Appendix A for error codes.
---

#### **SetPanelPos**

int status = SetPanelPos (int panelHandle, int panelTop, int panelLeft);

## **Purpose**

Sets the position of upper left corner (directly below the title bar) of the panel. The size of the panel remains constant.

The size of the panel may be changed with the SetPanelAttribute function.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	panelTop	integer	The vertical coordinate at which the upper left corner of the panel (directly below the title bar) is placed.
	panelLeft	integer	The horizontal coordinate at which the upper left corner of the panel (directly below the title bar) is placed.

# **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

## **Parameter Discussion**

The **panelTop** and **panelLeft** coordinates must be integer values from -32768 to 32767, or VAL\_AUTO\_CENTER to center the panel. For a top-level panel, (0,0) is the upper-left corner of the screen. For a child panel, (0,0) is the upper-left corner of the parent panel (directly below the title bar) before the parent panel is scrolled.

#### **SetPlotAttribute**

# **Purpose**

Sets the value of a graph plot attribute.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	plotHandle	integer	The handle for a particular plot in the graph. It will have been returned by one of the graph plotting functions.
	plotAttribute	integer	Selects a particular graph plot attribute. See Table 3-20 in Chapter 3 for a complete listing of plot attributes.
	attributeValue	depends on the attribute	The value of the specified plot attribute. See Table 3-20 in Chapter 3 type of for a complete listing of plot attributes.

#### Return Value

status integer Refer to Appendix A for error codes.	
---	--

#### **SetPrintAttribute**

int status = SetPrintAttribute (int printAttribute, int attributeValue);

### **Purpose**

Sets the value of the selected print attribute.

#### **Parameters**

Input	printAttribute	integer	A particular print attribute. See Table 3-27 in Chapter 3 for a complete listing of print attributes.
	attributeValue	integer	The new value of the print attribute. See Table 3-27 in Chapter 3 for a complete listing of print attribute values.

#### **Return Value**

<b>status</b> intege	Refer to Appendix A for error codes.
----------------------	--------------------------------------

# **SetSleepPolicy**

int status = SetSleepPolicy (int sleepPolicy);

#### **Purpose**

Each time the User Interface Library checks for an event from the operating system, it may put your program in the background ("to sleep") for a specified period of time. The benefit is that other applications are given more processor time. The disadvantage is that your program may run slower.

This function sets the degree your program "sleeps" when checking for events. The setting that is optimal for your program depends on the operating system you are using and the other applications you are running. If you think you may need to make an adjustment, try the different settings and observe the resulting behavior.

#### **Parameters**

Input	sleepPolicy	integer	The degree to which your program periodically sleeps
			each time the User Interface Library checks for events from the operating system.

#### **Return Value**

status integer	Refer to Appendix A for error codes.
----------------	--------------------------------------

### **Parameter Discussion**

Sleep policy may be one of the following:

VAL_SLEEP_NONE	1	Never be put to sleep. The default value.
VAL_SLEEP_SOME	2	Be put to sleep a small period.
VAL_SLEEP_MORE	3	Be put to sleep for a longer period.

# SetSystemAttribute

int status = SetSystemAttribute (int systemAttribute, ...);

# **Purpose**

Sets the value of a particular system attribute.

#### **Parameters**

Input	systemAttribute	integer	ATTR_ALLOW_UNSAFE_TIMER_EVENTS ATTR_REPORT_LOAD_FAILURE ATTR_ALLOW_MISSING_CALLBACKS
	attributeValue	depends on the attribute	The value of the specified attribute. See Table 3-26 for values associated with this attribute.

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

# **SetSystemPopupsAttribute**

int status = SetSystemPopupsAttribute (int popupAttribute, ...);

# **Purpose**

Sets the value of a particular system pop-up attribute. All subsequent system pop-ups inherit the new attribute value.

#### **Parameters**

Input	popupAttribute	integer	ATTR_MOVABLE or ATTR_SYSTEM_MENU_VISIBLE.
	attributeValue	on the	The value of the specified attribute. See Table 3-2 in Chapter 3 for valid values associated with these attributes.

#### **Return Value**

<b>status</b> in	nteger	Refer to Appendix A for error codes.
------------------	--------	--------------------------------------

\_\_\_\_\_

## **SetTraceAttribute**

## **Purpose**

Sets the value of a particular strip chart trace attribute.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
	controlID	integer	The defined constant (located in the .uir header file) which was assigned to the control by the User Interface Editor, or the ID returned by the NewCtrl or DuplicateCtrl function.
	traceNumber	integer	The strip chart trace number may be from 1 to the number of defined strip chart traces. The number of defined strip chart traces is established through editing the strip chart in the User Interface Editor or calling SetCtrlAttribute.
	traceAttribute	integer	Selects a particular strip chart trace attribute. See Table 3-20 in Chapter 3 for a complete listing of trace attributes.
	attributeValue	integer	The current value of the trace attribute.

## **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **SetWaitCursor**

int status = SetWaitCursor (int waitCursorState);

## **Purpose**

Specifies the state of the wait cursor. If the wait cursor is activated, all other cursor styles are overridden to display the wait cursor.

## **Parameters**

Input	waitCursorState	integer	Specifies the state of the wait cursor. When the wait
			cursor is active, all other cursor styles are overridden
			until cursor is deactivated
			1 = wait cursor active
			0 = wait cursor inactive.

#### Return Value

- 11
------

# SuspendTimerCallbacks

int status = SuspendTimerCallbacks (void)

### **Purpose**

This function stops all timer callbacks until a call is made to ResumeTimerCallbacks. The function does not alter the ongoing schedule of timer intervals. It only inhibits the calling of callback functions.

#### **Return Value**

status	integer	Refer to Appendix A for error codes.
--------	---------	--------------------------------------

#### See Also

ResumeTimerCallbacks, ResetTimer

# **UnRegisterWinMsgCallback**

int status = UnRegisterWinMsgCallback (int callbackID);

#### **Purpose**

Note: This function is available only on the Windows version of LabWindows/CVI.

This function registers a callback function that will be called when the LabWindows/CVI application receives the specified Windows message.

#### **Parameters**

Input	callbackID	integer	The ID that was returned in the <b>callbackID</b> parameter
			of RegisterWinMsgCallback.

status	integer	1 = Successfully unregistered the callback function
		0 = Failed to unregister the callback function.

## **ValidatePanel**

int status = ValidatePanel (int panelHandle, int \*valid);

## **Purpose**

Verifies that the value of each numeric control in notify mode is within the range specified in the User Interface Editor or set by the SetCtrlAttribute function using ATTR\_MAX\_VALUE and ATTR\_MIN\_VALUE.

If a control is out of range, a red outline appears around it prompting the user to enter a new value.

When the control has the input focus, a pop-up appears indicating the control's range and default value.

Note: This function is automatically called when a user attempts to generate a commit event on a validate control.

#### **Parameters**

Input	panelHandle	integer	The specifier for a particular panel that is currently in memory. This handle will have been returned by the LoadPanel, NewPanel, or DuplicatePanel function.
Output	valid	integer	A Boolean value indicating whether or not the panel is valid. If valid, then each control is valid. If invalid, then at least one and possibly more controls are invalid.  0 = one or more controls are out of range 1 = all controls are in range.

<b>status</b> inte	ger Refer to Appendix A for error codes.	
--------------------	--	--

# WaveformGraphPopup

## **Purpose**

Plots a waveform on a dialog box.

The values in **YArray** are scaled according to **YGain** and **YOffset**. The **Xaxis** timebase is scaled according to **InitialX** and **XIncrement**. Each point in the plot is computed as follows:

$$x_i = (i * XInc) + InitX$$

$$y_i = (wfm_i * YGain) + Yoff$$

where i is the index of the point in the waveform array.

#### **Parameters**

			<del>,</del>
Input	title	string	The title to be displayed on the dialog box.
	yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType</b> .
numberofPoints into		integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>numberofPoints.</b>
	yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
	yGain	double- precision	Specifies the gain to be applied to the waveform (yArray) data.
	yOffset	double- precision	Specifies a constant offset to be added to the waveform (yArray) data.
	initialX	double- precision	Specifies the initial value for the X axis.
	xIncrement	double- precision	Specifies the increment along the X axis for each new point.

status in	nteger	Refer to Appendix A for error codes.
-----------	--------	--------------------------------------

# **XGraphPopup**

# **Purpose**

Plots an array of X values against its indices along the Y axis in a dialog box.

#### **Parameters**

Input	title	string	The title to be displayed in the dialog box.
	xArray	void *	The array that contains the values to be plotted along the X axis. The data type must be of the type specified by <b>xDataType.</b>
	numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>number of Points.</b>
	xDataType	integer	Specifies the data type of the <b>xArray</b> . See Table 3-11 in Chapter 3 for a list of data types.

#### **Return Value**

status integer Refer to Appendix A for each	rror codes.
---	-------------

# XYGraphPopup

## **Purpose**

Plots an array of Y values against an array of X values in a dialog box.

#### **Parameters**

Input	title	string	The title to be displayed in the dialog box.
	xArray	void *	The array that contains the values to be plotted along the X axis. The data type must be of the type specified
			by <b>xDataType.</b>

(continues)

# **Parameters (Continued)**

yArray	void *	The array that contains the values to be plotted along the Y axis. The data type must be of the type specified by <b>yDataType.</b>
numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>number of Points.</b>
xDataType	integer	Specifies the data type of the <b>xArray</b> . See Table 3-11 in Chapter 3 for a list of data types.
yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.

#### **Return Value**

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **YGraphPopup**

# **Purpose**

Plots an array of Y values against its indices along the X axis in a dialog box.

#### **Parameters**

Input	title yArray	string void *	The title to be displayed on the dialog box.  The array that contains the values to be plotted along
			the Y axis. The data type must be of the type specified by <b>yDataType.</b>
	numberofPoints	integer	The number of points to plot. This value controls the number of points to plot even if the number of elements in <b>xArray</b> is greater than the <b>number of Points.</b>
	yDataType	integer	Specifies the data type of the <b>yArray</b> . See Table 3-11 in Chapter 3 for a list of data types.

<b>status</b> integer	Refer to Appendix A for error codes.
-----------------------	--------------------------------------

# **Chapter 5 LabWindows/CVI Sample Programs**

\_\_\_\_\_\_

When you installed LabWindows/CVI, you had the option to install a collection of sample programs that demonstrate various concepts of the User Interface Library. If you selected this installation option, the programs were copied to the samples subdirectory. These sample programs supplement the information presented in this manual. For more information on User Interface and other example programs, see the samples.doc text file in LabWindows/CVI's main directory.

# **Example Program Files**

Table 5-1 is a quick reference guide outlining the sample programs and the concepts that they illustrate.

Table 5-1. Sample Program Files

Item Number	Project File Name	Program Description
1.	io.prj	Standard I/O
2.	callback.prj	Introduction to Callback Functions
3.	events.prj	User Interface Events
4.	menus.prj	Menus Controlled by Callback Functions
5.	graphs.prj	Graphs
6.	chart prj	Strip Charts
7.	cursors.prj	Graph Cursor
8.	popups.prj	Pop-Up Panels
9.	listbox.prj	Selection Lists
10.	panels.prj	Child Windows
11.	timerctl.prj.	Timer Controls
12.	textbox.prj	Text Boxes

(continues)

Sample Programs Chapter 5

Table 5-1. Sample Program Files (Continued)

Item Number	Project File Name	Program Description
13.	picture.prj	Using Picture Controls
14.	build.prj	Building a User Interface Programmatically
15.	getusrev.prj	Programming with Event Loops
16.	keyfiltr.prj	Handling Keyboard Input
17.	moustate.prj	Getting the Mouse State
18.	listdelx.prj	Colors in List Boxes
19.	2yaxis.prj	Two Y Axes on a Graph
20.	intgraph.prj	Intensity Plots
21.	autostrp.prj	Autoscaling the Y-Axis on a Strip Chart
22.	canvas.prj	Canvas Controls
23.	canvsbmk.prj	Canvas Benchmark
24.	drawpad.prj	Using Canvas as Drawing Pad
25.	piedemo.prj	Pie Chart
26.	imagedit.prj	Changing Image Colors
27.	clipbord.prj	Using System Clipboard

# **Using the Sample Programs**

Each of these sample programs are meant to illustrate a particular feature or concept of the LabWindows/CVI User Interface Library. The source code is meant to be simple and easy to read, so that you can use these sample programs to learn how to use particular controls and event processing concepts, and act as a guideline for developing your own applications.

To examine or run a sample program, load the project file corresponding to the desired sample into the Project Window. Remember, all sample programs are in the samples\userint subdirectory. We recommend that you review the sample programs in the order presented in Table 5-1. The first few samples highlight fundamental concepts for building programs in LabWindows/CVI, while the later samples illustrate more specialized features of the User Interface Library.

Chapter 5 Sample Programs

#### 1. io.prj—Standard I/O

This sample program demonstrates how to display and retrieve information from users through the Standard Input/Output window using the ANSI C stdio library functions.

#### 2. callback.prj—Introduction to Callback Functions

This sample program demonstrates how to use callback functions to respond to events generated on a LabWindows/CVI user interface.

## 3. events.prj—User Interface Events

This sample program demonstrates how you can respond to multiple events generated from a single control on the user interface. For example, this sample demonstrates how your programs can recognize the difference between a left mouse click and right mouse click occurring on a panel. This sample also shows how to gain access to supplementary event information, such as the X and Y-coordinates of the mouse cursor when the click occurred.

#### 4. menus.prj—Menus Controlled by Callback Functions

This sample illustrates some of the ways that you can build menus in the menu editor in the User Interface Editor, and how to respond to these menu selections through a menu callback function.

#### 5. graphs.prj—Graphs

This sample demonstrates the various graphing routines available in the User Interface Library.

#### 6. chart.prj—Strip Charts

This sample demonstrates how to display multiple traces on a strip chart control.

#### 7. cursors.prj—Graph Cursors

This sample program demonstrates how to use cursors for zooming operations on a graph control, and how to use snap-to-point cursor to get X- and Y-coordinate information from the graph.

#### 8. popups.prj—Pop-Up Panels

This sample program demonstrates the various pop-up panel controls available in the LabWindows/CVI User Interface Library.

Sample Programs Chapter 5

#### 9. listbox.prj—Selection Lists

This sample program demonstrates how to select, add, and delete items from a list box control programmatically.

#### 10. panels.prj—Child Windows

This sample program demonstrates how you can define and display child windows in LabWindows/CVI.

#### 11. timerctl.prj—Timer Controls

This sample program demonstrates how you can use a timer control to perform a particular action continuously without being affected by other user interface operations. For example, you can plot data to a strip chart continuously without hesitation, even when a menu bar is pulled down, or a panel is popped up on top of the strip chart.

## 12. textbox.prj—Text Boxes

This sample program demonstrates how you can use a text box control to display help and status information. You see the fundamental actions you can perform on a text box such as adding a new line of text, inserting a line of text, and deleting text.

#### 13. picture.prj—Using Picture Controls

This sample program illustrates how you can use picture controls to enhance a user interface. The program contains two PCX images imported into two picture controls. One image sits on top of and covers the other. A left click event on the picture control causes a callback function to bring the hidden image to the foreground, covering the other image. You could follow the example of this sample program to create a toggle button that has different images for the on and off states.

## 14. build.prj—Building a User Interface Programmatically

This sample program demonstrates how to build a user interface from your program using the NewPanel and NewCtrl functions, and how to install callback functions manually with the InstallCtrlCallback function. It also illustrates how to change customize controls programmatically using the SetCtrlAtrribute function.

Chapter 5 Sample Programs

#### 15. getusrev.prj—Programming with Event Loops

This sample program demonstrates the event loop programming model. Although the callback function model is much more flexible and easy to use, you can use the event loop model in certain applications, such as modal dialog boxes. LabWindows for DOS uses the event loop model exclusively. Thus, programs translated from LabWindows for DOS to LabWindows/CVI use the event loop model unless you restructure the program to use the callback model.

#### 16. keyfiltr.prj—Handling Keyboard Input

This sample program demonstrates how you can make a control respond to keypress events. The program displays a string control that is configured to handle keyboard input according to options selected on the main panel of this example project.

#### 17. moustate.prj—Getting the Mouse State

This sample program demonstrates how to use the GetGlobalMouseState and GetRelativeMouseState functions. You can use these functions to determine the current position of the mouse, the current state of the mouse buttons, and the current state of the <Shift> and <Ctrl> keys on the keyboard.

#### 18. listdelx.prj—Colors in List Boxes

This sample program demonstrates how you can add items of different colors to a list box control. Escape characters that you add to a string can control its background and foreground colors as well as the positioning in the list box. (A list of the available escape sequences appears in the help for the **itemLabel** parameter in the InsertListItem function panel.)

#### 19. 2yaxis.prj - Two Y Axes on a Graph

This sample program shows how to use left and right Y axes on the same graph and how graph cursors can be assigned to the two axes.

#### 20. intgraph.prj - Intensity Plots

This sample program demonstrates the different ways in which intensity plots can be used in a graph. It allows you to experiment with the different interpolation options as you plot a semi-random block of data.

Sample Programs Chapter 5

## 21. autostrp.prj - Autoscaling the Y-Axis on a Strip Chart

This sample program demonstrates how you can autoscale the Y-axis on a strip chart. The User Interface Library supports autoscaling only on graphs, not on strip charts. This program simulates autoscaling by storing the data before sending it to the chart, and the using SetAxisRange to modify the Y-axis as needed.

#### 22. canvas.prj - Canvas Controls

This sample program demonstrates drawing on a Canvas control, including objects such as arcs, rectangles, polygons, lines, ovals and bitmaps.

#### 23. canvsbmk.prj - Canvas Benchmark

This sample program shows the increase in speed you can achieve by using a canvas control instead of a graph control for drawing objects such as arcs, rectangles, polygons, lines, ovals and bitmaps.

#### 24. drawpad.prj - Using Canvas as Drawing Pad

This sample program demonstrates how to use a canvas control as a drawing port or scratch pad for the mouse.

#### 25. piedemo.prj - Pie Chart

This sample program demonstrates how to use a canvas control to draw a pie chart using an instrument driver.

#### 26. imagedit.prj - Changing Image Colors

This is a very simple program which modifies the colors of an existing image. It loads an image into a picture ring and then makes use of the GetImageBits and SetImageBits functions.

#### 27. clipbord.prj - Using System Clipboard

This sample program demonstrates how to use the clipboard functions to transfer images and text to and from the system clipboard.

# **Appendix A Error Conditions**

This appendix lists the meanings associated with the integer error codes that the LabWindows/CVI User Interface library functions return.

Every function returns an integer code representing the result of the call. If the return code is negative, an error has occurred. Otherwise, the function successfully completed.

Note: The GetUILErrorString function can convert an error code number into a message string.

Table A-1. User Interface Library Error Codes

Code	Error Message
-1	The Interface Manager could not be opened.
-2	The system font could not be loaded.
-3	The operation attempted cannot be performed while a pop-up menu is active.
-4	Panel, pop-up, menu bar, or plot ID is invalid.
-5	Attempted to position panel at an invalid location
-6	Attempted to make an inoperable control the active control.
-7	The operation requires that a panel be loaded.
-8	The operation requires that a pop-up menu be active.
-9	The operation requires that a menu bar be loaded.
-10	The control is not the type expected by the function.
-11	Invalid menu item ID.
-12	Out of memory!
-13	Invalid control ID.
-14	Value is invalid or out of range.
-15	File is not a User Interface file or has been corrupted.
-16	File format is out-of-date.

Error Conditions Appendix A

Appendix A Error Conditions

Table A-1. User Interface Library Error Codes (Continued)

Code	Error Message
-17	PCX image is corrupted or incompatible with current display type.
-18	No user event possible in current configuration.
-19	Unable to open UIR file.
-20	Error reading UIR file.
-21	Error writing UIR file.
-22	Error closing UIR file.
-23	Panel state file has invalid format.
-24	Invalid panel ID or menu bar ID in resource file.
-25	Error occurred during hardcopy output.
-26	Invalid default directory specified in FileSelectPopup function.
-27	Operation is invalid for specified object.
-28	Unable to find specified string in menu.
-29	Palette menu items can only be added to the end of the menu.
-30	Too many menus in the menu bar.
-31	Separators cannot have checkmarks.
-32	Separators cannot have submenus.
-33	The menu item must be a separator.
-34	The menu item cannot be a separator.
-35	The menu item already has a submenu.
-36	The menu item does not have a submenu.
-37	The control ID passed must be a menu ID, a menu item ID, or NULL.
-38	The control ID passed must be a menu ID, or a menu item ID.
-39	The control ID passed was not a submenu ID.
-40	The control ID passed was not a valid ID.

Error Conditions Appendix A

Table A-1. User Interface Library Error Codes (Continued)

Code	Error Message		
-41	The ID is not a menu bar ID.		
-42	The ID is not a panel ID.		
-43	This operation cannot be performed while this pop-up panel is active.		
-44	This control/panel/menu/ does not have the specified attribute.		
-45	The control type passed was not a valid type.		
-46	The attribute passed is invalid.		
-47	The fill option must be set to fill above or fill below to paint ring slide's fill color.		
-48	The fill option must be set to fill above or fill below to paint numeric slide's fill color.		
-49	The control passed is not a ring slide.		
-50	The control passed is not a numeric slide.		
-51	The control passed is not a ring slide with inc/dec arrows.		
-52	The control passed is not a numeric slide with inc/dec arrows.		
-53	The data type passed in is not a valid data type for the control.		
-54	The attribute passed is not valid for the data type of the control.		
-55	The index passed is out of range.		
-56	There are no items in the list control.		
-57	The buffer passed was to small for the operation.		
-58	The control does not have a value.		
-59	The value passed is not in the list control.		
-60	The control passed must be a list control.		
-61	The control passed must be a list control or a binary switch.		
-62	The data type of the control passed must be set to a string.		
-63	That attribute is not a settable attribute.		
-64	The value passed is not a valid mode for this control.		

Appendix A Error Conditions

Table A-1. User Interface Library Error Codes (Continued)

Code	Error Message		
-65	A NULL pointer was passed when a non-NULL pointer was expected.		
-66	The text background color on a menu ring cannot be set or gotten.		
-67	The ring control passed must be one of the menu ring styles.		
-68	Text cannot be colored transparent.		
-69	A value cannot be converted to the specified data type.		
-70	Invalid tab order position for control.		
-71	The tab order position of an indicator-only control cannot be set.		
-72	Invalid number.		
-73	There is no menu bar installed for the panel.		
-74	The control passed is not a text box.		
-75	Invalid scroll mode for chart.		
-76	Invalid image type for picture.		
-77	The attribute is valid for child panels only. Some attributes of top level panels are determined by the host operating system.		
-78	The list control passed is not in check mode.		
-79	The control values could not be completely loaded into the panel because the panel has changed.		
-80	Maximum value must be greater than minimum value.		
-81	Graph does not have that many cursors.		
-82	Invalid plot.		
-83	New cursor position is outside plot area.		
-84	The length of the string exceeds the limit.		
-85	The specified callback function does not have the required prototype.		
-86	The specified callback function is not a known function.		

Error Conditions Appendix A

Table A-1. User Interface Library Error Codes (Continued)

Code	Error Message
-87	Graph cannot be in this mode without cursors.
-88	Invalid axis scaling mode for chart.
-89	The font passed is not in font table.
-90	The attribute value passed is not valid.
-91	Too many files are open.
-92	Unexpectedly reached end of file.
-93	Input/Output error.
-94	File not found.
-95	File access permission denied.
-96	File access is not enabled.
-97	Disk is full.
-98	File already exists.
-99	File already open.
-100	Badly formed pathname.
-101	File is damaged.
-102	The format of the resource file is too old to read.
-103	File is corrupted.
-104	The operation could not be performed.
-105	The control passed is not a ring knob, dial, or gauge.
-106	The control passed is not a numeric knob, dial, or gauge.
-107	The count passed is out of range.
-108	The keycode is not valid.
-109	The picture control has no image.
-110	Panel background cannot be colored transparent.

Appendix A Error Conditions

Table A-1. User Interface Library Error Codes (Continued)

Code	Error Message
-111	Title background cannot be colored transparent.
-112	Not enough memory for printing.
-113	The shortcut key passed is reserved.
-114	The format of the file is newer than this version of CVI.
-115	System printing error.
-116	Driver printing error.
-117	The deferred callback queue is full.
-118	The mouse cursor passed is invalid.
-119	Printing functions are not reentrant.
-120	Out of Windows GDI space.
-121	The panel must be visible.
-122	The control must be visible.
-123	The attribute is not valid for the type of plot.
-124	Intensity plots cannot use transparent colors.
-125	Color is invalid.
-126	The specified callback function differs only by a leading underscore from another function or variable. Change one of the names for proper linking.
-127	Bitmap is invalid.
-128	There is no image in the control.

# Appendix B

# **Customer Communication**

For your convenience, this appendix contains forms to help you gather the information necessary to help us solve technical problems you might have as well as a form you can use to comment on the product documentation. Filling out a copy of the *Technical Support Form* before contacting National Instruments helps us help you better and faster.

National Instruments provides comprehensive technical assistance around the world. In the U.S. and Canada, applications engineers are available Monday through Friday from 8:00 a.m. to 6:00 p.m. (central time). In other countries, contact the nearest branch office. You may fax questions to us at any time.

## **Electronic Services**



## **Bulletin Board Support**

National Instruments has BBS and FTP sites dedicated for 24-hour support with a collection of files and documents to answer most common customer questions. From these sites, you can also download the latest instrument drivers, updates, and example programs. For recorded instructions on how to use the bulletin board and FTP services and for BBS automated information, call (512) 795-6990. You can access these services at:

- United States: (512) 794-5422 or (800) 327-3077
   Up to 14,400 baud, 8 data bits, 1 stop bit, no parity
- United Kingdom: 01635 551422 Up to 9,600 baud, 8 data bits, 1 stop bit, no parity
- France: 1 48 65 15 59 Up to 9,600 baud, 8 data bits, 1 stop bit, no parity



## **FaxBack Support**

FaxBack is a 24-hour information retrieval system containing a library of documents on a wide range of technical information. You can access FaxBack from a touch-tone telephone at the following number: (512) 418-1111.

Customer Communication Appendix B



## **FTP Support**

To access our FTP site, log on to our Internet host, ftp.natinst.com, as anonymous and use your Internet address, such as joesmith@anywhere.com, as your password. The support files and documents are located in the /support directories.



## E-Mail Support (currently U.S. only)

You can submit technical support questions to the appropriate applications engineering team through e-mail at the Internet addresses listed below. Remember to include your name, address, and phone number so we can contact you with solutions and suggestions.

GPIB: gpib.support@natinst.com DAQ: daq.support@natinst.com VXI: vxi.support@natinst.com LabVIEW: lv.support@natinst.com LabWindows: lw.support@natinst.com HiO: hiq.support@natinst.com Lookout: lookout.support@natinst.com VISA: visa.support@natinst.com

# **Fax and Telephone Support**

National Instruments has branch offices all over the world. Use the list below to find the technical support number for your country. If there is no National Instruments office in your country, contact the source from which you purchased your software to obtain support.

	Telephone	Fax
Australia	03 9 879 9422	03 9 879 9179
Austria	0662 45 79 90 0	0662 45 79 90 19
Belgium	02 757 00 20	02 757 03 11
Canada (Ontario)	519 622 9310	
Canada (Quebec)	514 694 8521	514 694 4399
Denmark	45 76 26 00	45 76 26 02
Finland	90 527 2321	90 502 2930
France	1 48 14 24 24	1 48 14 24 14
Germany	089 741 31 30	089 714 60 35
Hong Kong	2645 3186	2686 8505
Italy	02 413091	02 41309215
Japan	03 5472 2970	03 5472 2977
Korea	02 596 7456	02 596 7455
Mexico	95 800 010 0793	5 520 3282
Netherlands	0348 433466	0348 430673
Norway	32 84 84 00	32 84 86 00
Singapore	2265886	2265887
Spain	91 640 0085	91 640 0533
Sweden	08 730 49 70	08 730 43 70
Switzerland	056 200 51 51	056 200 51 55
Taiwan	02 377 1200	02 737 4644
U.K.	01635 523545	01635 523154

# **Technical Support Form**

Photocopy this form and update it each time you make changes to your software or hardware, and use the completed copy of this form as a reference for your current configuration. Completing this form accurately before contacting National Instruments for technical support helps our applications engineers answer your questions more efficiently.

If you are using any National Instruments hardware or software products related to this problem, include the configuration forms from their user manuals. Include additional pages if necessary.

Name					
Company					
Address					
Fax ()_			Phone	()	
Computer brand		Model		Processor	
Operating system: Windows 95, other			kgroups 3.11,	Windows NT 3.1,	Windows NT 3.5,
Version of Excel (le	ook at Excel's A	bout box): 5.0, 5.0	c, other		
Clock Speed	MHz	RAM	MB	Display ada	pter
Mouseyes	no	Other adapters in	stalled		
Hard disk capacity	MB	Brand			
Instruments used					
National Instrumen	ts hardware prod	uct model		Revision	
Configuration					
National Instrumen	ts software prod	ict		Version	
Configuration					
The problem is					
List any error mess	ages				
The following steps	s will reproduce	the problem _			
	1				

# **Hardware and Software Configuration Form**

Record the settings and revisions of your hardware and software on the line to the right of each item. Complete a new copy of this form each time you revise your software or hardware configuration, and use this form as a reference for your current configuration. When you complete this form accurately before contacting National Instruments for technical support, our applications engineers can answer your questions more efficiently.

**National Instruments Products** 

Data Acquisition Hardware Revision
Interrupt Level of Hardware
DMA Channels of Hardware
Base I/O Address of Hardware
NI-DAQ, LabVIEW, or LabWindows Version
Other Products
Computer Make and Model
Microprocessor
Clock Frequency
Type of Video Board Installed
Operating System
Operating System Version
Operating System Mode
Programming Language
Programming Language Version
Other Boards in System
Base I/O Address of Other Boards
DMA Channels of Other Boards
Interrupt Level of Other Boards

# **Documentation Comment Form**

Edition Date:

**July 1996** 

National Instruments encourages you to comment on the documentation supplied with our products. This information helps us provide quality products to meet your needs.

LabWindows®/CVI User Interface Reference Manual

Part Number: 320683C-01 Please comment on the completeness, clarity, and organization of the manual. If you find errors in the manual, please record the page numbers and describe the errors. Thank you for your help. Name\_\_\_\_\_ Company\_\_\_\_\_ Fax Phone Mail to: Technical Publications Fax to: Technical Publications National Instruments Corporation National Instruments Corporation 6504 Bridge Point Parkway, MS 53-02 MS 53-02 Austin, TX 78730-5039 (512) 794-5678

# Glossary

Prefix	Meaning	Value
m-	milli-	10-3
μ-	micro-	10-6

B

binary switch A control that selects between two states: on and off.

bitmap A set of data that can be used to draw a graphic image. The data

consist of information determining the height and width of the image

or pixel grid, and the color of each pixel.

bps Bits per second.

 $\mathbf{C}$ 

canvas An arbitrary drawing surface to display text, shapes, and bitmap

images.

CodeBuilder The LabWindows/CVI feature that creates code based on a .uir file

to connect your GUI to the rest of your program. This code can be

compiled and run as soon as it is created.

confirm pop-up panel Allows you to confirm an action before it is taken.

control An object that resides on a panel and provides a mechanisms for

accepting input from and displaying information to the user.

 $\mathbf{E}$ 

event Informs the application program that the user has performed an action.

An event is generated whenever the user selects a command from the menu bar or manipulates a control that was configured to generate

events.

 $\mathbf{F}$ 

file select pop-up panel A predefined pop-up panel that displays a list of files on disk from

which the user can select.

 $\mathbf{G}$ 

graph control Displays graphical data as one or more plots.

graph pop-up panel A predefined pop-up panel for displaying numerical data graphically.

There are different functions for graphing X, Y, X-Y, and waveform

data sets.

H

hot control Similar to normal control except that the control generates an event

when acted upon by the user. Events are returned to the application program, which must determine what action to take. Normally, a hot control generates an event when its state is changed. For example, if the user moves a binary switch from off to on, an event is generated.

I

immediate command A menu title that ends in an exclamation point does not have an

associated menu. Selecting an immediate command executes it

directly.

in inches.

indicator control A control that can be changed programmatically but cannot be

operated by the user. LED, scale, text, text box, graph (without

cursors), and strip chart controls are always indicators.

L

LED A control that is modeled to operate like light emitting diodes, which

indicate on/off states. When an LED is on, it appears lighted.

 $\mathbf{M}$ 

MB Megabytes of memory.

menu bar A mechanism for encapsulating a set of commands. A menu bar

appears at the top of the screen and contains a set of menu titles.

message pop-up panel A predefined pop-up panel for displaying a message.

N

normal control A control that can be operated by the user and changed

programmatically.

numeric/string control Used to input or view numeric values or text strings. A typical use of

this control might be to input a person's name or to display a voltage

value.

P

panel A rectangular region of the screen containing a set of controls that

accept input from the user and display information to the user. Panels can perform many different functions, from representing the front panel of an instrument to allowing the user to select a file name.

pen A drawing construct which defines the characteristics to be used to

draw images on a canvas control. The settable attributes include width,

style, color, mode and pattern of the line or object drawn.

pixel An element of a picture. The smallest resolvable rectangular area of an

image, either on a screen or stored in memory. Each pixel has its own brightness and color, usually represented as a red, green, and blue

intensities (see RGB).

point A structure used to specify the location of a point in the Cartesian

coordinate systems used in canvas controls and bitmaps. The structure

contains two integer values, x and y.

plot Consists of a curve, a point, a geometric shape, or a text string.

pop-up panel A panel that pops up, accepts user input, and then disappears.

prompt pop-up panel A predefined pop-up panel for requesting input from the user.

pull-down menu A menu title without an exclamation point contains a collection of

commands that appear when you select it.

push button Used to trigger an action indicated by a label on the button.

R

radio button Similar to binary switches, these buttons allow you to switch between

the off and on state. A radio button is either pressed in or popped out.

rect A structure used to specify the location and size of a rectangle in the

Cartesian coordinate systems used in canvas controls and bitmaps. The structure contains four integer values, top, left, height, and

width.

resource file Contains all of the object associated with a user interface. This

includes menu bars, panels, controls, pop-up panels, preferences, images, and fonts. To display user interface objects, an application program must call the User Interface Library to load them from the resource file. A single application program can use multiple resource

files.

RGB Red-green-blue. The three colors of light which can be mixed to

produce any other color.

ring control Allows you to select from a group of items. Only the currently

selected item shows. You can scroll forward or backward through the list of items, or you can select an item through its pop-up format.

S

s Seconds.

scale control Indicates the magnitude of a value relative to a predefined range. The

scale moves up and down within the control as its value changes. Scale controls are indicator controls and cannot be operated.

selection list control Used to select a item from a list.

slide control Allows you to select one item from a group of items. The slider, or

cross-bar, indicates the current selection.

slider The cross-bar of the slide control that points to the currently selected

item.

standard libraries The LabWindows Graphics, Analysis, Formatting and I/O, GPIB,

GPIB-488.2, RS-232, and System libraries.

string control See *numeric/string control*.

strip chart control A graph that displays graphical data as one or more traces in real time.

stylized fonts Fixed-size, bitmapped fonts that have a variety of type faces.

system fonts Bitmapped fonts designed for a particular display adapter. They are

sized to fit the standard 80-column by 25-line display format. The User Interface Library automatically selects the appropriate system

font for your adapter.

T

text boxes Display a window of text.

text controls Display a string of text.

timer control A user interface control that schedules the periodic execution of a

callback function. A typical use of this control might be to update a

graph every second.

traces Curves in strip charts.

U

User Interface Editor Used to create resource files.

V

validate control Similar to hot control except that all numeric/scalar controls on the

panel are validated before the event is generated. The value of each numeric/scalar control is checked against its predefined range. If an invalid condition is found, a dialog box appears to inform you.

# **Index**

$\mathbf{A}$	ATTR_ACTIVE_YAXIS, 3-72
	ATTR_ALLOW_MISSING_CALLBACKS,
Add File to Project command, File	3-86
menu, 2-4	ATTR_ALLOW_ROOM_FOR_IMAGES,
Align Horizontal Centers command,	3-39
Arrange menu, 2-21	ATTR_ALLOW_UNSAFE_TIMER_EVENTS,
Alignment command, Arrange menu, 2-20	3-86
to 2-21	ATTR_BACKCOLOR, 3-12
All Callbacks command, Generate	ATTR_BINARY_SWITCH_COLOR, 3-41
menu, 2-27	ATTR_BORDER_VISIBLE, 3-68
All Code command	ATTR_CALLBACK_DATA, 3-12, 3-24,
description, 2-25 to 2-26	3-32
Generate All Code dialog box, 2-25	ATTR_CALLBACK_FUNCTION_POINTER,
AllocBitmapData function, 4-12 to 4-13	3-12, 3-24, 3-32
AllocImageBits function, 4-14 to 4-15	ATTR_CALLBACK_NAME, 3-12, 3-24,
Always Append Code to End option,	3-32
Preferences command, 2-30	ATTR_CALLBACK_NAME_LENGTH,
Apply Default Font command, Edit	3-12, 3-24, 3-32
menu, 2-15	ATTR_CAN_MAXIMIZE, 3-12, 3-17
Arrange menu, User Interface Editor	ATTR_CAN_MINIMIZE, 3-12, 3-17
Align Horizontal Centers	ATTR_CHECK_MODE, 3-39
command, 2-21	ATTR_CHECK_RANGE, 3-37, 3-51
Alignment command, 2-20 to 2-21	ATTR_CHECK_STYLE, 3-40
Center Label command, 2-22	ATTR_CHECKED, 3-25
Control Coordinates command, 2-23	ATTR_CLOSE_CTRL, 3-12
Control ZPlane Order command, 2-22	ATTR_CLOSE_ITEM_VISIBLE, 3-12,
Distribute Vertical Centers	3-17
command, 2-22	ATTR_CMD_BUTTON_COLOR, 3-40
Distribution command, 2-21 to 2-22	ATTR_COLOR_MODE, 3-89, 3-91
illustration, 2-20	ATTR_CONFORM_TO_SYSTEM, 3-13
ASCII keys, 3-26, 4-157 to 4-158	ATTR_CONSTANT_NAME, 3-13, 3-24,
ASCII text format	3-32
loading objects into User Interface	ATTR_CONSTANT_NAME_LENGTH,
Editor window, 2-34	3-13, 3-24, 3-32
saving contents of User Interface Editor	ATTR_COPY_ORIGINAL_DATA, 3-72,
window in, 2-33	3-84 to 3-85
Assign Missing Constants command,	ATTR_CROSS_HAIR_STYLE, 3-74, 3-78
Options menu, 2-33	ATTR_CTRL_INDEX, 3-37
ATTR_ACTIVATE_WHEN_CLICKED_ON,	ATTR_CTRL_MODE, 3-33
3-12	ATTR_CTRL_STYLE, 3-32, 3-46 to 3-50
ATTR_ACTIVE, 3-12	ATTR_CTRL_TAB_POSITION, 3-33

ATTR\_CTRL\_VAL, 3-33 ATTR\_INNER\_LOG\_MARKERS\_VISIBLE, ATTR\_CURSOR\_COLOR, 3-74 3-68 ATTR CURSOR MODE, 3-74 ATTR INTERPOLATE PIXELS, 3-75 ATTR\_CURSOR\_POINT\_STYLE, 3-74, ATTR\_INTERVAL, 3-44, 3-64 3-78 to 3-79 ATTR IS SEPARATOR, 3-25 ATTR ITEM NAME, 3-25 ATTR CURSOR YAXIS, 3-74 ATTR DATA MODE, 3-72, 3-84 ATTR ITEM NAME LENGTH, 3-25 ATTR\_DATA\_TYPE, 3-36, 3-50 ATTR\_LABEL\_BGCOLOR, 3-35 ATTR DFLT INDEX, 3-37 ATTR LABEL BOLD, 3-34 ATTR DFLT VALUE, 3-37 ATTR LABEL COLOR, 3-34 ATTR\_DIG\_DISP\_HEIGHT, 3-42 ATTR\_LABEL\_FONT, 3-34 ATTR\_DIG\_DISP\_LEFT, 3-42 ATTR\_LABEL\_FONT\_NAME\_LENGTH, ATTR DIG DISP TOP, 3-42 3-34 ATTR\_DIG\_DISP\_WIDTH, 3-42 ATTR\_LABEL\_HEIGHT, 3-35 ATTR DIMMED, 3-13, 3-24, 3-32 ATTR LABEL ITALIC, 3-34 ATTR LABEL JUSTIFY, 3-35 ATTR DRAW LIGHT BEVEL, 3-25 ATTR\_DRAW\_POLICY, 3-56, 3-57 ATTR LABEL LEFT, 3-35 ATTR DUPLEX, 3-89, 3-90 ATTR LABEL POINT SIZE, 3-34 ATTR\_EDGE\_STYLE, 3-68 ATTR\_LABEL\_RAISED, 3-35 ATTR EJECT AFTER, 3-89, 3-90 ATTR LABEL SIZE TO TEXT, 3-35 ATTR\_ENABLE\_ZOOMING, 3-72 ATTR\_LABEL\_STRIKEOUT, 3-34 ATTR\_ENABLED, 3-44, 3-64, 3-65 ATTR\_LABEL\_TEXT, 3-34 ATTR ENTER IS NEWLINE, 3-38 ATTR LABEL TEXT LENGTH, 3-34 ATTR\_LABEL\_TOP, 3-35 ATTR\_EXTRA\_LINES, 3-38 ATTR\_FILL\_COLOR, 3-42 ATTR\_LABEL\_UNDERLINE, 3-34 ATTR FILL HOUSING COLOR, 3-43 ATTR LABEL VISIBLE, 3-34 ATTR\_FILL\_OPTION, 3-43 ATTR LABEL WIDTH, 3-35 ATTR\_FIRST\_CHILD, 3-13 ATTR\_LEFT, 3-14, 3-33 ATTR FIRST VISIBLE LINE, 3-39 ATTR LINE STYLE, 3-74, 3-79 ATTR FIT MODE, 3-44 ATTR\_MARKER\_END\_ANGLE, 3-43 ATTR\_MARKER\_START\_ANGLE, 3-43 ATTR FLOATING, 3-13 ATTR FORMAT, 3-37, 3-51 ATTR MARKER STYLE, 3-42 ATTR FRAME COLOR, 3-13, 3-34 ATTR MAX ENTRY LENGTH, 3-38 ATTR\_FRAME\_STYLE, 3-13, 3-18 to 3-19 ATTR\_MAX\_VALUE, 3-37 ATTR FRAME THICKNESS, 3-13 ATTR MENU ARROW COLOR, 3-43 ATTR\_FRAME\_VISIBLE, 3-44 ATTR\_MENU\_BAR\_VISIBLE, 3-14 ATTR GRAPH BGCOLOR, 3-68 ATTR MENU HEIGHT, 3-14 ATTR\_GRID\_COLOR, 3-68 ATTR\_MENU\_NAME, 3-25 ATTR\_HEIGHT, 3-13, 3-33 ATTR\_MENU\_NAME\_LENGTH, 3-25 ATTR HILITE CURRENT ITEM, 3-40 ATTR MIN VALUE, 3-37 ATTR\_HSCROLL\_OFFSET, 3-13, 3-38 ATTR\_MOUSE\_CURSOR, 3-14, 3-19 ATTR HSCROLL OFFSET MAX, 3-13 ATTR MOVABLE, 3-14 ATTR IMAGE FILE, 3-45 ATTR NEEDLE COLOR, 3-42 ATTR IMAGE FILE LENGTH, 3-45 ATTR NEXT CTRL, 3-33 ATTR\_INCR\_VALUE, 3-37 ATTR\_NEXT\_PANEL, 3-14 ATTR NO EDIT TEXT, 3-40

ATTR\_NSCROLL\_OFFSET\_MAX, 3-37 ATTR\_PLOT\_ORIGIN, 3-75, 3-81 ATTR\_NUM\_CHILDREN, 3-14 ATTR\_PLOT\_SNAPPABLE, 3-75 ATTR NUM COPIES, 3-89 ATTR\_PLOT\_STYLE, 3-74, 3-80 ATTR\_NUM\_CTRLS, 3-14 ATTR\_PLOT\_XDATA, 3-76 ATTR\_NUM\_CURSORS, 3-72 ATTR\_PLOT\_XDATA\_SIZE, 3-77 ATTR\_PLOT\_XDATA\_TYPE, 3-76 ATTR NUM MENU ITEMS, 3-25 ATTR NUM MENUS, 3-25 ATTR PLOT YAXIS, 3-75 ATTR\_NUM\_POINTS, 3-75 ATTR\_PLOT\_YDATA, 3-76 ATTR NUM TRACES, 3-73 ATTR PLOT YDATA SIZE, 3-77 ATTR OFF COLOR, 3-41 ATTR PLOT YDATA TYPE, 3-76 ATTR\_OFF\_TEXT, 3-41 ATTR\_PLOT\_ZDATA, 3-76 ATTR\_PLOT\_ZDATA\_SIZE, 3-77 ATTR\_OFF\_TEXT\_LENGTH, 3-41 ATTR\_OFF\_VALUE, 3-41 ATTR\_PLOT\_ZDATA\_TYPE, 3-76 ATTR\_OFF\_VALUE\_LENGTH, 3-41 ATTR\_PLOT\_ZPLANE\_POSITION, 3-76 ATTR\_ON\_COLOR, 3-41 ATTR POINTS PER SCREEN, 3-73 ATTR ON TEXT, 3-41 ATTR PRECISION, 3-37 ATTR\_ON\_TEXT\_LENGTH, 3-41 ATTR\_REFRESH\_GRAPH, 3-72, 3-83 ATTR ON VALUE, 3-41 ATTR REPORT LOAD FAILURE, 3-86, ATTR\_ON\_VALUE\_LENGTH, 3-41 ATTR SCROLL BAR COLOR, 3-14, ATTR ORIENTATION, 3-89, 3-90 ATTR\_OVERLAPPED, 3-33 3-39 ATTR\_OVERLAPPED\_POLICY, 3-56, ATTR\_SCROLL\_BAR\_SIZE, 3-39 3-58 ATTR SCROLL BARS, 3-15, 3-39 ATTR\_PANEL\_FIRST\_CTRL, 3-14 ATTR\_SCROLL\_MODE, 3-73 ATTR\_PANEL\_MENU\_BAR\_CONSTANT, ATTR\_SHIFT\_TEXT\_PLOTS, 3-73 3-14 ATTR SHORTCUT KEY, 3-25, 3-40 ATTR\_PANEL\_MENU\_BAR\_CONSTANT ATTR\_SHOW\_DIG\_DISP, 3-42 LENGTH, 3-14 ATTR\_SHOW\_INCDEC\_ARROWS, 3-37 ATTR PANEL PARENT, 3-14 ATTR SHOW MORE BUTTON, 3-43 ATTR\_PAPER\_HEIGHT, 3-89, 3-90 ATTR\_SHOW\_RADIX, 3-37 ATTR\_PAPER\_WIDTH, 3-89, 3-90 ATTR\_SHOW\_TRANSPARENT, 3-43 ATTR\_PARENT\_SHARES\_SHORTCUT ATTR SIZABLE, 3-15 KEYS, 3-14 ATTR SIZE TO TEXT, 3-40 ATTR\_PEN\_COLOR, 3-56 ATTR\_SLIDER\_COLOR, 3-42 ATTR PEN FILL COLOR, 3-56 ATTR SLIDER HEIGHT, 3-43 ATTR\_PEN\_MODE, 3-56, 3-58 ATTR\_SLIDER\_WIDTH, 3-43 ATTR PEN PATTERN, 3-56, 3-58 to 3-59 ATTR SMOOTH UPDATE, 3-73, 3-82, ATTR\_PEN\_STYLE, 3-56 3-84 ATTR\_PEN\_WIDTH, 3-57 ATTR\_STRING\_TEXT\_LENGTH, 3-38 ATTR PICT BGCOLOR, 3-44 ATTR SUBIMAGE HEIGHT, 3-45 ATTR\_PLOT\_AREA\_HEIGHT, 3-68 ATTR\_SUBIMAGE\_LEFT, 3-45 ATTR PLOT AREA WIDTH, 3-68 ATTR SUBIMAGE TOP, 3-45 ATTR PLOT BGCOLOR, 3-68 ATTR SUBIMAGE WIDTH, 3-45 ATTR PLOT FONT, 3-75 ATTR SUBMENU ID, 3-25 ATTR\_PLOT\_FONT\_NAME\_LENGTH, ATTR\_SYSTEM\_MENU\_VISIBLE, 3-15 3-75

ATTR\_SYSTEM\_WINDOW\_HANDLE, ATTR\_VISIBLE\_LINES, 3-39 3-15, 3-17 ATTR\_VSCROLL\_OFFSET, 3-16 ATTR TAB INTERVAL, 3-89 ATTR\_VSCROLL\_OFFSET\_MAX, 3-16 ATTR TEXT BGCOLOR, 3-36 ATTR\_WIDTH, 3-16, 3-33 ATTR\_WINDOW\_ZOOM, 3-16, 3-17 ATTR TEXT BOLD, 3-35 ATTR TEXT CLICK TOGGLES CHEC ATTR\_WRAP\_MODE, 3-38 K. 3-39, 3-40 ATTR XAXIS GAIN, 3-69 ATTR\_TEXT\_COLOR, 3-35 ATTR\_XAXIS\_OFFSET, 3-69 ATTR TEXT FONT, 3-35 ATTR XCOORD AT ORIGIN, 3-57 ATTR TEXT FONT\_NAME\_LENGTH, ATTR XDIVISIONS, 3-69 3-36 ATTR\_XENG\_UNITS, 3-69 ATTR\_TEXT\_ITALIC, 3-36 ATTR\_XFORMAT, 3-69 ATTR TEXT JUSTIFY, 3-36 ATTR XGRID VISIBLE, 3-69 ATTR\_TEXT\_POINT\_SIZE, 3-36 ATTR\_XLABEL\_VISIBLE, 3-69 ATTR TEXT RAISED, 3-40 ATTR\_XMAP\_MODE, 3-73 ATTR TEXT SELECTION LENGTH, ATTR XMARK ORIGIN, 3-73 3-38 ATTR XNAME, 3-69 ATTR TEXT SELECTION START, 3-38 ATTR XNAME LENGTH, 3-70 ATTR\_TEXT\_STRIKEOUT, 3-36 ATTR\_XOFFSET, 3-89, 3-90 ATTR TEXT UNDERLINE, 3-36 ATTR XPRECISION, 3-70 ATTR\_TEXT\_WRAP, 3-89 ATTR\_XRESOLUTION, 3-89, 3-90 ATTR\_TICK\_STYLE, 3-42 ATTR\_XREVERSE, 3-73 ATTR TITLE, 3-15 ATTR XSCALING, 3-57 ATTR\_TITLE\_BACKCOLOR, 3-15 ATTR\_XUSE\_LABEL\_STRINGS, 3-69 ATTR\_TITLE\_BOLD, 3-15 ATTR\_XYLABEL\_BOLD, 3-70 ATTR TITLE COLOR, 3-15 ATTR XYLABEL COLOR, 3-70 ATTR\_TITLE\_FONT, 3-15 ATTR XYLABEL FONT, 3-70 ATTR\_TITLE\_FONT\_NAME\_LENGTH, ATTR\_XYLABEL\_FONT\_NAME\_LENGTH, 3-15 3-70 ATTR\_TITLE\_ITALIC, 3-15 ATTR\_XYLABEL\_ITALIC, 3-70 ATTR TITLE LENGTH, 3-15 ATTR\_XYLABEL\_POINT\_SIZE, 3-71 ATTR TITLE POINT SIZE, 3-15 ATTR\_XYLABEL\_STRIKEOUT, 3-71 ATTR TITLE SIZE TO FONT, 3-16 ATTR XYLABEL UNDERLINE, 3-71 ATTR\_TITLE\_STRIKEOUT, 3-16 ATTR\_XYNAME\_BOLD, 3-71 ATTR XYNAME COLOR, 3-71 ATTR TITLE UNDERLINE, 3-16 ATTR\_TITLEBAR\_THICKNESS, 3-16 ATTR\_XYNAME\_FONT, 3-71 ATTR\_TITLEBAR\_VISIBLE, 3-16 ATTR\_XYNAME\_FONT\_NAME\_LENGTH, ATTR\_TOP, 3-16, 3-33 3-71 ATTR\_TOTAL\_LINES, 3-38 ATTR\_XYNAME\_ITALIC, 3-71 ATTR TRACE BGCOLOR, 3-76 ATTR XYNAME POINT SIZE, 3-71 ATTR\_TRACE\_COLOR, 3-74 ATTR\_XYNAME\_STRIKEOUT, 3-71 ATTR TRACE POINT STYLE, 3-74, ATTR XYNAME UNDERLINE, 3-71 ATTR YAXIS GAIN, 3-69 3-78 to 3-79 ATTR TRACE VISIBLE, 3-74 ATTR YAXIS OFFSET, 3-70 ATTR\_USE\_SUBIMAGE, 3-45 ATTR\_YAXIS\_REVERSE, 3-70 ATTR VISIBLE, 3-16, 3-33 ATTR YCOORD AT ORIGIN, 3-57

ATTR_YDIVISIONS, 3-71	list of attributes (table), 3-68 to 3-77
ATTR_YENG_UNITS, 3-71	plot origins, 3-80 to 3-81
ATTR_YFORMAT, 3-71	plot styles for ATTR_PLOT_STYLE
ATTR_YGRID_VISIBLE, 3-72	(table), 3-80
ATTR_YLABEL_VISIBLE, 3-72	styles for
ATTR_YMAP_MODE, 3-72	ATTR_CURSOR_POINT_STYLE
ATTR_YMARK_ORIGIN, 3-73	and
ATTR_YNAME, 3-72	ATTR_TRACE_POINT_STYLE
ATTR_YNAME_LENGTH, 3-72	(table), 3-78 to 3-79
ATTR_YOFFSET, 3-89, 3-90	two Y axes, 3-81
ATTR_YPRECISION, 3-72	values for ATTR_PLOT_ORIGIN
ATTR_YRESOLUTION, 3-89, 3-90	(table), 3-81
ATTR_YSCALING, 3-57	hard copy, 3-89
ATTR_YUSE_LABEL_STRINGS, 3-70	menu bars
ATTR_ZPLANE_POSITION, 3-16, 3-33	constants for masking three bit fields
attributes	(table), 3-28
canvas controls, 3-56 to 3-59	menu and menu item attributes
ATTR_DRAW_POLICY values	(table), 3-24 to 3-25
(table), 3-57	modifiers and virtual keys for
ATTR_OVERLAPPED_POLICY	shortcut keys (table), 3-26 to 3-27
values (table), 3-58	panels
ATTR_PEN_MODE values	color values (table), 3-17 to 3-18
(table), 3-58	fonts, 3-20 to 3-21
list of attributes (table), 3-56 to 3-57	frame style values, 3-18
pixel values for	geometric attributes (table), 3-18
ATTR_PEN_PATTERN, 3-58	list of attributes (table), 3-12 to 3-16
to 3-59	values and cursor styles for
controls	ATTR_MOUSE-CURSOR
ATTR_CHECK_RANGE values	(table), 3-19
(table), 3-51	picture controls, 3-52 to 3-53
control data types for	appearanc3, 3-51
ATTR_DATA_TYPE (table), 3-50	giving picture controls visual
control styles for	impact, 3-51
ATTR_CTRL_STYLE (table),	system attributes, 3-86 to 3-88
3-46 to 3-50	list of attributes (table), 3-86
list of attributes (table), 3-32 to 3-33	reporting load failures, 3-87 to 3-88
numeric formats for	unsafe timer events, 3-86 to 3-87
ATTR_FORMAT (table), 3-51	timer controls, 3-64 to 3-65
graph and strip chart controls	autoscaling of graph plots, 3-82 to 3-83
cursor styles for	axis label string functions
ATTR_CROSSHAIR_STYLE	ClearAxisItems, 4-46 to 4-47
(table), 3-78	DeleteAxisItem, 4-55 to 4-56
discussion of specific attributes, 3-77	function tree, 4-5
to 3-80	GetAxisItem, 4-82 to 4-83
line styles for ATTR_LINE_STYLE	GetAxisItemLabelLength, 4-83 to 4-84
(table), 3-79	GetNumAxisItems, 4-111
(11010), 3 / /	Och tulli Mishcillo, T 111

InsertAxisItem, 4-128 to 4-129	Edit Panel dialog box, 2-10
ReplaceAxisItem, 4-213 to 4-214	callback functions
axis scale functions	assigning
function tree, 4-5	controls, 1-3
GetAxisRange, 4-84 to 4-85	User Interface Editor vs.
GetAxisScalingMode, 4-86 to 4-87	programmatic method, 3-2
SetAxisRange, 4-224 to 4-226	associated with close controls
SetAxisScalingMode, 4-223 to 4-224	(note), 2-25
	avoiding longjmp function (note), 3-7
D	diagram of callback function
В	concept, 3-5
hatah duamina samusa santuala 2.54	example program, 5-3
batch drawing, canvas controls, 3-54	function reference
binary switch controls	function tree, 4-6 to 4-7
definition, 1-12	InstallCtrlCallback, 4-133 to 4-134
illustration, 1-12	InstallMainCallback, 3-92 to 3-93,
bitmap, offscreen, 3-55	4-135 to 4-136
bitmap functions	InstallMenuCallback, 4-136 to 4-137
AllocBitmapData, 4-12 to 4-13	InstallMenuDimmerCallback, 4-137
DiscardBitmap, 4-61	to 4-138
function tree, 4-8	InstallPanelCallback, 4-138 to 4-139
GetBimapData, 4-87 to 4-89	PostDeferredCall, 3-94, 4-189
GetBitmapFromFile, 4-89 to 4-90	to 4-190
GetBitmapInfo, 4-90 to 4-91	generating code for
GetCtrlBitmap, 4-92 to 4-93	All Callbacks command, 2-27
GetCtrlDisplayBitmap, 4-94 to 4-95	Control Callbacks command, 2-28
GetPanelDisplayBitmap, 4-114 to 4-116	Main Function command, 2-26
NewBitmap, 4-151 to 4-153	to 2-27
SetCtrlBitmap, 4-227 to 4-228	Menu Callbacks command, 2-28
bitmap objects, 3-62 to 3-63	Panel Callbacks command, 2-28
creating, extracting, or discarding, 3-62	precedence of callback functions, 3-91
displaying or copying, 3-63	to 3-92
retrieving image data, 3-63	processing events
Windows metafiles, 3-62 to 3-63	control events, 3-31
Bottom Edges option	menu bar events, 3-23
Alignment command, 2-21	panel events, 3-11
Distribution command, 2-21	pseudocode example, 3-6 to 3-7
Bring Panel to Front command, View	purpose and use, 1-2
menu, 2-19	responding to user interface events, 3-5
bulletin board support, B-1	to 3-7
	swallowing events, 3-92
	timer callbacks, 3-64
C	using InstallMainCallback, 3-92 to 3-93
	windows interrupt support functions
Callback Function field	function tree, 4-7
Edit Control dialog box, 2-11	GetCVITaskHandle, 4-98
Edit Menu Bar dialog box, 2-9	OCIC VII askiialiule, 4-70

GetCVIWindowHandle, 4-98 to 4-99	CanvasDrawText, 4-30 to 4-31
RegisterWinMsgCallback, 4-210	CanvasDrawTextAtPoint, 4-32 to 4-33
to 4-212	CanvasEndBatchDrawing, 4-34
UnRegisterWinMsgCallback, 4-229	CanvasGetClipRect, 4-35
canvas controls, 3-53 to 3-59	CanvasGetPenPosition, 4-35 to 4-36
attributes, 3-56 to 3-59	CanvasGetPixel, 4-36 to 4-37
ATTR_DRAW_POLICY values	CanvasGetPixels, 4-37 to 4-39
(table), 3-57	CanvasInvertRect, 4-39
ATTR_OVERLAPPED_POLICY	CanvasScroll, 4-40 to 4-41
values (table), 3-58	CanvasSetClipRect, 4-41 to 4-42
ATTR_PEN_MODE values	CanvasSetPenPosition, 4-42
(table), 3-58	CanvasStartBatchDraw, 4-43 to 4-44
list of attributes (table), 3-56 to 3-57	CanvasUpdate, 4-44 to 4-45
pixel values for	function tree, 4-5 to 4-6
ATTR_PEN_PATTERN, 3-58	Case Sensitive option, Find UIR Objects
to 3-59	dialog box, 2-18
background color, 3-55	Center Label command, Arrange menu, 2-22
batch drawing, 3-54	Checked field, Edit Menu Bar dialog
canvas coordinate system, 3-54	box, 2-9
clipping, 3-55	CheckListItem function, 4-45 to 4-46
example programs	child panel
canvas benchmark program, 5-6	example program, 5-4
drawing on canvas control, 5-6	purpose and use, 3-11
pie chart, 5-6	ClearAxisItems function, 4-46 to 4-47
using canvas control as drawing port	ClearListCtrl function, 4-47
for mouse, 5-6	ClearStripChart function, 4-47 to 4-48
functions for drawing on canvas, 3-53	clipboard functions
to 3-54	ClipboardGetBitmap, 4-48 to 4-49
offscreen bitmap, 3-55	ClipboardGetText, 4-49
pens, 3-55	ClipboardPutBitmap, 4-49 to 4-50
pixel values, 3-56	ClipboardPutText, 4-50
purpose and use, 1-21	example program, 5-6
canvas functions	function tree, 4-8
CanvasClear, 4-15 to 4-16	clipping, canvas controls, 3-55
CanvasDefaultPen, 4-16 to 4-17	Close command, File menu, 2-4
CanvasDimRect, 4-17 to 4-18	code. See source files.
CanvasDrawArc, 4-18 to 4-19	code generation, automatic. See
CanvasDrawBitmap, 4-20 to 4-21	CodeBuilder.
CanvasDrawLine, 4-21 to 4-22	Code menu, User Interface Editor
CanvasDrawLineTo, 4-23	Generate submenu, 2-24 to 2-28
CanvasDrawOval, 4-24 to 4-25	All Callbacks command, 2-27
CanvasDrawPoint, 4-25	All Code command, 2-25 to 2-26
CanvasDrawPoly, 4-26 to 4-27	Control Callbacks command, 2-28
CanvasDrawRectangle, 4-27 to 4-28	enabled commands (note), 2-24
CanvasDrawRoundedRectangle, 4-28	Generate Code dialog box, 2-24
to 4-29	illustration, 2-24

Main Function command, 2-26	confirm pop-up panel, 1-23
to 2-27	ConfirmPopup function, 4-51 to 4-52
Menu Callbacks command, 2-28	Constant Name Assignment section, User
Panel Callback command, 2-28	Interface Editor Preferences dialog box,
illustration, 2-23	2-32 to 2-33
Preferences command, 2-20 to 2-30	Constant Name field
Always Append Code to End	Edit Control dialog box, 2-11
option, 2-30	Edit Menu Bar dialog box, 2-8 to 2-9
Default Control Events option, 2-30	Edit Panel dialog box, 2-9
Default Panel Events option, 2-30	constant names, assigning
Set Target File command, 2-23 to 2-24	Assign Missing Constants command,
View command, 2-28 to 2-29	Options menu, 2-33
CodeBuilder	constant name separator (_), 3-3
creating source code for GUI, 1-4 to 1-5	constant prefixes, 3-2 to 3-3
overview, 2-2 to 2-3	controls, 1-3, 3-3
Color Preferences section, User Interface	menu bars, 3-3
Editor Preferences dialog box, 2-32	menu items, 3-3
Coloring tool, 2-2	menus, 3-3
colors	rules for User Interface Editor, 3-2 to 3-
background color for canvas	3
controls, 3-55	User Interface Editor method, 3-2 to 3-3
common color values for panel attributes	constant prefix, assigning
(table), 3-17 to 3-18	menus, 3-3
example program	panels, 3-2 to 3-3
changing image colors, 5-6	Control Appearance section, Edit
colors in list boxes, 5-5	Label/Value Pairs dialog box, 2-13
functions accepting RGB color	control attributes. See attributes.
values, 4-10	Control Callbacks command, Generate
generating with MakeColor function,	menu, 2-28
4-146 to 4-147	
	Control command, Edit menu, 2-11 to 2-14.
RGB color values for drawing three-	See also Edit Control dialog box.
dimensional objects, 4-79	Control Coordinates command, Arrange
command button controls	menu, 2-23
definition, 1-11	control functions. See also specific types of
illustration, 1-11	control functions.
operating, 1-11	function reference
commit events	DefaultCtrl, 4-54
control modes for generating, 1-3 to 1-4	DiscardCtrl, 4-61 to 4-62
hot, 1-4	DuplicateCtrl, 4-69 to 4-70
indicator, 1-3	GetActiveCtrl, 4-80
normal, 1-3	GetCtrlAttribute, 4-91 to 4-92
validate, 1-4	GetCtrlBoundingRect, 4-93 to 4-94
definition, 1-2	GetCtrlVal, 4-96 to 4-97
placed in GetUserEvent queue after	NewCtrl, 4-153 to 4-154
being sent to callbacks, 3-92	SetActiveCtrl, 4-221
ConfigurePrinter function, 4-51	SetCtrlAttribute, 4-226 to 4-227

SetCtrlVal, 4-229 to 4-230	Menu Bars command, 2-16
programming overview	Panel command, 2-16
control attributes. See attributes.	CreateMetaFont function, 4-52 to 4-53
functions applicable to all controls,	cursor and mouse functions
3-28 to 3-29	function tree, 4-4
list box and ring control functions,	GetActiveGraphCursor, 4-80 to 4-81
3-29 to 3-30	GetCursorAttribute, 4-97
processing control events, 3-31	GetGlobalMouseState, 4-99 to 4-100
to 3-32	GetGraphCursor, 4-100 to 4-101
text box functions, 3-30 to 3-31	GetGraphCursorIndex, 4-101
Control Settings section, Edit Control dialog	GetMouseCursor, 4-110
box, 2-12	GetRelativeMouseState, 4-118 to 4-119
Control Style command, Edit menu, 2-16	GetWaitCursorState, 4-127
Control ZPlane Order command, Arrange	SetActiveGraphCursor, 4-221 to 4-222
menu, 2-22	SetCursorAttribute, 4-230 to 4-231
controls, 1-7 to 1-21. See also control	SetGraphCursor, 4-233
functions.	SetGraphCursorIndex, 4-234
activating, 1-8	SetMouseCursor, 4-241 to 4-242
assigning callback functions, 1-3	SetWaitCursor, 4-248 to 4-249
assigning constant names, 1-3, 3-3	cursors
attributes. See attributes.	cursor styles for
binary switch, 1-12	ATTR_CROSSHAIR_STYLE
canvas. See canvas controls.	(table), 3-78
command button, 1-11	example program, 5-3
data types, 1-8	keyboard operation
for ATTR_DATA_TYPE, 3-50	cursor selection (table), 1-17 to 1-18
decorations, 1-16	free-form cursors (table), 1-17
definition, 1-7	to 1-18
graph. See graph controls.	snap-to-point cursors (table), 1-17
LED, 1-12	to 1-18
list box, 1-14 to 1-16	mouse operation, 1-18
numeric, 1-8 to 1-9	styles for
picture. See picture controls.	ATTR_CURSOR_POINT_STYLE
processing control events, 3-31 to 3-32	and ATTR_TRACE_POINT_STYLE
ring, 1-13 to 1-14	(table), 3-78 to 3-79
string, 1-9 to 1-10	values and cursor styles for
strip chart. See strip chart controls.	ATTR_MOUSE-CURSOR
text box, 1-10 to 1-11	(table), 3-19
text messages, 1-10	customer communication, xxi, B-1 to B-2
timer. See timer controls.	Cut command, Edit menu, 2-6
toggle button, 1-11 to 1-12	Cut Panel command, Edit menu, 2-6
types of controls, 1-7 to 1-8	CVICALLBACK macro, 3-7
Copy command, Edit menu, 2-6	
Copy Panel command, Edit menu, 2-6	
Create menu. User Interface Editor	

illustration, 2-16

D	conventions used in manual, xx organization of manual, xix-xx
data types	DOSColorToRGB function, 4-67 to 4-68
controls	DOSCompatWindow function, 4-68
valid data types, 1-8	drawing. See canvas controls; canvas
values for ATTR_DATA_TYPE	functions.
attribute (table), 3-50	DuplicateCtrl function, 4-69 to 4-70
	DuplicatePanel function, 4-70 to 4-71
plot arrays, 4-11 to 4-12 decorations, 1-16	Duplicated and function, 1,70 to 1,71
·	
Default Control Events option, Preferences	E
command, 2-30	
Default Panel Events option, Preferences	Edit button, Find UIR Objects dialog
command, 2-30	box, 2-18
DefaultCtrl function, 4-54	Edit Control dialog box
DefaultPanel function, 4-54 to 4-55	Control Settings section, 2-12
Delete command, Edit menu, 2-6	Edit Label/Value Pairs dialog box, 2-12
DeleteAxisItem function, 4-44 to 4-56	to 2-13
DeleteGraphPlot function, 4-56 to 4-57	Quick Edit Window, 2-14
DeleteImage function, 4-58	Source Code Connection, 2-11
DeleteListItem function, 4-58 to 4-59	Edit Label/Value Pairs dialog box
DeleteTextBoxLine function, 4-59	Control Appearance section, 2-13
developing graphical user interfaces (GUI).	illustration, 2-12
See graphical user interface (GUI),	Label Appearance section, 2-13
building.	purpose and use, 2-13
Dimmed field, Edit Menu Bar dialog	Edit menu, User Interface Editor
box, 2-9	
DirSelectPopup function, 4-60	Apply Default Font command, 2-15
DiscardBitmap function, 4-61	Control Command, 2-11 to 2-14
DiscardCtrl function, 4-61 to 4-62	Control Style command, 2-16
DiscardMenu function, 4-62	Copy command, 2-6
DiscardMenuBar function, 4-63	Copy Panel command, 2-6
DiscardMenuItem function, 4-63	Cut command, 2-6
DiscardPanel function, 4-64	Cut Panel command, 2-6
DiscardSubMenu function, 4-64	Delete command, 2-6
DisplayImageFile function, 4-65	illustration, 2-5
DisplayPanel function, 4-66 to 4-67	Menu Bars command, 2-7 to 2-9
DisplayPCXFile function, 4-66	Panel command, 2-9 to 2-11
Distribute Vertical Centers command,	Paste command, 2-6
Arrange menu, 2-22	Redo command, 2-5
Distribution command, Arrange menu, 2-21	Set Default Font command, 2-15
to 2-22	Tab Order command, 2-14 to 2-15
dltd	Undo command, 2-5
control attributes	when commands are enabled (note), 2-5
ATTR_CHECK_RANGE values	Edit Menu Bar dialog box
(table), 3-51	available options, 2-8 to 2-9
documentation	illustration, 2-8

Edit Panel dialog box	event types and information passed to
Panel Attributes section, 2-10	program (table), 3-4
Quick Edit Window section, 2-10	example program, 5-3
to 2-11	GetUserEvent function (event loop) for
Source Code Connection section, 2-9	responding to events, 3-8 to 3-9
Edit Tab Order dialog box, 2-15	diagram of event loop concept, 3-8
Editing tool, 2-1	pseudocode example, 3-8 to 3-9
electronic technical support, B-1 to B-2	GOT_FOCUS event, 1-2
e-mail support, B-2	LEFT_CLICK event, 1-2
EmptyMenu function, 4-71	loops. See event loops.
EmptyMenuBar function, 4-71 to 4-72	precedence of callback functions, 3-91
error conditions, User Interface Library, A-1	to 3-92
to A-6	processing
error reporting, User Interface Library, 4-12	control events, 3-31 to 3-32
event functions	graph and strip chart events, 3-67
GetUserEvent, 3-8 to 3-9, 4-125	to 3-68
ProcessDrawEvents, 3-93, 4-195	menu bar events, 3-22 to 3-23
ProcessSystemEvents, 3-93 to 3-94,	panel events, 3-11
4-195 to 4-196	ProcessSystemEvents function, 3-93
QueueUserEvent, 4-197	to 3-94, 4-195 to 4-196
SetIdleEventRate, 3-92 to 3-93, 4-235	setting idle event rates, 3-92 to 3-93
event loops	swallowing events, 3-92
definition, 1-2	unsafe timer events, 3-86 to 3-87
example program, 5-4 to 5-5	example programs, 5-1 to 5-6
GetUserEvent function for responding to	Exit LabWindows/CVI command, File
events, 3-8 to 3-9	menu, 2-4
processing events	mond, 2
control events, 3-31 to 3-32	
menu bar events, 3-23	F
event-blocking conditions, 3-86	
events	FakeKeystroke function, 3-94, 4-72
callback functions for responding to	fax and telephone technical support, B-2
events, 3-5 to 3-7	faxback support, B-1
avoiding longimp function	File menu, User Interface Editor
(note), 3-7	Add File to Project command, 2-4
diagram of callback function	Close command, 2-4
concept, 3-5	Exit LabWindows/CVI command, 2-4
pseudocode example, 3-6 to 3-7	illustration, 2-3
commit events	New command, 2-4
control modes for generating, 1-3	Open command, 2-4
to 1-4	Print command, 2-4
definition, 1-2	Read Only command, 2-4
placed in GetUserEvent queue after	Save command, 2-4
being sent to callbacks, 3-92	Save All command, 2-4
designing, 1-2	Save As command, 2-4
designing, 1-2	Save Copy As command, 2-4

file select pop-up panel, 1-23 to 1-24	$\mathbf{G}$
FileSelectPopup function, 4-72 to 4-74	
Find button, Find UIR Objects dialog	Generate All Code dialog box, 2-25
box, 2-18	Generate Code dialog box, 2-24
Find Next button, Find UIR Objects dialog	Generate Main Function dialog box, 2-26
box, 2-19	Generate menu, 2-24 to 2-28
Find Prev button, Find UIR Objects dialog	All Callbacks command, 2-27
box, 2-18	All Code command, 2-25 to 2-26
Find UIR Objects command, View menu,	Control Callbacks command, 2-28
2-17 to 2-18	enabled commands (note), 2-24
Find UIR Objects dialog box	Generate Code dialog box, 2-24
Case Sensitive option, 2-18	illustration, 2-24
Edit button, 2-18	Main Function command, 2-26 to 2-27
Find button, 2-18	Menu Callbacks command, 2-28
Find Next button, 2-18	Panel Callback command, 2-28
Find Prev button, 2-18	generating code automatically. See
illustration, 2-17	CodeBuilder.
Regular Expression option, 2-18	generic message pop-up panel, 1-22
search criteria in Search By ring control,	GenericMessagePopup function, 4-77
2-17 to 2-18	to 4-79
Stop button, 2-18	geometric panel attributes, 3-18
Wrap option, 2-18	Get3dBorderColors function, 4-79 to 4-80
fonts	GetActiveCtrl function, 4-80
CreateMetaFont function, 4-52 to 4-53	GetActiveGraphCursor function, 4-80
FontSelectPopup function, 4-74 to 4-77	to 4-81
functions using fonts as input	GetActivePanel function, 4-81
parameters, 4-10	GetAxisItem function, 4-82 to 4-83
metafonts	GetAxisItemLabelLength function, 4-83
included with	to 4-84
LabWindows/CVI, 1-25	GetAxisRange function, 4-84 to 4-85
typefaces native to each	GetAxisScalingMode function, 4-86 to 4-87
platform, 1-25	GetBimapData function, 4-87 to 4-89
panel attributes	GetBitmapFromFile function, 4-89 to 4-90
host fonts, 3-21	GetBitmapInfo function, 4-90 to 4-91
metafonts included with	GetCtrlAttribute function, 4-91 to 4-92
LabWindows/CVI, 3-21	GetCtrlBitmap function, 4-92 to 4-93
platform independent fonts on PCs	GetCtrlBoundingRect function, 4-93 to 4-94
and UNIX, 3-20	GetCtrlDisplayBitmap function, 4-94
platform independent metafonts on	to 4-95
PCs and UNIX, 3-20 to 3-21	GetCtrlIndex function, 4-95 to 4-96
user defined metafonts, 3-21	GetCtrlVal function, 4-96 to 4-97
valid font values (table), 3-20	GetCursorAttribute function, 4-97
setting and applying default fonts, 2-15	GetCVITaskHandle function, 4-98
typefaces native to each platform, 1-25	GetCVIWindowHandle function, 4-98
FontSelectPopup function, 4-74 to 4-77	to 4-99
FTP support, B-2	

GetGlobalMouseState function, 4-99	pseudocode example, 3-8 to 3-9
to 4-100	GetValueFromIndex function, 4-126
GetGraphCursor function, 4-100 to 4-101	GetValueLengthFromIndex function, 4-126
GetGraphCursorIndex function, 4-101	to 4-127
GetImageBits function, 4-102 to 4-104	GetWaitCursorState function, 4-127
GetImageInfo function, 4-105 to 4-106	GOT_FOCUS event, 1-2
GetIndexFromValue function, 4-106	graph control functions
to 4-107	AllocImageBits, 4-14 to 4-15
GetLabelFromIndex function, 4-107	ClearStripChart, 4-47 to 4-48
GetLabelLengthFromIndex function, 4-108	DeleteGraphPlot function, 4-56 to 4-57
GetListItemImage function, 4-108 to 4-109	DeleteImage, 4-58
GetMenuBarAttribute function, 4-109	DisplayImageFile, 4-65
to 4-110	DisplayPCXFile, 4-66
GetMouseCursor function, 4-110	function tree, 4-4
GetNumAxisItems function, 4-111	GetActiveGraphCursor, 4-80 to 4-81
GetNumCheckedItems function, 4-112	GetAxisRange, 4-84 to 4-85
GetNumListItems function, 4-112 to 4-113	GetCursorAttribute, 4-97
GetNumTextBoxLines function, 4-113	GetGraphCursor, 4-100 to 4-101
to 4-114	GetGraphCursorIndex, 4-101
GetPanelAttribute function, 4-114	GetImageBits, 4-102 to 4-104
GetPanelDisplayBitmap function, 4-114	GetImageInfo, 4-105 to 4-106
to 4-116	GetPlotAttribute, 4-116 to 4-117
GetPanelMenuBar function, 4-116	GetTraceAttribute, 4-123 to 4-124
GetPlotAttribute function, 4-116 to 4-117	graph and strip chart controls, 3-66
GetPrintAttribute function, 4-117 to 4-118	to 3-67
GetRelativeMouseState function, 4-118	PlotArc, 4-160 to 4-162
to 4-119	PlotBitMap, 4-162 to 4-163
GetScreenSize function, 4-119	PlotIntensity, 4-163 to 4-166
GetSharedMenuBarEventPanel function,	PlotLine, 4-166 to 4-167
4-119 to 4-120	PlotOval, 4-167 to 4-168
GetSleepPolicy function, 4-120	PlotPoint, 4-169
GetSystemAttribute function, 4-120	PlotPolygon, 4-170 to 4-171
to 4-121	PlotRectangle, 4-171 to 4-172
GetSystemPopupsAttribute function, 4-121	PlotScaledIntensity, 4-173 to 4-176
GetTextBoxLine function, 4-121 to 4-122	PlotStripChart, 4-176 to 4-178
GetTextBoxLineLength function, 4-122	PlotStripChartPoint, 4-178 to 4-179
to 4-123	PlotText, 4-179 to 4-180
GetTextDisplaySize function, 4-123	PlotWaveform, 4-181 to 4-182
GetTraceAttribute function, 4-123 to 4-124	PlotX, 4-183 to 4-184
GetUILErrorString function, 4-124	PlotXY, 4-184 to 4-185
GetUserEvent function. See also event	PlotY, 4-185 to 4-187
loops.	RefreshGraph, 4-210
description, 4-125	ResetTimer, 4-216 to 4-217
purpose, 3-92	ResumeTimerCallbacks, 4-217
responding to events, 3-8 to 3-9	SetActiveGraphCursor, 4-221 to 4-222
diagram of event loop concept, 3-8	SetAxisRange, 4-224 to 4-226

SetCursorAttribute, 4-230 to 4-231	GetPlotAttribute, 4-116 to 4-117
SetGraphCursor, 4-233	PlotArc, 4-160 to 4-162
SetGraphCursorIndex, 4-234	PlotBitMap, 4-162 to 4-163
SetImageBits, 4-236 to 4-238	PlotIntensity, 4-163 to 4-166
SetPlotAttribute, 4-244 to 4-245	PlotLine, 4-166 to 4-167
SetTraceAttribute, 4-247 to 4-248	PlotOval, 4-167 to 4-168
SuspendTimerCallbacks, 4-249	PlotPoint, 4-169
graph controls. See also graph control	PlotPolygon, 4-170 to 4-171
functions.	PlotRectangle, 4-171 to 4-172
attributes	PlotText, 4-179 to 4-180
cursor styles for	PlotWaveform, 4-181 to 4-182
ATTR_CROSSHAIR_STYLE	PlotX, 4-183 to 4-184
(table), 3-78	PlotXY, 4-184 to 4-185
discussion of specific attributes, 3-77	PlotY, 4-185 to 4-187
to 3-80	RefreshGraph, 4-210
line styles for ATTR_LINE_STYLE	SetPlotAttribute, 4-244 to 4-245
(table), 3-80	graph pop-up panel, 1-24
list of attributes (table), 3-68 to 3-77	graphical user interface (GUI)
plot origin, 3-80 to 3-81	building. See graphical user interface
plot styles for ATTR_PLOT_STYLE	(GUI), building.
(table), 3-80	components, 1-1
styles for	decorations, 1-16
ATTR_CURSOR_POINT_STYLE	fonts, 1-25
and	illustration, 1-1
ATTR_TRACE_POINT_STYLE	pop-up panels, 1-21 to 1-24
(table), 3-78 to 3-79	graphical user interface (GUI), building. See
two Y axes, 3-81	also User Interface Editor.
values for ATTR_PLOT_ORIGIN	assigning constant names in User
(table), 3-81	Interface Editor, 3-2 to 3-3
definition, 1-16	bitmap objects, 3-62 to 3-63
example program, 5-3	creating, extracting, or
illustration, 1-16	discarding, 3-62
operating, 1-16 to 1-19	displaying or copying, 3-63
optimizing, 3-82 to 3-85	retrieving image data, 3-63
controlling refresh, 3-83 to 3-84	Windows metafiles, 3-62 to 3-63
example canvas benchmark	canvas controls, 3-53 to 3-59
program, 5-6	attributes, 3-56 to 3-59
memory usage, 3-84 to 3-85	background color, 3-55
speed, 3-82 to 3-84	batch drawing, 3-54
processing events, 3-67 to 3-68	canvas coordinate system, 3-54
zooming and panning on graphs, 1-19	clipping, 3-55
graph cursor functions. See cursor and	functions for drawing on canvas,
mouse functions.	3-53 to 3-54
graph cursors. See cursors.	offscreen bitmap, 3-55
graph plotting and deleting functions	pens, 3-55
DeleteGraphPlot function, 4-56 to 4-57	pixel values, 3-56

control functions	image formats (table), 3-52
for all controls, 3-28 to 3-29	simple picture control, 3-52
list boxes and rings, 3-29 to 3-30	pop-up panels, 3-85 to 3-86
text boxes, 3-30 to 3-31	recompiling program after saving .uir
controlling the interface	file, 3-1
basic methods, 1-2	rect and point structures, 3-59 to 3-61
callback functions, 3-5 to 3-7	comparing or obtaining values, 3-61
GetUserEvent function (event loop),	functions and macros for
3-8 to 3-9	creating, 3-60
User Interface Editor vs.	modifying, 3-60 to 3-61
programmatic method, 3-2	source code connection, 1-3
user interface events, 3-3 to 3-9	special functions
controls	FakeKeystroke, 3-94
attributes, 3-32 to 3-33	InstallMainCallback, 3-92 to 3-93
callback functions, 3-31	PostDeferredCall, 3-94
event loops, 3-31 to 3-32	precedence of callback functions,
processing events, 3-31 to 3-32	3-91 to 3-92
development procedure, 3-1	ProcessSystemEvents, 3-93 to 3-94,
events, 1-2	4-195 to 4-196
callback functions for responding to	QueueUserEvent, 3-94
events, 3-5 to 3-7	QuitUserInterface, 3-94
control modes for generating commit	RunUserInterface, 3-91
events, 1-3 to 1-4	SetIdleEventRate, 3-92 to 3-93
event types and information passed	swallowing events, 3-92
to program (table), 3-4	system attributes, 3-86 to 3-88
GetUserEvent function (event loop)	list of attributes (table), 3-86
for responding to events, 3-8 to 3-9	reporting load failures, 3-87 to 3-88
example program, 5-4	unsafe timer events, 3-86 to 3-87
general guidelines, 3-1	timer controls, 3-63 to 3-65
generating hard copy output	attributes, 3-64 to 3-65
functions, 3-88	operations, 3-65
hard copy attributes, 3-89 to 3-91	timer callbacks, 3-64
graph and strip chart controls	timer control functions, 3-63 to 3-65
attributes, 3-68 to 3-80	GUI. See graphical user interface (GUI).
functions, 3-65 to 3-67	
processing events, 3-67 to 3-68	
menu bars, 1-6 to 1-7	Н
attributes, 3-24 to 3-25	
functions, 3-21 to 3-22	hard copy. See also printing functions.
processing events, 3-22 to 3-23	attributes (table), 3-89
panels	compatible printers, 4-9
attributes (table), 3-12 to 3-16	configuring devices, 4-9 to 4-10
functions, 3-9 to 3-10	discussion of specific attributes, 3-90
processing events, 3-11	to 3-91
picture controls, 3-51 to 3-53	functions for generating, 3-88
attributes, 3-52 to 3-53	limitations with UNIX (note), 3-90

obtaining output, 4-9	InsertSeparator function, 4-132
values for ATTR_COLOR_MODE	InsertTextBoxLine function, 4-132 to 4-133
(table), 3-91	InstallCtrlCallback function, 4-133 to 4-134
header files	InstallMainCallback function, 3-92 to 3-93,
created by saving .uir file in User	4-135 to 4-136
Interface Editor, 1-3	InstallMenuCallback function, 4-136
previewing, 2-19	to 4-137
HidePanel function, 4-128	InstallMenuDimmerCallback function,
hierarchy buttons, Edit Menu Bar dialog	4-137 to 4-138
box, 2-9	InstallPanelCallback function, 4-138
Horizontal Centers option	to 4-139
Alignment command, 2-20	InstallPopup function, 4-139
Distribution command, 2-22	intensity plot sample program, 5-5
Horizontal Compress option, Distribution	IsListItemChecked function, 4-140
command, 2-22	Item field, Edit Menu Bar dialog box, 2-8
Horizontal Gap option, Distribution	
command, 2-22	
host fonts, 3-21	K
hot control mode for commit events	1 10 0 10 1
definition, 1-4	key modifiers. See modifier key.
rules for generation of commit	keyboard input, example program, 5-5
events, 1-4	
hot keys. See shortcut keys.	L
	L
I	Label Appearance section, Edit Label/Value
1	Pairs dialog box, 2-13
IDs for interface objects. See constant	Labeling tool, 2-2
names, assigning.	Label/Value Pairs button, 2-12. See also
images. See picture control functions;	Edit Label/Value Pairs dialog box.
picture controls.	LabWindows for DOS compatibility
immediate action menus, 1-6	functions. See LW DOS compatibility
include files	functions.
include file for User Interface Library	LED controls, 1-12
(userint.h), 4-12	Left Edges option
required for referencing resource IDs	Alignment command, 2-20
and callback functions, 3-2	Distribution command, 2-22
updating by recompiling programs, 3-1	LEFT_CLICK event, 1-2
indicator control mode for commit	Library menu, User Interface Editor, 2-30
events, 1-3	line styles for ATTR_LINE_STYLE
Insert New Item field, Edit Menu Bar dialog	(table), 3-79
box, 2-9	list box control functions
Insert Separator field, Edit Menu Bar dialog	CheckListItem, 4-45 to 4-46
box, 2-9	ClearListCtrl, 4-47
InsertAxisItem function, 4-128 to 4-129	DeleteListItem, 4-58 to 4-59
	Defete Listite III, 7-30 to 7-37
InsertListItem function, 4-130 to 4-131	function tree, 4-3 GetCtrlIndex, 4-95 to 4-96

GetIndexFromValue, 4-106 to 4-107	manual. See documentation.
GetLabelFromIndex, 4-107	memory usage, optimizing, 3-84 to 3-85
GetLabelLengthFromIndex, 4-108	Menu Bar Constant Prefix field, Edit Menu
GetListItemImage, 4-108 to 4-109	Bar dialog box, 2-8
GetNumCheckedItems, 4-112	menu bar functions. See also menu
GetNumListItems, 4-112 to 4-113	functions; menu item functions.
GetValueFromIndex, 4-126	DiscardMenuBar, 4-63
GetValueLengthFromIndex, 4-126	EmptyMenuBar, 4-71 to 4-72
to 4-127	function tree, 4-2
InsertListItem, 4-130 to 4-131	GetMenuBarAttribute, 4-109 to 4-110
IsListItemChecked, 4-140	GetPanelMenuBar, 4-116
list of functions, 3-29 to 3-30	GetSharedMenuBarEventPanel, 4-119
ReplaceListItem, 4-214 to 4-215	to 4-120
SetCtrlIndex, 4-229	LoadMenuBar, 4-140 to 4-141
SetListItemImage, 4-240	LoadMenuBarEx, 4-142 to 4-143
list box controls. See also Edit Label/Value	NewMenuBar, 4-155
Pairs dialog box.	programming graphical user interface
definition, 1-14	(GUI), 3-21 to 3-22
example program, 5-4, 5-5	SetMenuBarAttribute, 4-241 to 4-242
illustration, 1-14	SetPanelMenuBar, 4-243
operating, 1-15 to 1-16	menu bars, 1-6 to 1-7
load failures, reporting, 3-87 to 3-88	assigning constant names
Load From Text Format command, Options	constant prefix for menus, 3-3
menu, 2-34	menu items, 3-3
LoadMenuBar function, 4-140 to 4-141	requirements, 3-3
LoadMenuBarEx function, 4-142 to 4-143	submenus (note), 3-3
LoadPanel function, 4-143 to 4-145	attributes
LoadPanelEx function, 4-145 to 4-146	constants for masking three bit fields
longjmp function, avoiding in callback	(table), 3-28
functions (note), 3-7	menu and menu item attributes
LW DOS compatibility functions	(table), 3-24 to 3-25
ConfigurePrinter, 4-51	modifiers and virtual keys for
DisplayPCXFile, 4-66	shortcut keys (table), 3-26 to 3-27
DOSColorToRGB, 4-67 to 4-68	definition, 1-6
DOSCompatWindow, 4-68	illustration, 1-6
function tree, 4-9	immediate action menus, 1-6
GetUILErrorString, 4-124	operating, 1-6 to 1-7
	processing menu bar events, 3-22 to 3-
	23
M	pull-down menus, 1-6
M. F. C.	Menu Bars command
Main Function command, Generate menu,	Create menu, 2-16
2-26 to 2-27	Edit menu, 2-7 to 2-9
MakeColor function, 4-146 to 4-147	Menu Bars List dialog box. See also Edit
MakePoint function, 4-148	Menu Bar dialog box.
MakeRect function, 4-148 to 4-149	available command buttons, 2-7

illustration, 2-7	mouse state, example program, 5-5
Menu Callbacks command, Generate	Move Backward option, Control ZPlane
menu, 2-28	Order command, 2-22
menu functions. See also menu bar	Move Forward option, Control ZPlane
functions; menu item functions.	Order command, 2-22
DiscardMenu, 4-62	Move to Back option, Control ZPlane Order
DiscardSubMenu, 4-64	command, 2-22
EmptyMenu, 4-71	Move to Front option, Control ZPlane Order
example program, 5-3	command, 2-22
NewMenu, 4-154 to 4-155	MultiFileSelectPopup function, 4-150
NewSubMenu, 4-160	to 4-151
RunPopupMenu, 4-218 to 4-219	
menu item functions. See also menu bar	
functions; menu functions.	N
DiscardMenuItem, 4-63	
InsertSeparator, 4-132	New command, File menu, 2-4
NewMenuItem, 4-156 to 4-158	NewBitmap function, 4-151 to 4-153
message pop-up panel, 1-22	NewCtrl function, 4-153 to 4-154
MessagePopup function, 4-149	NewMenu function, 4-154 to 4-155
metafonts	NewMenuBar function, 4-155
included with	NewMenuItem function, 4-156 to 4-158
LabWindows/CVI, 1-25, 3-21	NewPanel function, 4-159 to 4-160
platform independent fonts on PCs and	NewSubMenu function, 4-160
UNIX, 3-20	Next Panel command, View menu, 2-19
typefaces native to each platform, 1-25	Next Tool command, Options menu, 2-31
user defined metafonts, 3-21	normal control mode for commit events, 1-3
miscellaneous functions	numeric controls
CreateMetaFont, 4-52 to 4-53	definition, 1-8
Get3dBorderColors, 4-79 to 4-80	illustration, 1-8
GetMouseCursor, 4-110	operating, 1-8 to 1-9
GetScreenSize, 4-119	numeric formats for ATTR_FORMAT, 3-51
GetSystemAttribute, 4-120 to 4-121	
GetTextDisplaySize, 4-123	
GetWaitCursorState, 4-127	0
MakeColor, 4-146 to 4-147	
SetMouseCursor, 4-241 to 4-242	offscreen bitmap, 3-55
SetSystemAttribute, 4-226	Open command, File menu, 2-4
SetWaitCursor, 4-248 to 4-249	Operate Visible Panels command, Options
modifier key	menu, 2-31
attribute values, 3-26, 4-157	Operating tool, 2-2
representation in source code, 3-26	optimizing graph controls, 3-82 to 3-85
Modifier Key field, Edit Menu Bar dialog	controlling refresh, 3-83 to 3-84
box, 2-9	example canvas benchmark program, 5-
mouse functions. See cursor and mouse	6
functions.	memory usage, 3-84 to 3-85
mouse operation of cursors, 1-18	speed, 3-82 to 3-84
mouse operation of cursons, 1 10	Options menu

Project window	panels
Track Include File Dependencies	assigning constant prefix, 3-2 to 3-3
command, 3-1	attributes, 3-12 to 3-22
User Interface Editor	color values (table), 3-17 to 3-18
Assign Missing Constants	fonts, 3-20 to 3-21
command, 2-33	frame style values, 3-18
illustration, 2-31	geometric attributes (table), 3-18
Load From Text Format	list of attributes (table), 3-12 to 3-16
command, 2-34	programming considerations, 3-17
Next Tool command, 2-31	to 3-20
Operate Visible Panels	values and cursor styles for
command, 2-31	ATTR_MOUSE-CURSOR
Preferences command, 2-32 to 2-33	(table), 3-19
Save in Text Format command, 2-33	child panel role, 3-11
	copying or cutting, 2-6
	definition, 1-5
P	Edit Panel dialog box, 2-9 to 2-11
	illustration, 1-5
Panel Attributes section, Edit Panel dialog	operating, 1-5 to 1-6
box, 2-10	processing panel events, 3-11
Panel Callback command, Generate	Show/Hide Panels command, View
menu, 2-28	menu, 2-19
Panel command	panning on graphs
Create menu, 2-16	definition, 1-19
Edit menu, 2-9 to 2-11	enabling panning, 1-19
panel functions. See also pop-up panel	Paste command, Edit menu, 2-6
functions.	pen functions
DefaultPanel, 4-54 to 4-55	CanvasDefaultPen, 4-16 to 4-17
DiscardPanel, 4-64	CanvasGetPenPosition, 4-35 to 4-36
DisplayPanel, 4-66 to 4-67	CanvasSetPenPosition, 4-42
DuplicatePanel, 4-70 to 4-71	pens for canvas controls, 3-55
function tree, 4-2	picture control functions
GetActivePanel, 4-81	AllocImageBits, 4-14 to 4-15
GetPanelAttribute, 4-114	DeleteImage, 4-58
HidePanel, 4-128	DisplayImageFile, 4-65
LoadPanel, 4-143 to 4-145	DisplayPCXFile, 4-66
LoadPanelEx, 4-145 to 4-146	function tree, 4-5
NewPanel, 4-159 to 4-160	GetImageBits, 4-102 to 4-104
programming graphical user interface	GetImageInfo, 4-105 to 4-106
(GUI), 3-9 to 3-10	SetImageBits, 4-236 to 4-238
RecallPanelState, 4-198 to 4-199	picture controls, 3-51 to 3-53
SavePanelState, 4-220	attributes, 3-52 to 3-53
SetActivePanel, 4-222	appearance, 3-51
SetPanelAttribute, 4-242	giving picture controls visual
SetPanelPos, 4-243 to 4-244	impact, 3-51
ValidatePanel, 4-250	definition, 1-20

example program, 5-4	InstallPopup, 4-139
image formats (table), 1-20, 3-52	MessagePopup, 4-149
simple picture control, 3-52	MultiFileSelectPopup, 4-150 to 4-151
pixel functions	PromptPopup, 4-196
CanvasGetPixel, 4-36 to 4-37	RemovePopup, 4-212
CanvasGetPixels, 4-37 to 4-39	SetFontPopupDefaults, 4-231 to 4-233
pixel values, canvas controls, 3-56	SetSystemPopupsAttribute, 4-247
plot array data types, 4-11 to 4-12	WaveformGraphPopup, 4-251
plot control functions. See graph control	XGraphPopup, 4-252
functions.	XYGraphPopup, 4-252 to 4-253
plot origin, graph and strip chart controls,	YGraphPopup, 4-253
3-80 to 3-81	pop-up panels, 1-21 to 1-24
plot styles for ATTR_PLOT_STYLE	confirm pop-up panels, 1-23
(table), 3-80	definition, 1-21
PlotArc function, 4-160 to 4-162	example program, 5-3
PlotBitMap function, 4-162 to 4-163	file select pop-up panel, 1-23 to 1-24
PlotIntensity function, 4-163 to 4-166	functions for accessing predefined pop-
PlotLine function, 4-166 to 4-167	up panels, 3-85 to 3-86
PlotOval function, 4-167 to 4-168	generic message pop-up panel, 1-22
PlotPoint function, 4-169	graph pop-up panel, 1-24
PlotPolygon function, 4-170 to 4-171	message pop-up panel, 1-22
PlotRectangle function, 4-171 to 4-172	programming overview, 3-85 to 3-86
PlotScaledIntensity function, 4-173 to 4-176	prompt pop-up panel, 1-22
PlotStripChart function, 4-176 to 4-178	PostDeferredCall function, 4-189 to 4-190
PlotStripChartPoint function, 4-178 to 4-179	precedence of callback functions, 3-91
PlotText function, 4-179 to 4-180	to 3-92
PlotWaveform function, 4-181 to 4-182	Preferences command
PlotX function, 4-183 to 4-184	Code menu, 2-29 to 2-30
PlotXY function, 4-184 to 4-185	Always Append Code to End
PlotY function, 4-185 to 4-187	option, 2-30
point functions. See rect and point functions.	Default Control Events option, 2-30
point structures. See rect and point	Default Panel Events option, 2-30
structures.	Preferences menu (illustration), 2-29
PointEqual function, 4-187	Options menu, 2-31 to 2-34. See also
PointPinnedToRect function, 4-188	User Interface Editor Preferences
PointSet function, 4-188 to 4-189	dialog box.
pop-up menus, User Interface Editor	Preview User Interface Header File
window, 2-2	command, View menu, 2-19
pop-up panel functions	Previous Panel command, View menu, 2-19
ConfirmPopup, 4-51 to 4-52	Print command, File menu, 2-4
DirSelectPopup, 4-60	PrintCtrl function, 4-190 to 4-191
FileSelectPopup function, 4-72 to 4-74	printing functions
FontSelectPopup, 4-74 to 4-77	GetPrintAttribute, 4-117 to 4-118
function tree, 4-6	PrintCtrl, 4-190 to 4-191
GenericMessagePopup, 4-77 to 4-79	PrintPanel, 4-191 to 4-193
GetSystemPopupsAttribute, 4-121	PrintTextBuffer, 4-193 to 4-194

PrintTextFile, 4-194 to 4-195	RectGrow, 4-202 to 4-203
SetPrintAttribute, 4-245	RectIntersection, 4-203 to 4-204
printing hardcopy. See hard copy.	RectMove, 4-204
PrintPanel function, 4-191 to 4-193	RectOffset, 4-204 to 4-205
PrintTextBuffer function, 4-193 to 4-194	RectRight, 4-205
PrintTextFile function, 4-194 to 4-195	RectSameSize, 4-206
ProcessDrawEvents function, 3-93, 4-195	RectSet, 4-206 to 4-207
ProcessSystemEvents function, 3-93 to 3-	RectSetBottom, 4-207
94, 4-195 to 4-196	RectSetCenter, 4-207 to 4-208
program shell, building. See CodeBuilder.	RectSetFromPoints, 4-208
programming examples, 5-1 to 5-6	RectSetRight, 4-208
programming graphical user interfaces. See	RectUnion, 4-209
graphical user interface (GUI), building.	rect and point structures, 3-59 to 3-61
prompt pop-up panel, 1-22	comparing or obtaining values, 3-61
PromptPopup function, 4-196	functions and macros for creating, 3-60
pull-down menus, 1-6	modifying, 3-60 to 3-61
push button controls. See command button	purpose and use, 3-59
controls.	Redo command, Edit menu, 2-5
	refresh rate for graphs, 3-83 to 3-84
	RefreshGraph function, 4-210
Q	RegisterWinMsgCallback function, 4-210
0 11 5 10 1 105	to 4-212
QueueUserEvent function, 4-197	Regular Expression option, Find UIR
Quick Edit Window	Objects dialog box, 2-18
Edit Control dialog box, 2-14	RemovePopup function, 4-212
Edit Panel dialog box, 2-10 to 2-11	ReplaceAxisItem function, 4-213 to 4-214
QuitUserInterface function	ReplaceListItem function, 4-214 to 4-215
definition, 3-94	ReplaceTextBoxLine function, 4-215
description, 4-197 to 4-198	reporting load failures, 3-87 to 3-88
	ResetTextBox function, 4-216
R	ResetTimer function, 4-216 to 4-217
K	resource ID
Read Only command, File menu, 2-4	controls, 2-11
RecallPanelState function, 4-198 to 4-199	menu bar, 2-8
rect and point functions	panels, 2-9
function tree, 4-7 to 4-8	ResumeTimerCallbacks function, 4-217
MakePoint, 4-148	RGB colors. See colors.
MakeRect, 4-148 to 4-149	Right Edges option
PointEqual, 4-187	Alignment command, 2-20
PointPinnedToRect, 4-188	Distribution command, 2-22
PointSet, 4-188 to 4-189	ring controls. See also Edit Label/Value
RectBottom, 4-199	Pairs dialog box.
RectCenter, 4-199 to 4-200	control functions, 3-29 to 3-30
RectContainsRect, 4-200	definition, 1-13
RectEmpty, 4-201 to 4-203	operating, 1-13 to 1-14
RectEqual, 4-202	pop-up format (illustration), 1-13
· · · · · · · · · · · · · · · · · · ·	

Run menu, User Interface Editor, 2-30	SetPanelAttribute function, 4-242
RunPopupMenu function, 4-218 to 4-219	SetPanelMenuBar function, 4-243
RunUserInterface function	SetPanelPos function, 4-243 to 4-244
description, 4-219 to 4-220	SetPlotAttribute function, 4-244 to 4-245
purpose, 3-91	SetPrintAttribute function, 4-245
	SetSleepPolicy function, 4-245 to 4-246
	SetSystemAttibute function, 4-226
$\mathbf{S}$	SetSystemPopupsAttribute function, 4-247
	SetTraceAttribute function, 4-247 to 4-248
sample programs, 5-1 to 5-6	SetWaitCursor function, 4-248 to 4-249
Save command, File menu, 2-4	shells, building. See CodeBuilder.
Save All command, File menu, 2-4	Shortcut Key field, Edit Menu Bar dialog
Save As command, File menu, 2-4	box, 2-9
Save Copy As command, File menu, 2-4	shortcut keys
Save in Text Format command, Options	constant for masking three bit fields
menu, 2-33	(table), 3-28
SavePanelState function, 4-220	functions using shortcut key values as
scale functions. <i>See</i> axis scale functions.	input parameters, 4-11
Set Default Font command, Edit menu, 2-15	producing (example), 4-157
Set Target File command, Code menu, 2-23	values for modifier keys and virtual
to 2-24	keys, 3-26 to 3-27, 4-157 to 4-158
Set Target File dialog box, 2-23 to 2-24	Show/Hide Panels command, View
SetActiveCtrl function, 4-221	menu, 2-19
SetActiveGraphCursor function, 4-221	skeleton code
to 4-222	creating with CodeBuilder, 1-4 to 1-5
SetActivePanel function, 4-222	definition, 2-2
SetAxisRange function, 4-224 to 4-226	function skeletons, 2-26
SetAxisScalingMode function, 4-223	placement in target file, 2-24, 2-26
to 4-224	smoothing graph updating, 3-82
SetCtrlAttribute function, 4-226 to 4-227	Source Code Connection
SetCtrlBitmap function, 4-227 to 4-228	Edit Control dialog box, 2-11
SetCtrlIndex function, 4-229	Edit Panel dialog box, 2-9
SetCtrlVal function, 4-229 to 4-230	source files
SetCursorAttribute function, 4-230 to 4-231	connecting code with graphical user
SetFontPopupDefaults function, 4-231	interface, 1-3
to 4-233	creating with CodeBuilder, 1-4 to 1-5,
SetGraphCursor function, 4-233	2-2 to 2-3
SetGraphCursorIndex function, 4-234	speed, optimizing
SetIdleEventRate function, 3-92	ATTR_SMOOTH_UPDATE, 3-82
to 3-93, 4-235	example canvas benchmark program, 5
SetImageBits function, 4-236 to 4-238	6
SetInputMode function, 4-239	VAL_AUTO_SCALE, 3-82 to 3-83
SetListItemImage function, 4-240	standard I/O example program, 5-3
SetMenuBarAttribute function, 4-241	string controls
to 4-242	definition, 1-9
SetMouseCursor function, 4-241 to 4-242	illustration, 1-9

operating, 1-9 to 1-10	DeleteTextBoxLine, 4-59
strip chart controls	function tree, 4-4
attributes	GetNumTextBoxLines, 4-113 to 4-114
cursor styles for	GetTextBoxLine, 4-121 to 4-122
ATTR_CROSSHAIR_STYLE	GetTextBoxLineLength, 4-122 to 4-123
(table), 3-78	InsertTextBoxLine, 4-132 to 4-133
discussion of specific attributes, 3-77	list of functions, 3-30 to 3-31
to 3-80	ReplaceTextBoxLine, 4-215
line styles for ATTR_LINE_STYLE	ResetTextBox, 4-216
(table), 3-79	text box controls
list of attributes (table), 3-68 to 3-77	definition, 1-10
plot styles for ATTR_PLOT_STYLE	entering text, 1-10 to 1-11
(table), 3-80	example program, 5-4
styles for	illustration, 1-10
ATTR_CURSOR_POINT_STYLE	text format. See ASCII text format.
and	text message controls
ATTR_TRACE_POINT_STYLE	illustration, 1-10
(table), 3-78 to 3-79	purpose and use, 1-10
values for ATTR_PLOT_STYLE	timer control functions
(table), 3-80	function tree, 4-6
definition, 1-20	programming with timer controls, 3-63
example program, 5-3, 5-5	to 3-65
illustration, 1-20	ResetTimer, 4-216 to 4-217
processing events, 3-67 to 3-68	ResumeTimerCallbacks, 4-217
strip chart trace functions	SuspendTimerCallbacks, 4-249
ClearStripChart, 4-47 to 4-48	timer controls
function tree, 4-4 to 4-5	attributes, 3-64 to 3-65
GetTraceAttribute, 4-123 to 4-124	definition, 1-21
list of functions, 3-67	example program, 5-4
PlotStripChart, 4-176 to 4-178	illustration, 1-21
PlotStripChartPoint, 4-178 to 4-179	operations, 3-65
SetTraceAttribute, 4-247 to 4-248	timer callbacks, 3-64
SuspendTimerCallbacks function, 4-249	timer events, unsafe, 3-86 to 3-87
swallowing events, 3-92	toggle button controls
system attributes, 3-86 to 3-88	definition, 1-11
list of attributes (table), 3-86	illustration, 1-11
reporting load failures, 3-87 to 3-88	operating, 1-11 to 1-12
unsafe timer events, 3-86 to 3-87	Top Edges option
	Alignment command, 2-20
T	Distribution command, 2-21
T	trace functions. <i>See</i> strip chart trace functions.
Tab Order command, Edit menu, 2-14 to 2-15	Track include file dependencies option, 3-1
technical support, B-1 to B-2	

text box control functions

$\mathbf{U}$	configuring devices, 4-9 to 4-10
	obtaining output, 4-9
.uir files, 3-1	include file, 4-12
Undo command, Edit menu, 2-5	plot array data types, 4-11 to 4-12
Undo Preferences section, User Interface	reporting errors, 4-12
Editor Preferences dialog box, 2-32	shortcut keys, 4-11
UnRegisterWinMsgCallback	User Interface Library functions
function, 4-229	function panels
unsafe timer events, 3-86 to 3-87	bitmap functions, 4-8
user interface. See graphical user interface	callback functions, 4-1, 4-6 to 4-7
(GUI).	canvas functions, 4-5 to 4-6
user interface, creating. See graphical user	clipboard functions, 4-8
interface (GUI), building.	controls, graphs, and
User Interface Editor	stripcharts, 4-1, 4-3
Arrange menu, 2-20 to 2-23	function classes, 4-1 to 4-2
Code menu, 2-23 to 2-30	LW DOS compatibility, 4-2, 4-9
Create menu, 2-16	menu structures, 4-1, 4-2 to 4-3
Edit menu, 2-5 to 2-16	miscellaneous, 4-2, 4-8
File menu, 2-3 to 2-4	panel functions, 4-1, 4-2
Library menu, 2-30	picture functions, 4-5
Options menu, 2-31 to 2-34	pop-up panels, 4-1, 4-6
Run menu, 2-30	printing, 4-2, 4-7
View menu, 2-17 to 2-19	rectangle and point functions, 4-7
Window menu, 2-31	to 4-8
User Interface Editor Preferences dialog box	timer functions, 4-6
Color Preferences section, 2-32	user interface management, 4-2, 4-7
Constant Name Assignment section,	function reference
2-32 to 2-33	AllocBitmapData, 4-12 to 4-13
illustration, 2-32	AllocImageBits, 4-14 to 4-15
Undo Preferences section, 2-32	CanvasClear, 4-15 to 4-16
User Interface Editor window, 2-1 to 2-3	CanvasDefaultPen, 4-16 to 4-17
Coloring tool, 2-2	CanvasDimRect, 4-17 to 4-18
Editing tool, 2-1	CanvasDrawArc, 4-18 to 4-19
illustration, 2-1	CanvasDrawBitmap, 4-20 to 4-21
Labeling tool, 2-2	CanvasDrawLine, 4-21 to 4-22
Operating tool, 2-2	CanvasDrawLineTo, 4-23
popup menus, 2-2	CanvasDrawOval, 4-24 to 4-25
tool bar, 2-1 to 2-2	CanvasDrawPoint, 4-25
user interface events. See events.	CanvasDrawPoly, 4-26 to 4-27
User Interface Library. See also User	CanvasDrawRect, 4-27 to 4-28
Interface Library functions.	CanvasDrawRoundedRect, 4-28
color support, 4-10	to 4-29
error conditions, A-1 to A-6	CanvasDrawText, 4-30 to 4-31
font support, 4-10	CanvasDrawTextAtPoint, 4-32
hardcopy output	to 4-33
compatible printers, 4-9	CanvasEndBatchDraw, 4-34

CanvasGetClipRect, 4-35 FontSelectPopup, 4-74 to 4-77 CanvasGetPenPosition, 4-35 to 4-36 GenericMessagePopup, 4-77 to 4-79 CanvasGetPixel, 4-36 to 4-37 Get3dBorderColors, 4-79 to 4-80 CanvasGetPixels, 4-37 to 4-39 GetActiveCtrl, 4-80 GetActiveGraphCursor, 4-80 to 4-81 CanvasInvertRect, 4-39 CanvasScroll, 4-40 to 4-41 GetActivePanel, 4-81 CanvasSetClipRect, 4-41 to 4-42 GetAxisItem. 4-82 to 4-83 CanvasStartBatchDraw, 4-43 to 4-44 GetAxisItemLabelLength, 4-83 CanvasUpdate, 4-44 to 4-45 to 4-84 CheckListItem, 4-45 to 4-46 GetAxisRange, 4-84 to 4-85 ClearAxisItems, 4-46 to 4-47 GetAxisScalingMode, 4-86 to 4-87 GetBitInfo, 4-90 to 4-91 ClearListCtrl, 4-47 ClearStripChart, 4-47 to 4-48 GetBitMapData, 4-87 to 4-89 ClipboardGetBitmap, 4-48 to 4-49 GetBitMapFromFile, 4-89 to 4-90 ClipboardGetText, 4-49 GetCtrlAttribute, 4-91 to 4-92 ClipboardPutBitap, 4-49 to 4-50 GetCtrlBitmap, 4-92 to 4-93 ClipboardPutText, 4-50 GetCtrlBoundingRect, 4-93 to 4-94 ConfigurePrinter, 4-51 GetCtrlDisplayBitmap, 4-94 to 4-95 GetCtrlIndex, 4-95 to 4-96 ConfirmPopup, 4-51 to 4-52 CreateMetaFont, 4-52 to 4-53 GetCtrlVal, 4-96 to 4-97 DefaultCtrl, 4-54 GetCursorAttribute, 4-97 GetCVITaskHandle, 4-98 DefaultPanel, 4-54 to 4-55 DeleteAxisItem, 4-55 to 4-56 GetCVIWindowHandle, 4-98 to 4-99 DeleteGraphPlot, 4-56 to 4-57 GetGlobalMouseState, 4-99 to 4-100 DeleteImage, 4-58 GetGraphCursor, 4-100 to 4-101 DeleteListItem, 4-58 to 4-59 GetGraphCursorIndex, 4-101 DeleteTextBoxLine, 4-59 GetImageBits, 4-102 to 4-104 DirSelectPopup, 4-60 GetImageInfo, 4-105 to 4-106 DiscardBitmap, 4-61 GetIndexFromValue, 4-106 to 4-107 DiscardCtrl, 4-61 to 4-62 GetLabelFromIndex, 4-107 DiscardMenu, 4-62 GetLabelLengthFromIndex, 4-108 DiscardMenuBar, 4-63 GetListItemImage, 4-108 to 4-109 GetMenuBarAttribute, 4-109 DiscardMenuItem, 4-63 DiscardPanel, 4-64 to 4-110 DiscardSubMenu, 4-64 GetMouseCursor, 4-110 DisplayImageFile, 4-65 GetNumAxisItems, 4-111 DisplayPanel, 4-66 to 4-67 GetNumCheckedItems, 4-112 DisplayPCXFile, 4-66 GetNumListItems, 4-112 to 4-113 DOSColorToRGB, 4-67 to 4-68 GetNumTextBoxLines, 4-113 to 4-114 DOSCompatWindow, 4-68 GetPanelAttribute, 4-114 DuplicateCtrl, 4-69 to 4-70 DuplicatePanel, 4-70 to 4-71 GetPanelDisplayBitmap, 4-114 EmptyMenu, 4-71 to 4-116 EmptyMenuBar, 4-71 to 4-72 GetPanelMenuBar, 4-116 FakeKeystroke, 3-94, 4-72 GetPlotAttribute, 4-116 to 4-117 FileSelectPopup, 4-72 to 4-74 GetPrintAttribute, 4-117 to 4-118

GetRelativeMouseState, 4-118 NewMenu, 4-154 to 4-155 to 4-119 NewMenuBar, 4-155 GetScreenSize, 4-119 NewMenuItem, 4-156 to 4-158 GetSharedMenuBarEventPanel. NewPanel, 4-159 to 4-160 4-119 to 4-120 NewSubMenu, 4-160 GetSleepPolicy, 4-120 PlotArc, 4-160 to 4-162 PlotBitMap, 4-162 to 4-163 GetSystemAttribute, 4-120 to 4-121 GetSystemPopupsAttribute, 4-121 PlotIntensity, 4-163 to 4-166 GetTextBoxLine, 4-121 to 4-122 PlotLine, 4-166 to 4-167 GetTextBoxLineLength, 4-122 PlotOval, 4-167 to 4-168 to 4-123 PlotPoint, 4-169 GetTextDisplaySize, 4-123 PlotPolygon, 4-170 to 4-171 GetTraceAttribute, 4-123 to 4-124 PlotRectangle, 4-171 to 4-172 GetUILErrorString, 4-124 PlotScaledIntensity, 4-173 to 4-176 GetUserEvent, 3-8 PlotStripChart, 4-176 to 4-178 to 3-9, 3-92, 4-125 PlotStripChartPoint, 4-178 to 4-179 GetValueFromIndex, 4-126 PlotText, 4-179 to 4-180 GetValueLengthFromIndex, 4-126 PlotWaveform, 4-181 to 4-182 to 4-127 PlotX, 4-183 to 4-184 GetWaitCursorState, 4-127 PlotXY, 4-184 to 4-185 HidePanel, 4-128 PlotY, 4-185 to 4-187 InsertAxisItem, 4-128 to 4-129 PointEqual, 4-187 InsertListItem, 4-130 to 4-131 PointPinnedToRect, 4-188 InsertSeparator, 4-132 PointSet, 4-188 to 4-189 InsertTextBoxLine, 4-132 to 4-133 PostDeferredCall, 3-94, 4-189 InstallCtrlCallback, 4-133 to 4-134 to 4-190 InstallMainCallback, 3-92 to 3-93, PrintCtrl, 4-190 to 4-191 4-135 to 4-136 PrintPanel, 4-191 to 4-193 InstallMenuCallback, 4-136 to 4-137 PrintTextBuffer, 4-193 to 4-194 InstallMenuDimmerCallback, 4-137 PrintTextFile, 4-194 to 4-195 to 4-138 ProcessDrawEvents, 3-93, 4-195 InstallPanelCallback, 4-138 to 4-139 ProcessSystemEvents, 3-93 to 3-94, 4-195 to 4-196 InstallPopup, 4-139 IsListItemChecked, 4-140 PromptPopup, 4-196 LoadMenuBar, 4-140 to 4-141 QueueUserEvent, 3-94, 4-197 LoadMenuBarEx, 4-142 to 4-143 QuitUserInterface, 3-94, 4-197 to 4-198 LoadPanel, 4-143 to 4-145 LoadPanelEx, 4-145 to 4-146 RecallPanelState, 4-198 to 4-199 MakeColor, 4-146 to 4-147 RectBottom, 4-199 MakePoint, 4-148 RectCenter, 4-199 to 4-200 MakeRect, 4-148 to 4-149 RectContainsRect, 4-200 MessagePopup, 4-149 RectEmpty, 4-201 to 4-202 MultiFileSelectPopup, 4-150 RectEqual, 4-202 to 4-151 RectGrow, 4-202 to 4-203 NewBitmap, 4-151 to 4-153 RectIntersection, 4-203 to 4-204 NewCtrl, 4-153 to 4-154 RectMove, 4-204

RectOffset, 4-204 to 4-205	SetPanelAttribute, 4-242
RectRight, 4-205	SetPanelMenuBar, 4-243
RectSameSize, 4-206	SetPanelPos, 4-243 to 4-244
RectSet, 4-206 to 4-207	SetPlotAttribute, 4-244 to 4-245
RectSetBottom, 4-207	SetPrintAttribute, 4-245
RectSetCenter, 4-207 to 4-208	SetSleepPolicy, 4-245 to 4-246
RectSetFromPoints, 4-208	SetSystemAttribute, 4-246
RectSetRight, 4-209	SetSystemPopupsAttribute, 4-247
RectUnion, 4-209	SetTraceAttribute, 4-247 to 4-248
RefreshGraph, 4-210	SetWaitCursor, 4-248 to 4-249
RegisterWinMsgCallback, 4-210	SuspendTimerCallbacks, 4-249
to 4-212	UnRegisterWinMsgCallback, 4-229
RemovePopup, 4-212	ValidatePanel, 4-250
ReplaceAxisItem, 4-213 to 4-214	WaveformGraphPopup, 4-251
ReplaceListItem, 4-214 to 4-215	XGraphPopup, 4-252
ReplaceTextBoxLine, 4-215	XYGraphPopup, 4-252 to 4-253
ResetTextBox, 4-216	YGraphPopup, 4-253
ResetTimer, 4-216 to 4-217	user interface management functions
ResumeTimerCallbacks, 4-217	FakeKeystroke, 3-94, 4-72
RunPopupMenu, 4-218 to 4-219	function tree, 4-7
RunUserInterface, 3-01, 4-219	GetSleepPolicy, 4-120
to 4-220	GetUserEvent, 3-92, 4-125
SavePanelState, 4-220	ProcessDrawEvents, 3-93, 4-195
SetActiveCtrl, 4-221	ProcessSystemEvents, 3-93 to 3-94,
SetActiveGraphCursor, 4-221	4-195 to 4-196
to 4-222	QueueUserEvent, 3-94, 4-197
SetActivePanel, 4-222	QuitUserInterface, 3-94, 4-197 to 4-198
SetAxisRange, 4-224 to 4-226	RunUserInterface, 3-01, 4-219 to 4-220
SetAxisScalingMode, 4-223 to 4-224	SetIdleEventRate, 3-92 to 3-93, 4-235
SetCtrlAttribute, 4-226 to 4-227	SetInputMode, 4-239
SetCtrlBitmap, 4-227 to 4-228	SetSleepPolicy, 4-245 to 4-246
SetCtrlIndex, 4-229	user interface objects, finding, 2-17 to 2-18
SetCtrlVal, 4-229 to 4-230	user interface resource (.uir) files, 3-1
SetCursorAttribute, 4-230 to 4-231	
SetFontPopupDefaults, 4-231	
to 4-233	${f V}$
SetGraphCursor, 4-233	
SetGraphCursorIndex, 4-234	VAL_AUTO_SCALE, 3-82 to 3-83
SetIdleEventRate, 3-92	validate control mode for commit events
to 3-93, 4-235	definition, 1-4
SetImageBits, 4-236 to 4-238	requirements, 1-4
SetInputMode, 4-239	ValidatePanel function, 4-250
SetListItemImage, 4-240	Vertical Centers option
SetMenuBarAttribute, 4-241	Alignment command, 2-21
to 4-242	Distribution command, 2-21
SetMouseCursor 4-241 to 4-242	

Vertical Compress option, Distribution command, 2-22	Y
Vertical Gap option, Distribution command, 2-21 View button, Edit Menu Bar dialog box, 2-9 View command, Code menu, 2-28 to 2-29 View menu, User Interface Editor Bring Panel to Front command, 2-19 Find UIR Objects command, 2-17 to 2-18	Y axes autoscaling Y-axis on strip chart, example, 5-5 example programs for left and right Y axes, 5-5 working with two Y axes, 3-81 YGraphPopup function, 4-253
illustration, 2-17	
Next Panel command, 2-19	${f Z}$
Preview User Interface Header File	
command, 2-19	zooming on graphs
Previous Panel command, 2-19	definition, 1-19
Show/Hide Panels command, 2-19	enabling zooming, 1-19
virtual keys	
representation in source code, 3-26 values for shortcut keys, 3-26 to 3-27, 4-157 to 4-158	

#### $\mathbf{W}$

WaveformGraphPopup function, 4-251
Window menu, User Interface Editor, 2-31
windows interrupt support functions
function tree, 4-7
GetCVITaskHandle, 4-98
GetCVIWindowHandle, 4-98 to 4-99
RegisterWinMsgCallback, 4-210
to 4-212
UnRegisterWinMsgCallback, 4-229
Windows metafiles, 3-62 to 3-63
Wrap option, Find UIR Objects dialog
box, 2-18

## $\mathbf{X}$

XGraphPopup function, 4-252 XYGraphPopup function, 4-252 to 4-253